

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
322	(23-BR-2)BR	FAYETTE	19	3
STA. 195+73.21		TO STA. 197+80.79		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNITS	TOTAL	CONSTRUCTION TYPE CODE 20% STATE / 80% FEDERAL	
				ROADWAY	BRIDGE
				I000-2A	X080-2A
28100109	STONE RIP RAP, CLASS A5	SQ YD	384	384	
28200200	FILTER FABRIC	SQ YD	384	384	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	14	14	
40600982	HOT-MIX SURFACE REMOVAL, BUTT JOINT	SQ YD	176	176	
40600990	TEMPORARY RAMP	SY YD	54	54	
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX 'C', N50	TON	16	16	
42001165	BRIDGE APPROACH PAVEMENT	SQ YD	294	294	
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	59	59	
44000100	PAVEMENT REMOVAL	SQ YD	200	200	
44004250	PAVED SHOULDER REMOVAL	SQ YD	190	190	
50101600	REMOVAL OF EXISTING SUPERSTRUCTURES	L SUM	1		1
50102400	CONCRETE REMOVAL	CU YD	6.6		6.6
50300225	CONCRETE STRUCTURES	CU YD	10.3		10.3
50300260	BRIDGE DECK GROOVING	SQ YD	620		620
50300300	PROTECTIVE COAT	SQ YD	944	294	650
50400405	PRECAST PRESTRESSED CONCRETE DECK BEAMS (21" DEPTH)	SQ FT	5827		5827
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	9780		9780
50800515	BAR SPLICERS	EACH	252		252
50901050	STEEL RAILING, TYPE SM	FOOT	270		270
51500100	NAME PLATES	EACH	1		1
52000110	PREFORMED JOINT STRIP SEAL	FOOT	153		153
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	187.5	187.5	
* 63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	4	4	
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1, SPECIAL (TANGENT)	EACH	4	4	
63200305	STEEL PLATE BEAM GUARD RAIL REMOVAL	FOOT	550	550	
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	6	6	

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNITS	TOTAL	CONSTRUCTION TYPE CODE 20% STATE / 80% FEDERAL	
				ROADWAY	BRIDGE
				I000-2A	X080-2A
67100100	MOBILIZATION	L SUM	1	1	
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1	1	
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	10	10	
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1	
70106700	TEMPORARY RUMBLE STRIP	EACH	6	6	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	140	140	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	450	450	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	412.5	412.5	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	412.5	412.5	
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	1212	1212	
* 78200410	GUARD RAIL MARKERS, TYPE A	EACH	12	12	
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4	
78300100	PAVEMENT MARKING REMOVAL	SQ FT	335	335	
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	29		29
X5030305	CONCRETE WEARING SURFACE 5"	SQ YD	650		650
Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	78		78
Z0030265	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, WIDE), TEST LEVEL 2	EACH	2	2	
Z0030320	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 2	EACH	2	2	
Z0037300	PAVEMENT GROOVING	SQ YD	294	294	

*** SPECIALTY ITEMS**

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
 F.A.P. ROUTE 322 (IL 51)
 SECTION (23-BR-2)BR
 FAYETTE COUNTY

SCALE: VERT. NONE
 HORIZ. NONE
 DATE 08/23/07
 DRAWN BY WJS
 CHECKED BY AJD