

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
322	(23-BR-2)BR	FAYETTE	19	5
STA. 195+73.21		TO STA. 197+80.79		
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				

STAGE I CONSTRUCTION SCHEDULE		TEMPORARY RUMBLE STRIP	IMPACT ATTENUATORS, TEMPORARY	TEMPORARY CONCRETE BARRIER	PAVEMENT MARKING REMOVAL
STATION to STATION	SIDE	EACH	EACH	FOOT	SQ FT
170+89.5	RT.	1			
180+89.5	RT.	1			
185+89.5	RT.	1			
192+89.5	200+68.1 CL.				162.7
194+49.5	LT.		1		
194+74.5	195+08.3 LT.			35.7	
195+00.7	198+53.0 RT.				117.3
195+08.3	198+48.3 RT.			341.1	
198+48.3	198+83.1 LT.			35.7	
199+08.1	LT.		1		
207+68.1	LT.	1			
212+68.1	LT.	1			
222+68.1	LT.	1			
TOTAL		6	2	412.5	280.0

MISCELLANEOUS REMOVAL ITEMS			GUARDRAIL REMOVAL	PAVEMENT REMOVAL	PAVED SHOULDER REMOVAL	HMA SURFACE REMOVAL BUTT JOINT
STATION to STATION	SIDE	FOOT	FOOT	SQ YD	SQ YD	SQ YD
194+43.4	196+21.4 RT.	178				
194+92.0	195+96.0 LT.	104				
195+61.2	195+79.2 LT. & RT.					88
195+73.2	196+09.2 LT. & RT.			100	98	
197+32.6	198+97.6 LT.	165				
197+44.8	197+80.8 LT. & RT.			100	92	
197+58.0	198+61.0 RT.	103				
197+74.8	197+92.8 LT. & RT.					88
TOTAL			550	200	190	176

STAGE II CONSTRUCTION SCHEDULE		IMPACT ATTENUATORS, RELOCATE	RELOCATE TEMPORARY CONCRETE BARRIER	PAVEMENT MARKING REMOVAL
STATION to STATION	SIDE	EACH	FOOT	SQ FT
194+49.5	RT.	1		
194+74.5	195+08.3 RT.		35.7	
194+96.2	195+66.4 LT.			23.4
195+08.3	198+48.3 LT.		341.1	
197+73.8	198+67.3 LT.			31.1
198+48.3	198+83.1 RT.		35.7	
199+08.1	RT.	1		
TOTAL		2	412.5	54.5

GUARDRAIL SCHEDULE			TERMINAL MARKER DIRECTLY APPLIED FOOT	TRAFFIC BARRIER TERMINAL, TYPE 1, SPECIAL, (TANGENT) EACH	STEEL PLATE BEAM GUARDRAIL TYPE A FOOT	TRAFFIC BARRIER TERMINAL, TYPE 6A EACH	GUARDRAIL MARKERS, TYPE A EACH
STATION to STATION	SIDE	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT
194+39.9	194+89.9 RT.	1	1				
194+89.5	195+39.5 LT.	1	1				
194+89.9	195+77.4 RT.				87.5		
195+39.5	195+52.0 LT.				12.5		
195+52.0	195+97.2 LT.					1	
195+77.4	196+22.6 RT.					1	
197+31.4	197+76.6 LT.					1	
197+56.8	198+02.0 RT.					1	
197+76.6	198+51.6 LT.				75.0		
198+02.0	198+14.5 RT.				12.5		
198+14.5	198+64.5 RT.	1	1				
198+51.6	199+01.6 LT.	1	1				
194+39.9	198+64.5 RT.						6
194+89.5	199+01.6 LT.						6
TOTAL			4	4	187.5	4	12

PAVEMENT MARKING SCHEDULE			PAINT PAVEMENT MARKING - LINE 4" (YELLOW - SKIP DASH)	PAINT PAVEMENT MARKING - LINE 4" (WHITE - SOLID)	PAINT PAVEMENT MARKING - LINE 4" (YELLOW - DBL. SOLID)	SHORT TERM PAVEMENT MARKING	WORK ZONE PAVEMENT MARKING REMOVAL
STATION TO STATION	SIDE	FOOT	FOOT	FOOT	FOOT	FOOT	SQ FT
192+89.5	199+03.8 CL.	160.0				60	72.6
194+96.2	198+67.3 LT.		371.1			20	130.2
195+00.7	198+53.0 RT.		352.3			20	124.0
199+03.8	200+68.1 CL.			328.6		40	122.7
TOTAL			160.0	723.4	328.6	140	449.5

PAVING SCHEDULE			BITUMINOUS MATERIALS (PRIME COAT)	HOT-MIX ASPHALT SURFACE COURSE MIX "C", N50	TEMPORARY RAMP	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	BRIDGE APPROACH PAVEMENT	PAVEMENT GROOVING	PROTECTIVE COAT
STATION to STATION	SIDE	GAL	TON	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD
195+61.2	195+79.2 LT. & RT.	6.6	7.9	26.7					
195+73.2	195+79.2 LT. & RT.				29.3				
195+79.2	196+09.2 LT. & RT.					146.7	146.7	146.7	
197+44.8	197+74.8 LT. & RT.					146.7	146.7	146.7	
197+74.8	197+80.8 LT. & RT.				29.3				
197+74.8	197+92.8 LT. & RT.	6.6	7.9	26.7					
TOTAL			13.2	15.8	53.4	58.6	293.4	293.4	293.4

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
 F.A.P. ROUTE 322 (IL 51)
 SECTION (23-BR-2)BR
 FAYETTE COUNTY

SCALE: VERT. NONE
 HORIZ. DATE 08/23/07
 DRAWN BY WJS
 CHECKED BY AJD