

SUMMARY OF QUANTITIES

F.A.U. SECTION COUNTY TOTAL SHEETS SHEET NO.	05-00054-00-WR MADISON 110 3
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT	
CONTRACT NO. 07320	

SUMMARY OF QUANTITIES

1000

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY
20200100	EARTH EXCAVATION	CU YD	7627
20800150	TRENCH BACKFILL	CU YD	521
25000100	SEEDING, CLASS 1	ACRE	3.5
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	317
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	317
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	317
25100115	MULCH, METHOD 2	ACRE	7.0
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	350
28000300	TEMPORARY DITCH CHECKS	EACH	31
28000400	PERIMETER EROSION BARRIER	FOOT	986
28000500	INLET AND PIPE PROTECTION	EACH	42
28100707	STONE DUMPED RIPRAP, CLASS A4	SQ YD	118
28200200	FILTER FABRIC	SQ YD	118
30200650	PROCESSING MODIFIED SOIL 12"	SQ YD	8774
30201500	LIME	TON	217
31100300	SUB-BASE GRANULAR MATERIAL, TYPE A 4"	SQ YD	6083
31100700	SUB-BASE GRANULAR MATERIAL, TYPE A 8"	SQ YD	2691
35400500	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 10"	SQ YD	4224
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	400
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	2333
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	3640
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	1960
42001200	PAVEMENT FABRIC	SQ YD	4224
42001300	PROTECTIVE COAT	SQ YD	3837
42301000	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 10 INCH, SPECIAL	SQ YD	2535
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	10551
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	2203
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	311
44004250	PAVED SHOULDER REMOVAL	SQ YD	132

SUMMARY OF QUANTITIES

1000

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY
44201353	CLASS C PATCHES, TYPE II, 10 INCH	SQ YD	26
44201359	CLASS C PATCHES, TYPE IV, 10 INCH	SQ YD	499
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	6800
48101200	AGGREGATE SHOULDERS, TYPE B	TON	33
48203100	HOT-MIX ASPHALT SHOULDERS	TON	606
50105220	PIPE CULVERT REMOVAL	FOOT	1065
54200430	PIPE CULVERTS, TYPE 1 RCCP 15"	FOOT	330
54200433	PIPE CULVERTS, TYPE 1 RCCP 18"	FOOT	237
54200439	PIPE CULVERTS, TYPE 1 RCCP 24"	FOOT	196
54200640	PIPE CULVERTS, TYPE 1, CORRUGATED STEEL OR ALUMINUM CULVERT PIPE 15"	FOOT	40
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	8
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	13
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	7
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	4
54213870	STEEL END SECTIONS 15"	EACH	2
54213873	STEEL END SECTIONS 18"	EACH	1
54214515	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, EQUIVALENT ROUND-SIZE 30"	EACH	1
55019500	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 12"	FOOT	51
55019600	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 15"	FOOT	317
55019700	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 18"	FOOT	41
55034300	STORM SEWERS, TYPE 1, REINFORCED CONCRETE ELLIPTICAL PIPE, SPAN 30, RISE 19	FOOT	148
55034500	STORM SEWERS, TYPE 1, REINFORCED CONCRETE ELLIPTICAL PIPE, SPAN 38, RISE 24	FOOT	306
60223800	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1

SUMMARY OF QUANTITIES

1000

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY
60235700	INLETS, TYPE A, TYPE 3 FRAME AND GRATE	EACH	11
60242900	INLETS, SPECIAL, TYPE 1	EACH	5
60243000	INLETS, SPECIAL, TYPE 2	EACH	5
60243100	INLETS, SPECIAL, TYPE 3	EACH	1
60243700	INLETS, SPECIAL, TYPE 4	EACH	1
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	3906
66410400	CHAIN LINK FENCE TO BE REMOVED AND RE-ERECTED	FOOT	20
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	8
67100100	MOBILIZATION	L SUM	1
70103700	TRAFFIC CONTROL COMPLETE	L SUM	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	732
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	645
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	15639
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	219
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	6321
72000100	SIGN PANEL - TYPE 1	SQ FT	56
72000200	SIGN PANEL - TYPE 2	SQ FT	10
72900100	METAL POST - TYPE A	FOOT	68
72900200	METAL POST - TYPE B	FOOT	108
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	15639
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	65
* 78003100	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LETTERS AND SYMBOLS	SQ FT	645
* 78003150	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 12"	FOOT	154
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	177
X0324767	RUBBLIZE PAVEMENT	SQ YD	2489

BY: _____ DATE: _____
 SURVEYED _____
 PLOTTED _____
 NOTE BOOK TEMPLATE _____
 AREAS CHECKED _____
 NO. _____

BY: _____ DATE: _____
 ORIGINAL SURVEYED _____
 PLOTTED _____
 NOTE BOOK TEMPLATE _____
 AREAS CHECKED _____
 NO. _____

* SPECIALTY ITEMS

Juneau Associates, Inc. P.C. <small>CONSULTING ENGINEERS AND LAND SURVEYORS</small> <small>2100 South Street, P.O. Box 1207 Granite City, Illinois 62040 Phone: (618) 937-4400 / (618) 937-4000 Fax: (618) 937-2541</small>		SUMMARY OF QUANTITIES OLD MADISON ROAD MADISON, ILLINOIS SECTION No. 05-00054-00-WR	
REVISIONS			
NO.	DATE	BY	REMARKS
DSN. BY: BFK		DATE: 06/06/07	SHEET 3
DWN. BY: JJB		DATE: 06/06/07	
CHK'D: BFK		DATE: 06/06/07	
JOB NO. E061003		DRN. NAME: SUMQTY	OF 110 SHTS