


SIDEWALK / DRIVEWAY SCHEDULE							
STATION	STATION	OFFSET	PCC DRIVEWAY PAVT 8 (SQ YD)	PC CONC SIDEWALK 4" (SQ FT)	PC CONC SIDEWALK 4 SPECIAL (SQ FT)	PC CONC SIDEWALK 6" (SQ FT)	DETECTABLE WARNINGS (SQ FT)
SOUTH ILLINOIS STREET (IL 159)							
46+00.1	46+17.2	RT			27		
46+00	46+20	RT		140.3			
46+00	48+04	LT		1822.7			
46+23.7	48+03.4	LT			240		
46+33.1	47+88.1	RT		1118.6	215		
46+37		RT	15.5				
NORTH ILLINOIS STREET (IL 159)							
50+50	51+46	LT			127		
50+50	51+55	LT		762		43.8	16
50+50	51+57.8	RT		841.5	140		
51+72.4	52+41.4	RT		566.8	91	43.8	16
52+04	52+41.4	LT		271.8			
52+11	52+41.4	LT			39		
PUBLIC SQUARE							
SE QUADRANT				7963.9	378	140.4	32
SW QUADRANT				2275.5		156.9	32
NE QUADRANT				7143.9	277	140.4	32
NW QUADRANT				7472.4	277	140.4	32
WEST MAIN STREET							
26+14	28+28.5	LT		1461			
26+14	28+37.7	RT		1675			
26+20.5	27+57.2	LT			182		
26+71	28+35.6	RT			219		
26+85		LT			12		
27+70.6	28+10.8	LT			54		
27+34		LT			12		
27+84		LT			12		
EAST MAIN STREET							
31+13	32+73.9	LT		1784	215		
31+07.4	32+73.9	RT		1644			
31+08.4	33+29.4	RT			296		
31+50		RT			12		
31+50		LT			12		
32+00		RT			12		
32+00		LT			12		
32+50		RT			12		
32+50		LT			12		
TOTAL			15.5	36,943	2,885	666	160

CURB AND GUTTER SCHEDULE					
STATION	STATION	OFFSET	COMB CC&G TY B6.18 (FOOT)	COMB CC&G TY B SPL (FOOT)	CONC CURB (FOOT)
SOUTH ILLINOIS STREET (IL 159)					
46+00	48+04	LT	205.5		
46+00	47+89	RT	189.5		
NORTH ILLINOIS STREET (IL 159)					
50+50	51+55	LT	110		
50+50	52+42.7	RT	190.8		
51+49	51+69	LT	20		
51+91	52+11	LT	20		
52+03.5	52+42.7	LT	43		
PUBLIC SQUARE					
SE QUADRANT			195		113
SW QUADRANT			391.8		
NE QUADRANT			204		245.3
NW QUADRANT			177		113
WEST MAIN STREET					
26+14	28+28.5	LT	214.5	85	
27+04	28+37.7	RT	133.7		
EAST MAIN STREET					
31+25.4	32+73.9	RT		148.5	
31+25.4	32+73.9	LT		148.5	
TOTAL			2,095	382	471

PAVEMENT SCHEDULE															
STATION	STATION	OFFSET	AGGREGATE-TEMP ACCESS (TON)	BIT MATLS PR CT (GALLON)	AGG PR CT ACCESS	HMA SURF REM BUTT JT (SQ YD)	TEMP RAMP (SQ YD)	LEV BIND MM N70 (TON)	HMA SC 'D' N70 (TON)	HMA SURF REM VAR DP (SQ YD)	PVT PATCHING (FD) (SQ YD)	PCC BASE CSE W 8 (SQ YD)	AREA REFLTY CRACK CONTROL TREAT (SQ YD)	CONC MED TSM4.18 (SQ FT)	BIT PAVT IMPRINTING (SQ YD)
SOUTH ILLINOIS STREET (IL 159)															
46+00	47+81.48	RT/LT	10	90	1.8	147	49	32	77	456			888		42
47+94	48+03	RT/LT													
NORTH ILLINOIS STREET (IL 159)															
50+58.39	52+41.70	RT/LT	10	90	1.8	147	49	28	76	488			998		38
50+38	50+45	RT/LT												295	
51+65.5	51+94	LT													
PUBLIC SQUARE															
SE QUADRANT			10	97	1.9			12	84	123			972		
SW QUADRANT			10	97	1.8				76	405			881		
NE QUADRANT			10	88	1.9			15	84	154			970		
NW QUADRANT			10	93	1.9			9	81	131			930		
WEST MAIN STREET															
27+04	28+19.37	RT/LT	20	60	1.2	147	49	19	51	347			584		42
28+33	28+42	RT/LT													
28+50		28' RT									17				
EAST MAIN STREET															
31+28.83	32+75	RT/LT	20	60	1.2	120	40	21	51	375			585		40
30+95	31+04	RT/LT													
31+56	32+25	RT													
TOTAL			100	675	13.5	561	187	136	582	2479	17	76	6708	295	162

*
Remove
* Revised 11-5-07

Kaskaskia Engineering
 Group L.L.C.
 23 Public Square, Suite 404
 Belleville, Illinois 62220
 Office: (618) 235-3877 Fax: (618) 235-3977
 www.kaskaskiaeng.com
 A Disadvantaged Business Enterprise

PREPARED BY: 
 PROFESSIONAL REGISTRATIONS LICENSE NO. 188772
 ILLINOIS PROFESSIONAL ENGINEER REG. NO. 28-080888
 PROFESSIONAL ENGINEERING CORP.

REV	DATE	DESCRIP
△	08/29/2007	FIRST REVIEW
△	09/20/2007	1ST REVISION
△	11/02/2007	ADDENDUM 1

SCHEDULES
 PROJECT TITLE: DOWNTOWN BELLEVILLE STREETSCAPE PH. 2
 CITY OF BELLEVILLE
 ST. CLAIR COUNTY, ILLINOIS

DESIGNED BY: TJM	SHEET
DRAWN BY: CHA/DWK	5
CHECKED BY: TJM	
DATE OF PRELIMINARY: 08/20/2007	
DATE OF FINAL: 09/13/2007	
SHEET NO. 5 OF 48 SHEETS	
PROJECT NUMBER 07-0041	

P:\07-0041 Belleville Square\dwg\07-0041_SCHEDULES.dwg 11/2/2007 10:40:01 AM CDT