F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
885	(107A)B-1	JOHNSON	38	4
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

CONTRACT NO. 98776

SUMMARY OF QUANTITIES

RURAL - JOHNSON COUNTY
HBP FUNDING
80% FEDERAL; 20% STATE
X071-2A
SN 044-0059

CODE NUMBER	ITEM DESCRIPTION	UNIT	QUANTITY
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	2
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1
70106700	TEMPORARY RUMBLE STRIP	EACH	6 △1
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	2
70300100	SHORT - TERM PAVEMENT MARKING	FOOT	116
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	2800
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	972
70400100	TEMPORARY CONCRETE BARRIER	FOOT	425
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	375
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	2800
* 78200405	GUARDRAIL MARKERS	EACH	14
* 78200500	BARRIER WALL MARKERS	EACH	6
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4
78300100	PAVEMENT MARKING REMOVAL	SQ FT	553
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	6
X0321430	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC) SPECIAL	SQ YD	77
X0323988	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	648
X6330103	REMOVE AND RE-ERECT TRAFFIC BARRIER TERMINAL, TYPE 1 SPECIAL, (TANGENT)	EACH	1
X7050167	TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 1, SPECIAL (TANGENT)	EACH	1
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2
X8620020	UNINTERRUPTIBLE POWER SUPPLY	EACH	2

* SPECIALTY ITEMS

△1 Rev. 10-26-07

PLOT DATE = 7/30/2007
FILE NAME = c:\pw_work\PW_35\d35\d044-001\d.dgn
PLOT SCALE = 50.0000 ' / IN.
USER NAME = Mukherjee