

SUMMARY OF QUANTITIES

F.A.P. RTG.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
885	(107A)B-1	JOHNSON	38	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
CONTRACT NO. 98776				

RURAL - JOHNSON COUNTY			
HBP FUNDING			
80% FEDERAL; 20% STATE			
CONSTRUCTION TYPE CODE X071-2A			
SN 044-0059			
CODE NUMBER	ITEM DESCRIPTION	UNIT	QUANTITY
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	2
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	2
20200100	EARTH EXCAVATION	CU YD	95
20300100	CHANNEL EXCAVATION	CU YD	508
20400100	BORROW EXCAVATION	CU YD	1161
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	229
25000350	SEEDING, CLASS 7	ACRE	0.4
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	64
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	48
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	48
25000700	AGRICULTURAL GROUND LIMESTONE	TON	0.8
25001010	SEEDING, CLASS 2 (MODIFIED)	ACRE	0.4
25100115	MULCH, METHOD 2	ACRE	0.6
25100630	EROSION CONTROL BLANKET	SQ YD	1224
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	40
28000400	PERIMETER EROSION BARRIER	FOOT	1152
28100107	STONE RIPRAP, CLASS A4	SQ YD	39
28100109	STONE RIPRAP, CLASS A5	SQ YD	974
28200200	FILTER FABRIC	SQ YD	1013
35600716	HOT-MIX ASPHALT BASE COURSE WIDENING, 10"	SQ YD	288
40600100	<i>BITUMINOUS</i> MATERIALS (PRIME COAT)	GALLON	127
40600300	AGGREGATE (PRIME COAT)	TON	2
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	160
40600990	TEMPORARY RAMP	SQ YD	26
40603090	HOT - MIX ASPHALT BINDER COURSE, IL - 19.0, N90	TON	161
40603320	HOT - MIX ASPHALT SURFACE COURSE, MIX "C", N90	TON	103
42001165	BRIDGE APPROACH PAVEMENT	SQ YD	249
42001300	PROTECTIVE COAT	SQ YD	326
44000100	PAVEMENT REMOVAL	SQ YD	356
44001114	HOT-MIX ASPHALT SURFACE REMOVAL (ASBESTOS)	SQ YD	208
44004250	PAVED SHOULDER REMOVAL	SQ YD	124
48100700	AGGREGATE SHOULDERS, TYPE A, 8"	SQ YD	58
48203029	HOT - MIX ASPHALT SHOULDERS, 8"	SQ YD	566

RURAL - JOHNSON COUNTY			
HBP FUNDING			
80% FEDERAL; 20% STATE			
CONSTRUCTION TYPE CODE X071-2A			
SN 044-0059			
CODE NUMBER	ITEM DESCRIPTION	UNIT	QUANTITY
48203100	HOT - MIX ASPHALT SHOULDERS	TON	34
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1
50200100	STRUCTURE EXCAVATION	CU YD	261
50300100	FLOOR DRAINS	EACH	12
50300225	CONCRETE STRUCTURES	CU YD	29.8
50300255	CONCRETE SUPERSTRUCTURE	CU YD	141.4
50300260	BRIDGE DECK GROOVING	SQ YD	645
50300280	CONCRETE ENCASEMENT	CU YD	5.6
50300300	PROTECTIVE COAT	SQ YD	445
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1
50500505	STUD SHEAR CONNECTORS	EACH	1782
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	33800
50800515	BAR SPLICERS	EACH	421
51201600	FURNISHING STEEL PILES HP12X53	FOOT	632
51202305	DRIVING PILES	FOOT	632
51204650	PILE SHOES	EACH	16
51500100	NAME PLATES	EACH	1
52100520	ANCHOR BOLTS, 1"	EACH	24
54215547	METAL END SECTIONS 12"	EACH	2
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	111
60100945	PIPE DRAINS 12"	FOOT	44
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	128
60900240	TYPE C INLET BOX, STANDARD 609006	EACH	2
60900515	CONCRETE THRUST BLOCKS	EACH	2
* 63000000	STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	375
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1, SPECIAL (TANGENT)	EACH	3
63200310	GUARDRAIL REMOVAL	FOOT	484
66600105	FURNISHING AND ERECTING RIGHT OF WAY MARKERS	EACH	12
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	9
67100100	MOBILIZATION	L SUM	1

* SPECIALTY ITEMS

PLOT DATE = 07/2007
 FILE NAME = c:\pcc\mca\p03003\044-0033.dgn
 PLOT SCALE = 1/8" = 1'-0"
 USER NAME = halstoadx