

URBAN
100% STATE
7025

Pay Item Code No.	Item Description	Unit	Quantity
20101350	TREE PRUNING (OVER 10 INCH DIAMETER)	EACH	1
20200100	EARTH EXCAVATION	CU YD	190
20800150	TRENCH BACKFILL	CU YD	25
21101625	TOPSOIL FURNISH AND PLACE, 6"	SQ YD	339
25000100	SEEDING, CLASS 1	ACRE	0.40
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	32
** 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	32
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	32
25100105	MULCH, METHOD 1	ACRE	0.40
44000100	PAVEMENT REMOVAL	SQ YD	401
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	144
44000600	SIDEWALK REMOVAL	SQ FT	1250
54200640	PIPE CULVERTS, TYPE 1, CORRUGATED STEEL OR ALUMINUM CULVERT PIPE 15"	FOOT	26
54213870	STEEL END SECTIONS 15"	EACH	2
** 56109210	WATER VALVES TO BE ADJUSTED	EACH	1
** 56500400	DOMESTIC METER VAULTS TO BE REMOVED	EACH	1
** 60600095	CLASS S1 CONCRETE (OUTLET)	CU YD	4.5
** 60602400	CONCRETE GUTTER (SPECIAL)	FOOT	141.0
72000100	SIGN PANEL - TYPE 1	SQ FT	4
72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	1
72400500	RELOCATE SIGN PANEL ASSEMBLY - TYPE A	EACH	1
** 72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	24
** 78001100	PAINT PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	9.2
** 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	255
* X0301339	REMOVE EXISTING PARKING BLOCKS	EACH	15
* X0322983	STONE CURB	FOOT	189
* X0701000	WOOD BUMPER BLOCKS	EACH	12
* XX000882	WOOD FENCE	FOOT	405
* XX001758	WOOD FENCE REMOVAL	FOOT	197
* Z0013798	CONSTRUCTION LAYOUT	L SUM	1
* X0325449	SOIL SOLIDIFIED PAVEMENT AND SIDEWALK	SQ YD	923
* Z0027600	GATE, SPECIAL 6'-0"	FOOT	6
* X0325447	GATE, SPECIAL 10'-0"	FOOT	10
* X0325448	GATE, SPECIAL 20'-0"	FOOT	20
B2000768	TREE, AMELANCHIER X GRANDIFLORA AUTUMN BRILLIANCE (AUTUMN BRILLIANCE SERVICE BERRY), 7' HEIGHT, SHRUB FORM, BALLED AND BURLAPPED	EACH	1
* K0030394	PERENNIAL, ACHILLEA MILLEFOLIUM 'PAPRIKA', (PAPRIKA YARROW), 1 GALLON	EACH	18
* X0322852	PERENNIAL, ASTER NOVAE-ANGLIAE 'PURPLE DOME', (PURPLE DOME ASTER), 1 GALLON	EACH	11
* K0030407	PERENNIAL, ALCEA ROSEA 'INDIAN SPRING', (INDIAN SPRING HOLLYHOCK), 1 GALLON	EACH	34
* C2001326	SHRUB, CLETHRA ALNIFOLIA 'HUMMINGBIRD', (HUMMINGBIRD SUMMERSWEET), 18" HEIGHT, BALLED AND BURLAPPED/POT	EACH	14
* K0030409	PERENNIAL, CAMPANULA CARPATICA 'BLUE CLIPS', (BLUE CLIPS CARPATHIAN HAREBELL), 1 QUART	EACH	50
* K0030411	PERENNIAL, ECHINACEA PURPUREA 'MAGNUS', (MAGNUS PURPLE CONEFLOWER), 1 GALLON	EACH	8
* C2003426	SHRUB, HYDRANGEA ARBORESCENS 'ANNABELLE', (ANNABELLE SMOOTH HYDRANGEA), 3 GALLON	EACH	7
* C2015302	SHRUB, JUNIPERUS CHINENSIS 'KALLAY'S COMPACTA', (KALLAY COMPACT JUNIPER), 5 GALLON	EACH	7
** K0030413	PERENNIAL, PHLOX SUBULATA 'BLUE EMERALD', (BLUE EMERALD CREEPING PHLOX), 1 QUART	EACH	29
* XX060319	GRASS, PANICUM VIRGATUM 'HEAVY METAL', (HEAVY METAL SWITCH GRASS), 1 GALLON	EACH	19
* K0030404	PERENNIAL, RUDBECKIA FULGIDA 'GOLDSTURM', (GOLDSTURM BLACK EYED SUSAN), 1 GALLON	EACH	15
* X0325600	GRASS, SPOROBOLUS HETEROLEPIS, (PRAIRIE DROPSEED), 1 GALLON	EACH	13
* C2001328	SHRUB, SYRINGA VULGARIS, (COMMON LILAC), 30" HEIGHT, BALLED AND BURLAPPED	EACH	3
* K0030402	PERENNIAL, TRANSPLANTED DAYLILIES FROM EXISTING FENCE ROW	EACH	22
* K0030405	PERENNIAL, TRANSPLANTED IRISES FROM EXISTING FENCE ROW	EACH	17
* C2001330	SHRUB, THUJA OCCIDENTALIS 'LITTLE GIANT', (LITTLE GIANT ARBORVITAE), 5 GALLON	EACH	8
* C2011936	SHRUB, VIBURNUM DENTATUM RALPH SENIOR (AUTUMN JAZZ ARROWWOOD VIBURNUM), 3' HEIGHT, BALLED AND BURLAPPED	EACH	1
* X0300890	COMPOST PLACEMENT-2"	SQ YD	215
* K1003679	MULCH	CU YD	19
* X0301117	SPADE EDGING	FOOT	115
67100100	MOBILIZATION	L SUM	1
70103100	TRAFFIC CONTROL COMPLETE	L SUM	1

CLASS S1 CONCRETE (OUTLET)	
LOCATION	QUANTITY (CU. YD.)
GUTTER INLET	3.0
GUTTER OUTLET	1.5
TOTAL	4.5

SOIL SOLIDIFIED PAVEMENT AND SIDEWALK	
LOCATION	QUANTITY (SQ. YD.)
DRIVEWAY AND PARKING	742
SIDEWALK	181
TOTAL	923

* SPECIAL PROVISION
** SPECIALTY ITEMS

SIGN SCHEDULE											
ROUTE	STATION	OFFSET	SIGN # MUTCD	SIZE INxIN		SIGN PANEL TYPE 1 SQ. FT.	MESSAGE	# OF POSTS	TELESCOPING STEEL SIGN SUPPORT FOOT	REMOVE SIGN PANEL ASSEMBLY TYPE A	RELOCATE SIGN PANEL ASSEMBLY TYPE A
				W	H						
1ST STREET (BASELINE)	0+59	22' RT	--	--	--	--	EX. HANDICAPPED PARKING	1	--	1	--
	2+86	20' RT	--	--	--	--	RIGHT TURN	1	--	--	1
DRIVEWAY AND PARKING	1+19.7	35' LT	R7-8	12	18	1.5	RESERVED PARKING	1	12	--	--
			R7-1101	12	6	0.5	\$250 FINE	-	--	--	--
	1+19.7	35' RT	R7-8	12	18	1.5	RESERVED PARKING	1	12	--	--
			R7-1101	12	6	0.5	\$250 FINE	-	--	--	--
TOTALS:						4.0		24	1	1	

APPLICATION RATES	
NITROGEN FERTILIZER NUTRIENT	90 LB/ACRE
PHOSPHORUS FERTILIZER NUTRIENT	90 LB/ACRE
POTASSIUM FERTILIZER NUTRIENT	90 LB/ACRE
MULCH METHOD 1	2 TONS/ACRE

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION SUMMARY OF QUANTITIES AND SCHEDULES IDOT / IHPA JARROT MANSION STATE HISTORIC SITE
NAME	DATE	

SCALE: 1:20
DATE: 4-12-06
DRAWN BY: EJR
CHECKED BY: KCM

DISTRICT PROJECT ENGINEER - LANCE KIDD