

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
350	57B-3I	COOK	62	10
STA. 20+23.42		TO STA. 28+00.00		
FED. RD. DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 60440

LOCATION STA. TO STA.		EARTH EXCAVATION (CF)		TOTAL SUITABLE EXCAVATION (CF)		EXCAVATION TO BE USED IN EMBANKMENT (ADJ. FOR SHRINKAGE) 15% (CF)		EMBANKMENT (CF)		EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (CY)	
		STAGE I	STAGE II	STAGE I	STAGE II	STAGE I	STAGE II	STAGE I	STAGE II	STAGE I	STAGE II
20+00	21+00	1439	422	1439	422	1223	359	121	223	41	5
21+00	22+00	1439	422	1439	422	1223	359	1753	2322	-20	-73
22+00	23+00	0	0	0	0	0	0	2420	2532	-90	-94
24+00	25+00	0	0	0	0	0	0	4183	3327	-155	-123
25+00	26+00	30	7	30	7	25	6	5749	5515	-212	-204
26+00	26+90	27	6	27	6	23	5	1459	2164	-53	-80
26+90	27+00	0	0	0	0	0	0	5	22	0	-1
27+00	27+36	0	0	0	0	0	0	0	0	0	0
27+36	27+80	0	0	0	0	0	0	0	0	0	0
TOTALS		2934	858	2934	858	2494	729	15691	16105	-489	-569

	STAGE 1	STAGE 2	TOTAL
EARTH EXCAVATION (CY)	109	32	140
FURNISHED EXCAVATION (CY)	489	569	1058



LISLE, ILLINOIS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: NONE DRAWN BY SPG  
DATE SEPTEMBER 19, 2006 CHECKED BY AAC