

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
533	119R-1-B	MCHENRY	77	65
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT			



EARTHWORK SUMMARY			
STATION TO STATION	UNSUITABLE EXCAVATION* CU YD	EARTH EXCAVATION CU YD	FURNISHED EXCAVATION CU YD
28+50 TO 33+00	544	14	20
33+00 TO 49+00	3,676	793	9,053
49+00 TO 54+00	1,246	3,400	1,627
54+00 TO 66+50	2,713	452	6,824
66+50 TO 67+50	194	114	97
TOTALS	8,373	4,773	14,273

* BASED ON ASSUMED 9 INCH TOPSOIL REMOVAL