

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	X0B1-2A STATE 100%			
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	20	20			
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1	1			
50102400	CONCRETE REMOVAL	CU YD	0.5	0.5			
50300225	CONCRETE STRUCTURES	CU YD	0.5	0.5			
50300255	CONCRETE SUPERSTRUCTURE	CU YD	47	47			
50300260	BRIDGE DECK GROOVING	SQ YD	384	384			
50300300	PROTECTIVE COAT	SQ YD	566	566			
50400405	PRECAST PRESTRESSED CONCRETE DECK BEAMS (21" DEPTH)	SQ FT	4476	4476			
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	12030	12030			
50900105	ALUMINUM RAILING, TYPE L	FOOT	170	170			
51500100	NAME PLATES	EACH	1	1			
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	1	1			
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	25	25			
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	2	2			
63200310	GUARDRAIL REMOVAL	FOOT	127	127			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	1	1			
67100100	MOBILIZATION	L SUM	1	1			
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD T01321	EACH	1	1			
70102550	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	EACH	1	1			
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	1	1			
70300500	PAVEMENT MARKING TAPE, TYPE III	FOOT	2100	2100			
70400500	TEMPORARY CONCRETE BARRIER (STATE OWNED)	FOOT	190	190			
* 70000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	36.4	36.4			
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	1900	1900			
* 70000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	160	160			

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	X0B1-2A STATE 100%			
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	110	110			
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	356	356			
* 78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	30	30			
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	4	4			
78300105	PAVEMENT MARKING REMOVAL	FOOT	3270	3270			
X5030305	CONCRETE WEARING SURFACE, 5"	SQ YD	521	521			
XX001306	SIDEWALK REMOVAL AND REPLACEMENT	SQ FT	560	560			
* XX006128	TRAFFIC BARRIER TERMINAL TYPE 1 (SPECIAL)	EACH	2	2			
Z0002600	BAR SPLICERS	EACH	91	91			
Z0005215	BITUMINOUS STABILIZATION 6" AT STEEL PLATE BEAM GUARD RAIL	SQ YD	17	17			
Z0015550	DEBRIS REMOVAL	CU YD	30	30			
* Z0030240	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 2	EACH	2	2			
70101800	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	1			
70300520	PAVEMENT MARKING TAPE, TYPE III, 4"	FOOT	640	640			
70300570	PAVEMENT MARKING TAPE, TYPE III, 24"	FOOT	36	36			
70400100	TEMPORARY CONCRETE BARRIER	FOOT	110	110			
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	110	110			
89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	1	1			

* SPECIALTY ITEMS
 ■ SFTY-3N
 ▲ Rev. 10-23-06
 ▲ Rev. 11-2-06

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SUMMARY OF QUANTITIES