

SCHEDULE OF QUANTITIES

CONTRACT NO. 61526			
F.A.P. RYE	SECTION	COUNTY	TOTAL SHEETS
T42	3TRS-6	OGLE	69 14
STA. TO STA.		FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT	

44000600 SIDEWALK REMOVAL

SQ. FT.	LOCATION
	<u>IL 2</u>
4956.00	Lt 566+00 TO 570+31
120.00	Lt 566+56
35.00	Lt 566+82
86.00	Lt 567+09
67.00	Lt 567+68
55.00	Lt 568+96
46.00	Lt 569+44
97.00	Lt 569+61
71.00	Lt 570+05
20.00	Rt 574+90
	<u>IL 64</u>
3123.0	Rt 1034+99 TO 1037+37
30.0	Rt 1036+37
25.0	Rt 1037+20
TOTAL	8731.0

60255500 MANHOLES TO BE ADJUSTED

EACH	LOCATION	OFFSET
	<u>IL 2</u>	
1.0	Sta 565+79	0'
1.0	Rt 565+91	26'
1.0	Lt 565+93	38'
1.0	Rt 566+13	18'
1.0	Rt 570+38	44'
1.0	Sta 570+55	0'
1.0	Lt 570+76	40'
1.0	Lt 570+85	21'
1.0	Rt 571+02	18'
1.0	Lt 574+93	21'
1.0	Rt 575+31	1'
1.0	Rt 575+38	35'
1.0	Lt 575+39	22'
1.0	Lt 580+00	35'
1.0	Rt 580+09	44'
1.0	Sta 580+13	0'
1.0	Sta 580+18	0'
1.0	Sta 584+92	0'
1.0	Lt 585+07	37'
1.0	Rt 585+09	31'
1.0	Rt 585+14	2'
1.0	Rt 589+36	18'
1.0	Lt 589+54	45'
1.0	Sta 589+69	0'
1.0	Lt 589+79	21'
1.0	Rt 589+80	39'
1.0	Rt 589+90	27'
1.0	Lt 596+70	37'
1.0	Lt 603+40	15'
	<u>IL 64</u>	
1.0	Lt 1035+92	25'
SUB-TOTAL	30	
5	60255800 - MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LTD (DETERMINED BY RE)	
SUB-TOTAL	25	

60500060 REMOVING INLETS

EACH	LOCATION
	<u>IL 2</u>
1.00	Lt 570+11 25' LEFT
TOTAL	1.0

60605000 COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24

EQOI	LOCATION
	<u>IL 2</u>
456.00	Lt 565+99 TO 570+31
	<u>IL 64</u>
238.0	Rt 1034+99 TO 1037+37
TOTAL	694.0

78000100 THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS

SQ. FT.	LOCATION	REMARKS
	<u>IL 2</u>	
32.3	Rt 563+53	SCHOOL
21.6	Rt 563+93	X-ING
21.6	Lt 567+60	X-ING
32.2	Lt 568+10	SCHOOL
15.6	Lt/Rt 568+30.56	Left turn arrow
15.6	Lt/Rt 568+95.78	Left turn arrow
15.6	Lt/Rt 569+63.46	Left turn arrow
15.6	Lt/Rt 571+40.25	Left turn arrow
15.6	Lt/Rt 572+08.11	Left turn arrow
15.6	Lt/Rt 572+81.06	Left turn arrow
	<u>IL 64</u>	
15.6	Lt/Rt 1034+82.64	Left turn arrow
15.6	Lt/Rt 1036+10.83	Left turn arrow
15.6	Lt/Rt 1036+91.32	Left turn arrow
15.6	Lt/Rt 1038+72.56	Left turn arrow
15.6	Lt/Rt 1038+44.07	Left turn arrow
15.6	Lt/Rt 1040+78.20	Left turn arrow
TOTAL	294.9	

56400300 FIRE HYDRANT TO BE ADJUSTED

EACH	LOCATION
	<u>IL 64</u>
1.00	Rt 1037+31 29' RIGHT
TOTAL	1.0

60242400 INLETS, SPECIAL

EACH	LOCATION
	<u>IL 2</u>
1.00	Lt 570+11 25' LEFT
TOTAL	1.0

60260100 INLETS TO BE ADJUSTED

EACH	LOCATION
	<u>IL 2</u>
1.00	Lt 566+04 29' LEFT
1.00	Lt 566+21 26' LEFT
1.00	Lt 570+30 45' LEFT
1.00	Rt 575+04 30' LEFT SE Quadrant of IL 2 and Franklin Street
TOTAL	4.0

PLOT DATE: Wed Aug 09 14:05:05 2006
 FILE NAME: c:\pwworkspace\115488.dwg
 PLOT SCALE: 1/8" = 1'-0"
 USER: nbc

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
SCALE: VERT. _____ HORIZ. _____		DRAWN BY _____ CHECKED BY _____

SCHEDULE OF QUANTITIES