

# SCHEDULE OF QUANTITIES

F.A.P. SECTION COUNTY TOTAL SHEETS SHEET NO.
742 3TR5-6 OGLE 69 15
STA. TO STA.
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT

78000200 THERMOPLASTIC PAVEMENT MARKING - LINE 4"

FOOT	LOCATION	REMARKS
<u>IL 2</u>		
1017.0	Lt/Rt 566+17.63 TO 569+75.40	Median Yellow
48.0	Rt 566+38.65 TO 569+57.65	Parking Lane "T" White
26.0	Lt 567+06.50 TO 568+98.08	Parking Lane "T" White
1016.0	Lt/Rt 571+33.68 TO 574+91.06	Median Yellow
48.0	Lt 571+31.25 TO 574+71.25	Parking Lane "T" White
11.0	Rt 572+45.77 TO 572+89.77	Parking Lane "T" White
11.0	Rt 573+43.17 TO 573+93.17	Parking Lane "T" White
11.0	Rt 581+13.42 TO 581+78.43	Parking Lane "T" White
11.0	Rt 582+38.60 TO 583+03.60	Parking Lane "T" White
<u>IL 64</u>		
446.0	Lt/Rt 1034+77.82 TO 1036+98.82	Median Yellow
26.0	Rt 1035+04.68 TO 1036+88.22	Parking Lane "T" White
15.0	Lt 1035+67.77 TO 1036+57.77	Parking Lane "T" White
452.0	Lt/Rt 1038+62.09 TO 1040+85.97	Median Yellow
33.0	Lt 1038+64.73 TO 1040+79.74	Parking Lane "T" White
19.0	Rt 1039+16.52 TO 1040+56.52	Parking Lane "T" White
TOTAL	3190	

78000400 THERMOPLASTIC PAVEMENT MARKING - LINE 6"

FOOT	LOCATION	REMARKS
<u>IL 2</u>		
96.5	Lt/Rt 565+39.50 TO 565+46.50	Cross Walk White
98.0	Lt 565+51.46 TO 566+03.16	Cross Walk White
96.0	Rt 565+51.44 TO 566+01.41	Cross Walk White
111.0	Lt/Rt 566+10.26 TO 566+17.26	Cross Walk White
122.0	Lt/Rt 570+20.17 TO 570+27.17	Cross Walk White
113.0	Lt 570+26.33 TO 570+82.50	Cross Walk White
117.0	Rt 570+26.02 TO 570+85.71	Cross Walk White
122.0	Lt/Rt 570+82.55 TO 570+89.58	Cross Walk White
112.0	Lt/Rt 574+91.38 TO 574+98.38	Cross Walk White
98.0	Lt 575+06.39 TO 575+58.36	Cross Walk White
91.0	Rt 575+06.23 TO 575+54.03	Cross Walk White
83.0	Lt/Rt 575+64.50 TO 575+71.50	Cross Walk White
TOTAL	1260	

78000500 THERMOPLASTIC PAVEMENT MARKING - LINE 8"

FOOT	LOCATION	REMARKS
<u>IL 2</u>		
32.0	Lt 566+20.10 TO 567+06.50	Median White
95.0	Rt 566+18.05 TO 566+38.66	Median White
28.0	Rt 567+37.86 TO 568+21.72	Turn Lane Skip Dash White
168.0	Rt 568+21.72 TO 569+89.46	Turn Lane White
72.0	Lt 568+98.08 TO 569+62.03	Median White
60.0	Rt 569+57.66 TO 570+08.12	Median White
45.0	Lt 570+94.49 TO 571+31.25	Median White
169.0	Lt 571+18.79 TO 572+87.65	Turn Lane White
28.0	Lt 572+87.65 TO 573+71.51	Turn Lane Skip Dash White
54.0	Rt 574+49.51 TO 574+91.93	Median White
29.0	Lt 574+71.25 TO 574+91.46	Median White
56.0	Rt 580+67.40 TO 581+13.43	Median White
103.0	Rt 583+64.21 TO 584+56.36	Median White
<u>IL 64</u>		
81.0	Rt 1034+52.36 TO 1034+98.22	Median White
25.0	Lt 1034+77.82 TO 1035+02.77	Turn Lane White
32.0	Lt 1035+02.77 TO 1036+00.00	Turn Lane Skip Dash White
32.0	Rt 1035+02.82 TO 1035+98.82	Turn Lane Skip Dash White
118.0	Rt 1035+98.82 TO 1037+16.03	Turn Lane White
73.0	Lt 1036+57.77 TO 1037+20.49	Median White
52.0	Rt 1036+88.22 TO 1037+31.23	Median White
45.0	Lt 1038+28.97 TO 1038+64.73	Median White
93.0	Rt 1038+32.86 TO 1039+16.52	Median White
100.0	Lt 1038+51.04 TO 1039+51.02	Turn Lane White
32.0	Lt 1039+51.02 TO 1040+47.03	Turn Lane Skip Dash White
32.0	Rt 1039+51.10 TO 1040+47.03	Turn Lane Skip Dash White
37.0	Rt 1040+47.03 TO 1040+83.97	Turn Lane White
42.0	Rt 1040+56.52 TO 1040+87.30	Median White
TOTAL	1733	

PLT DATE = Wed Aug 05 14:25:42 2009  
 FILE NAME = c:\pwork\msh\105489\105489.dgn  
 USER NAME = jregan

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCALE: VERT. _____ HORIZ. _____ DATE _____
DRAWN BY _____		CHECKED BY _____