

F.A.P. RITE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
742	3TR5-6	OGLE	69	18
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

BITUMINOUS SCHEDULE

STATIONING	REMARKS	LENGTH	PROPOSED SURFACE		BIT. PRIME TON	AGG. PRIME TON	BIT SURF REM 2 1/4' SQ. YD.	LEVELING BIND. (MACH.) METHOD TON	BIT CONC SURF CSE SUPERPAVED MIX 'D' N50 TON	SHORT-TERM PAVT MARKING FOOT	WORK ZONE PAVT MARKING REMOVAL SQ. FT.	TEMP RAMP SQ. YD.
			WIDTH	SG. YD.								
IL 2 (Fourth St) MAINLINE												
565+14 - 566+18	30' to 55' Width	104	42.5	491.1	0.28	0.74	491.1	27.5	41.3	41.6	3.5	44.4
566+18 - 575+0		882	55	5390.0	3.08	8.09	5390.0	301.8	452.8	352.8	29.4	
575+0 - 575+92	55' to 30' Width	92	42.5	434.4	0.25	0.65	434.4	24.3	36.5	36.8	3.1	
575+92 - 579+55		363	30	1210.0	0.69	1.82	1210.0	67.8	101.6	145.2	12.1	
579+55 - 580+68	30' to 38' Width	113	34	426.9	0.24	0.64	426.9	23.9	35.9	45.2	3.8	
580+68 - 584+36		368	38	1553.8	0.89	2.33	1553.8	87.0	130.5	147.2	12.3	
584+36 - 585+46	38' to 30' Width	110	34	415.6	0.24	0.62	415.6	23.3	34.9	44.0	3.7	
585+46 - 598+0		1254	30	4180.0	2.39	6.27	4180.0	234.1	351.1	501.6	41.8	
598+0 - 600+0	30' to 28' Width	200	29	644.4	0.37	0.97	644.4	36.1	54.1	80.0	6.7	
600+0 - 603+0		300	28	933.3	0.53	1.40	933.3	52.3	78.4	120.0	10.0	
603+0 - 604+9	28' to 26' Width	109	27	327.0	0.19	0.49	327.0	18.3	27.5	43.6	3.6	
	SIDE ROADS	VAR	VAR	2345.0	0.67					204.0	22.0	
IL 64 (Washington St) MAINLINE												
1035+4 - 1037+55		251	55	1533.9	0.88	2.30	1533.9	85.9	128.8	100.4	8.4	81.5
1038+8 - 1040+76		268	55	1637.8	0.94	2.46	1637.8	91.7	137.6	107.2	8.9	81.5
TOTALS				21523.22	11.64	28.77	19178.22	1073.98	1610.97	1969.60	169.12	207.41

PLOT DATE * Wed Aug 09 14:05:03 2006
 FILE NAME * D:\pvc\mca\p215\037\dlc\64626\m.dgn
 PLOT SCALE * 0.010000 / 1"
 USER NAME * pvcuser

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCALE: VERT. HORIZ. DATE DRAWN BY CHECKED BY