

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
203	11BR-1	WHITESIDE	43	7
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

20100110

TREE REMOVAL (6 TO 15 UNITS DIA.)	
LOCATION	UNIT
STA 430+14.50, 32' RT.	6
TOTAL	6

28000400

PERIMETER EROSION BARRIER	
LOCATION	FOOT
STA 425+00 TO STA 427+75, LT.	275
STA 425+00 TO STA 427+50, RT.	250
STA 428+75 TO STA 432+00, LT.	325
STA 428+75 TO STA 430+25, RT.	150
TOTAL	1000

EARTHWORK QUANTITIES				
LOCATION	THEORETICAL		SHORTAGE (-) OR EXCESS (+)	REMARKS
	CUT	FILL		
	CU YD	CU YD	CU YD	
			[(A)0.75]-(B)	
	(A)	(B)	(C)	
STA 423+75.00 TO STA 427+69.86	19	254	-240	MOLINE ROAD
STA 428+71.74 TO STA 432+25.00	32	368	-344	
STA 427+09, 38' LT.	0	38	-38	FIELD ENTRANCE
STA 435+00, 73.5' LT.	0	292	-292	FIELD ENTRANCE
TOTAL	51	952	-914	
	PAY ITEM		PAY ITEM	
	20200100		20400800	

28000500

INLET AND PIPE PROTECTION	
LOCATION	FOOT
STA 429+50, LT.	1
TOTAL	1

20300100

CHANNEL EXCAVATION	
LOCATION	CU YD
STA 427+70.43 TO STA 428+71.17	26
TOTAL	26

28000250

TEMPORARY EROSION CONTROL SEEDING	
LOCATION	POUND
STA 423+75 TO STA 427+58.60, RT.	35
STA 423+75 TO STA 427+83, LT.	30
STA 428+58.59 TO STA 432+25, RT.	45
STA 428+83 TO STA 432+25, LT.	35
TOTAL	145

25000750

MOWING	
LOCATION	ACRE
STA 423+75 TO STA 427+58.6, RT	0.1
STA 423+75 TO STA 428+82.2, LT	0.3
STA 428+53.3 TO STA 432+25.0, RT	0.1
STA 428+83.0 TO STA 432+25.0, LT	0.4
TOTAL	0.9

28000300

TEMPORARY DITCH CHECK	
LOCATION	EACH
STA 427+00, RT	1
TOTAL	1

PAVEMENT SCHEDULE													
LOCATION (STA TO STA)	SQ YD	TON	SQ YD	FOOT	TON	SQ YD	TON	TON	TON	SQ YD	SQ YD	SQ YD	SQ YD
STA 423+75 TO STA 427+60.23, RT.					128								
STA 423+75 TO STA 427+81.12, LT.					90								
STA 423+75 TO STA 426+05.16				461			75		94				
STA 423+75 TO STA 424+72		280											
STA 426+05.16 TO STA 427+40.43	298					6				391	436		
STA 428+60.49 TO STA 432+25, RT.					108								
STA 428+81.37 TO STA 432+25, LT.					121								
STA 429+01.17 TO STA 430+05.40	230					8				301	336		
STA 430+05.40 TO STA 432+25				439			71		79				
STA 431+05 TO STA 432+25			347										
STA 435+00 LT (FIELD ENTRANCE)		64											
STA 427+09 LT (FIELD ENTRANCE)		22											
AS DIRECTED BY THE ENGINEER					100			100	3				
STA 426+05.16 TO STA 427+77.5													498
STA 428+64.3 TO STA 430+05.40													407
TOTAL	528	86	627	900	547	14	246	3	173	692	772	905	

PLOT DATE = 8/4/86  
 FILE NAME = 203003SCHD  
 PLOT SCALE = NONE  
 USER NAME = CHENG

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF  
 QUANTITIES  
 FAS 203 (MOLINE ROAD)  
 SECTION 11BR-1  
 WHITESIDE COUNTY  
 SCALE: VERT.      DRAWN BY ARR  
           HORIZ.      CHECKED BY JKC  
 DATE: 12/05