

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
203	11BR-1	WHITESIDE	43	8
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

BRIDGE APPROACH PAVEMENT SCHEDULE			
LOCATION (STA TO STA)	42001165 BRIDGE APPROACH PAVEMENT		50300300 PROTECTIVE COAT
	SQ	YD	
STA 427+40.43 TO STA 427+70.43	111	111	
STA 428+71.17 TO STA 429+01.17	111	111	
TOTAL	222	222	

63000000 STEEL PLATE BEAM GUARD RAIL, TYPE A	
LOCATION	FOOT
STA 425+55.30 TO STA 427+30.30, RT.	175
STA 428+92.30 TO STA 429+79.80, RT.	87.5
STA 429+11.30 TO STA 430+61.30, LT.	150
TOTAL	412.5

63200310 GUARDRAIL REMOVAL	
LOCATION	FOOT
STA 426+70 TO STA 427+60, RT.	90
STA 427+68 TO STA 427+89, LT.	37
STA 428+62 TO STA 429+62, RT.	90
STA 428+83 TO STA 428+95, LT.	24
TOTAL	241

78201000

78201000 TERMINAL MARKER - DIRECT APPLIED	
LOCATION	EACH
AT EACH TYPE 1 TERMINAL	3
TOTAL	3

63000130 STEEL PLATE BEAM GUARD RAIL, TYPE A, (SPECIAL)	
LOCATION	FOOT
STA 427+29.13, LT	37.5
TOTAL	37.5

63500105 DELINEATORS	
LOCATION	EACH
STA 425+05.35, RT.	1
STA 430+29.8, RT.	1
STA 431+11.3, LT.	1
TOTAL	3

78200000 TREE REPLACEMENT SCHEDULE					
CODE NO.	SCIENTIFIC NAME	COMMON NAME	SIZE	UNIT	QUANTITY
A2007814	TILIA AMERICANA	AMERICAN LINDEN/BRASSWOOD	1-34"	EACH	6
TOTAL					

(SEE GENERAL NOTE 33 ON SHEET 2)

44000700 APPROACH SLAB REMOVAL	
LOCATION	SQ YD
STA 427+77.50 TO STA 427+97.40	57
STA 428+44.40 TO STA 428+64.30	57
TOTAL	114

63100045 TRAFFIC BARRIER TERMINAL, TYPE 2	
LOCATION	EACH
STA 427+29.13, LT.	1
TOTAL	1

78200000 PAINT PAVEMENT MARKING - LINE 4"		
LOCATION	78001110	
	4" YELLOW FOOT	4" WHITE FOOT
STA 423+75 TO STA 432+25 2 APPLICATIONS	420	3400
TOTAL	3820	

542D0220 PIPE CULVERTS, CLASS D, TY 1, 15"	
LOCATION	FOOT
LT. STA. 435+00 (FIELD ENTRANCE)	76
LT. STA. 429+11 (FIELD ENTRANCE) *	68
TOTAL	144

63100085 TRAFFIC BARRIER TERMINAL, TYPE 6	
LOCATION	EACH
STA 427+30.30 TO STA 427+60.95, RT.	1
STA 427+49.30 TO STA 427+79.91, LT.	1
STA 428+61.69 TO STA 428+92.30, RT.	1
STA 428+80.65 TO STA 429+11.30, LT.	1
TOTAL	4

78200410 GUARDRAIL MARKERS, TYPE A	
LOCATION	EACH
STA 425+05.3 TO STA 430+29.8, RT	10
STA 427+29.13 TO STA 431+11.26, LT	6
TOTAL	16

54213450 END SECTIONS, 15"	
LOCATION	EACH
LT. STA. 435+00 (FIELD ENTRANCE)	2
LT. STA. 429+11 (FIELD ENTRANCE) *	1
TOTAL	3

63100167 TRAFFIC BARRIER TERMINAL TYPE 1 SPECIAL (TANGENT)	
LOCATION	EACH
STA 425+55.30, RT.	1
STA 429+79.80, RT.	1
TOTAL	2

78200520 BARRIER WALL MARKERS, TYPE B *	
LOCATION	EACH
BRIDGE	4
TOTAL	4

* MARKERS SHALL BE BIDIRECTIONAL SILVER/SILVER

60801015 FLAP GATE, 15"	
LOCATION	EACH
STA 428+82, LT	1
TOTAL	1

63100189 TRAFFIC BARRIER TERMINAL TYPE 1 SPECIAL (FLARED)	
LOCATION	EACH
STA 430+61.3	1
TOTAL	1

* PROVISIONAL PAY ITEM SHOULD THE ENGINEER DETERMINE THE CULVERT AT THIS LOCATION IS NOT OPERATION PROPERLY.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF
QUANTITIES
FAS 203 (MOLINE ROAD)
SECTION 11BR-1
WHITESIDE COUNTY

SCALE: VERT.
HORIZ.
DATE: 12/05

DRAWN BY ARR
CHECKED BY JKC