

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
67	U-BR	LA SALLE	38	3
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

ACF ACBRF

← 80% FED 20% STATE →

ROADWAY SN 050-0243 EX SN 050-0030

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT	TOTAL QNTY	I000	X080-2A	
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	33	33	0	
20100210	TREE QUERCUS BICOLOR (SWAMP WHITE OAK), 2" CALIPER, BALLED AND BURLAPPED	EACH	6	6	0	
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	18	18	0	
20101000	TEMPORARY FENCE	FOOT	350	350	0	
20200100	EARTH EXCAVATION	CU YD	268	268	0	
20300100	CHANNEL EXCAVATION	CU YD	162	162	0	
20400800	FURNISHED EXCAVATION	CU YD	84	84	0	
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	78	0	78	
* 25000200	SEEDING, CLASS 2	ACRE	0.5	0.5	0	
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	31	31	0	
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	31	31	0	
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	31	31	0	
* 25100115	MULCH, METHOD 2	ACRE	0.2	0.2	0	
* 25100630	EROSION CONTROL BLANKET	SQ YD	947	947	0	
28000300	TEMPORARY DITCH CHECKS	EACH	8	8	0	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	34	34	0	
28000400	PERIMETER EROSION BARRIER	FOOT	550	550	0	
28100107	STONE RIPRAP, CLASS A4	SQ YD	234	0	234	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GAL	156.1	156.1	0	
40600300	AGGREGATE (PRIME COAT)	TON	3.9	3.9	0	
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	189	189	0	
40600990	TEMPORARY RAMP	SQ YD	204	204	0	
42001165	BRIDGE APPROACH PAVEMENT	SQ YD	213	213	0	
42001300	PROTECTIVE COAT	SQ YD	365	0	365	
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	43	43	0	
44000100	PAVEMENT REMOVAL	SQ YD	249	249	0	
44000710	BITUMINOUS BASE COURSE REMOVAL	SQ YD	353	353	0	
44001430	BITUMINOUS SHOULDER REMOVAL	SQ YD	126	126	0	
44000030	BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	564	564	0	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	18	18	0	
48202000	BITUMINOUS SHOULDERS SUPERPAVE	TON	15	15	0	
48202600	BITUMINOUS SHOULDERS SUPERPAVE 8"	SQ YD	577	577	0	
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1	0	1	
50200100	STRUCTURE EXCAVATION	CU YD	140	0	140	
50300100	FLOOR DRAINS	EACH	12	0	12	
50300225	CONCRETE STRUCTURES	CU YD	56.9	0	56.9	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	202.5	0	202.5	
50300260	BRIDGE DECK GROOVING	SQ YD	273	0	273	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	48800	0	48800	
51201400	FURNISHING STEEL PILES HP10X42	FOOT	198	0	198	

* SPECIALTY ITEM
 Δ REVISED 10/16/06

PLOT DATE = 05/20/2006
 FILE NAME = \\s\...
 PLOT SCALE = 50.0000 / 1"
 USER NAME = DFC

COOMBE-BLOXDORF P.C.
 Engineers / Land Surveyors
 Springfield, Illinois
 Design Firm License No. 184-002703

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
 IL ROUTE 71 OVER UNNAMED STREAM
 FAP RT 67, SECTION U-BR
 LA SALLE COUNTY

SCALE: DATE: 01/13/06

DRAWN BY: CHECKED BY: