CONTRACT NO. 66586

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
39	(50-4B)BR	LASALLE	365	3
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES

CODE NO.	CONSTRUCTION CODE TYPE: ITEM	UNIT	URBAN 80% FED 20% STATE TOTAL QUANTITY	J000 RDWY	Y030-1E LIGHTING	X971-5B BRIDGE
20101000	TEMPORARY FENCE	FOOT	800	800		
42001165	BRIDGE APPROACH PAVEMENT	SQ YD	532	532		
42001300	PROTECTIVE COAT	SQ YD	75,225			75,225
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SQ YD	1,244	1244		
44000700	APPROACH SLAB REMOVAL	SQ YD	1,776	1776		
50102400	CONCRETE REMOVAL	CU YD	36			36
50104800	REMOVAL OF EXISTING CONCRETE DECK	L SUM	1			1
50300100	FLOOR DRAINS	EACH	600			600
50300225	CONCRETE STRUCTURES	CU YD	53			53
50300255	CONCRETE SUPERSTRUCTURE	CU YD	20,336			20,336
50300260	BRIDGE DECK GROOVING	SQ YD	59,821			59,821
50300310	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	10			10
50300320	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	260			260
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1			1
50500505	STUD SHEAR CONNECTORS	EACH	56,116			56,116
50500715	JACK AND REMOVE EXISTING BEARINGS	EACH	270			270
50600300	CLEANING AND PAINTING STEEL BRIDGE	L SUM	1			1
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	4,802,200			4,802,200
51500100	NAME PLATES	EACH	2			2
58700200	BRIDGE SEAT SEALER	SQ FT	8,074			8,074
59000100	EPOXY CRACK SEALING	FOOT	88			88
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	~~475~~	475		
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4		
* 63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	2	2		
63801200	MODULAR GLARE SCREEN SYSTEM	FOOT	3,940	3940		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	19	19		
67100100	MOBILIZATION	L SUM	1	1		
70100410	TRAFFIC CONTROL AND PROTECTION, STANDARD 701416	EACH	1	1		
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	2	2		
70103816	TRAFFIC CONTROL SURVEILLANCE	CAL MO	14	14		
70300625	TEMPORARY PAINT PAVEMENT MARKING LINE 4"	FOOT	137,424	137,424		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	32,402	32402		
70400100	TEMPORARY CONCRETE BARRIER	FOOT	19,513	19513		
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	19,513	19513		
70400600	RELOCATE TEMPORARY CONCRETE BARRIER (STATE OWNED)	FOOT	2,925	2925		
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	540	540		
* 78100300	REPLACEMENT REFLECTOR	EACH	550	550		
* 78200405	GUARDRAIL MARKERS	EACH	10	10		
78200500	BARRIER WALL MARKERS	EACH	576	576		
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	2	2		
78300505	PAINT PAVEMENT MARKING REMOVAL	FOOT	16,297	16297		
* 80400100	ELECTRIC SERVICE INSTALLATION	EACH	1		1	
* 80500200	SERVICE INSTALLATION, TYPE B	EACH	1	1		
* 80801500	WOOD POLE, 25 FT., CLASS 5	EACH	1	1		
* 81012600	CONDUIT IN TRENCH, 2" DIA., PVC	FOOT	208	133	75	
* 81021330	CONDUIT PUSHED, 2" DIA., PVC	FOOT	55		55	
* 81100600	CONDUIT ATTACHED TO STRUCTURE, 2" DIA., GALVANIZED STEEL	FOOT	133		133	
* 81200230	CONDUIT EMBEDDED IN STRUCTURE, 2" DIA., PVC	FOOT	23,030		23030	
* 81302600	JUNCTION BOX, NON-METALLIC, EMBEDDED IN STRUCTURE, 18" X 12" X 8"	EACH	68		68	
* 81400400	CONCRETE HANDHOLE	EACH	1	1		
* 81500200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	208	133	75	
* 81702140	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 4	FOOT	80,426	14,400	66,026	
* 81702180	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 3/0	FOOT	316		316	
* 82102250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT	EACH	54		54	
* 82500560	LIGHTING CONTROLLER TYPE CB-RCS 200AMP - 480VOLT	EACH	1		1	
* 83003200	LIGHT POLE, ALUMINUM, 45 FT. M.H., 6 FT. DAVIT ARM	EACH	14		14	
* 84200500	REMOVAL OF EXISTING LIGHTING UNIT, SALVAGE	EACH	50		50	
* 84500110	REMOVAL OF LIGHTING CONTROLLER	EACH	1		1	
* 84500120	REMOVAL OF ELECTRIC SERVICE INSTALLATION	EACH	1		1	
* 84500130	REMOVAL OF LIGHTING CONTROLLER FOUNDATION	EACH	1		1	
~~* 87160140~~	~~FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, 12F~~	~~FOOT~~	~~7,200~~	~~7200~~		
~~* 87301005~~	~~ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6-2 C~~	~~FOOT~~	~~1,200~~	~~1200~~		
* 87800200	CONCRETE FOUNDATION, TYPE D	FOOT	4	4		

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. HORIZ.

DATE

DRAWN BY

CHECKED BY

9/1/2006 12:09:52 PM
c:\projects\ed0505\details.dgn