

SUMMARY OF QUANTITIES				80% FEB 2015 ST	50% ST 501 CITY
CODE NO.	ITEM	CONSTRUCTION TYPE CODE		80% FEB 2015 ST	50% ST 501 CITY
		UNIT	TOTAL QUANTITY	X-028-2A SN 050-0238	SFTY-1B
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	23	23	
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	36	36	
20100500	TREE REMOVAL, ACRES	ACRE	0.12	0.12	
20400800	FURNISHED EXCAVATION	CU YD	501	501	
* 25000300	SEEDING, CLASS 3	ACRE	0.40	0.40	
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	36	36	
* 25000500	PHOSPHOROUS FERTILIZER NUTRIENT	POUND	36	36	
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	36	36	
* 25100115	MULCH METHOD 2	ACRE	0.40	0.40	
* 25100630	EROSION CONTROL BLANKET	SQ YD	2,360	2,360	
* 28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	40	40	
28000300	TEMPORARY DITCH CHECKS	EACH	2	2	
28000400	PERIMETER EROSION BARRIER	FOOT	633	633	
28100101	STONE RIPRAP CLASS A1	SQ YD	5	5	
28200200	FILTER FABRIC	SQ YD	5	5	
X032574	THREE-SIDED PRECAST CONCRETE STRUCTURE 32' X 9'	FOOT	44	44	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	84	84	
40600300	AGGREGATE (PRIME COAT)	TON	2	2	
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	0.40	0.40	
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	237.8	237.8	
40600990	TEMPORARY RAMP	SQ YD	26	26	
40800040	INCIDENTAL BITUMINOUS SURFACE	TON	56	56	
42001165	BRIDGE APPROACH PAVEMENT	SQ YD	288.9	288.9	
42001300	PROTECTIVE COAT	SQ YD	443	443	
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	46.7	46.7	
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	78	78	
42400100	PORTLAND CEMENT CONCRETE SIDEWALK, 4"	SQ FT	1,589	1,589	
44000100	PAVEMENT REMOVAL	SQ YD	313	313	
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	266	266	
44000500	COMBINATION CURB & GUTTER REMOVAL	FOOT	886	886	
44000600	SIDEWALK REMOVAL	SQ FT	151	151	
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1	1	
50105200	REMOVE EXISTING CULVERTS	EACH	1	1	
50200100	STRUCTURE EXCAVATION	CU YD	180	180	
50200400	ROCK EXCAVATION FOR STRUCTURES	CU YD	26.4	26.4	
50300225	CONCRETE STRUCTURES	CU YD	74.7	74.7	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	11.2	11.2	
50300260	BRIDGE DECK GROOVING	SQ YD	133	133	
50300300	PROTECTIVE COAT	SQ YD	181	181	
50301100	CONCRETE WEARING SURFACE	CU YD	58.2	58.2	
50800105	REINFORCEMENT BARS	POUND	3,600	3,600	
50800205	REINFORCEMENT BARS (EPOXY COATED)	POUND	6,770	6,770	
* 50900805	PEDESTRIAN RAILING	FOOT	35	35	

SUMMARY OF QUANTITIES				80% FEB 2015 ST	50% FEB 2015 ST
CODE NO.	ITEM	CONSTRUCTION TYPE CODE		80% FEB 2015 ST	50% FEB 2015 ST
		UNIT	TOTAL QUANTITY	X-028-2A SN 050-0238	SFTY-3N
* 50901001	STEEL BRIDGE RAILING	FOOT	35	35	
51500100	NAME PLATES	EACH	1	1	
54200217	PIPE CULVERTS, CLASS D, TYPE 1, 12"	FOOT	46	46	
54200220	PIPE CULVERTS, CLASS D, TYPE 1, 15"	FOOT	42	42	
54213447	END SECTION, 12"	EACH	2	2	
54213450	END SECTION, 15"	EACH	2	2	
X6020074	INLETS, TYPE A, TYPE 3V FRAME AND GRATE	EACH	2	2	
60255500	MANHOLES TO BE ADJUSTED	EACH	2	2	
60605100	COMBINATION CONCRETE CURB & GUTTER, TYPE B-6.24, (ABUTTING EXISTING PAVEMENT)	FOOT	886	886	
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	2	2	
* 63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	2	2	
63200310	GUARDRAIL REMOVAL	FOOT	228	228	
67000400	ENGINEERS FIELD OFFICE, TYPE A	CAL MD	8	8	
67100100	MOBILIZATION	L SUM	1	1	
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1	1	
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1	
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1	
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1	
* 70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1	
70300100	SHORT TERM PAVEMENT MARKING	FOOT	83	83	
70300220	TEMPORARY PAVEMENT MARKING-LINE 4"	FOOT	1,660	1,660	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	14	14	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	192	192	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	192	192	
* 78001110	PAINT PAVEMENT MARKING-LINE 4"	FOOT	1,660	1,660	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	6	6	
* 78200405	GUARDRAIL MARKERS	EACH	8	8	
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	6	6	
* X0323988	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	388	388	
X4066416	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N70	TON	91	91	
X4066740	LEVELING BINDER (HAND METHOD), SUPERPAVE N70	TON	0.66	0.66	
X4066770	LEVELING BINDER (MACHINE METHOD), SUPERPAVE N70	TON	225	225	
* X6310190	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED), MODIFIED	EACH	1	1	
* X6310195	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT), MODIFIED	EACH	3	3	
Z0002600	BAR SPLICERS	EACH	140	140	
* Z0030255	IMPACT ATTENUATORS TEMPORARY, (FULLY REDIRECTIVE NARROW), TEST LEVEL 2	EACH	2	2	
* Z0030240	IMPACT ATTENUATORS TEMPORARY, (NON-REDIRECTIVE), TEST LEVEL 2	EACH	2	2	
* Z0030320	IMPACT ATTENUATORS RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 2	EACH	2	2	
* Z0030340	IMPACT ATTENUATORS RELOCATE (NON-REDIRECTIVE), TEST LEVEL 2	EACH	2	2	

A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1279	(P-10)BR	SALLE	34	3
STA. N/A	TO ST. N/A	FED. ROAD DIST. PROJECT		

CONTRACT NO. 66661

REVISION	DATE
NAME	DATE

* SPECIALTY ITEMS

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. NONE
HORIZ. NONE
DATE: AUGUST 4, 2

DRAWN BY: _____
CHECKED BY: _____