

SUMMARY OF QUANTITIES

PAY ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	SUBTOTAL HANCOCK COUNTY	ROADWAY	STRUCTURE	STRUCTURES	ROADWAY	LIGHTING
						SN 034-2007 IL 336 EB & WB OVER TRIBUTARY OF EAST FORK LA MOINE RIVER	SN 034-0511 EB SN 034-0512 WB IL 336 OVER EAST FORK LA MOINE RIVER		
					80% FEDERAL 20% STATE RURAL HANCOCK CO	80% FEDERAL 20% STATE RURAL HANCOCK CO	80% FEDERAL 20% STATE RURAL HANCOCK CO	80% FEDERAL 20% STATE RURAL McDONOUGH CO	80% FEDERAL 20% STATE RURAL McDONOUGH CO
					CONSTRUCTION TYPE CODE				
					I000-2A	X028-2A	X081-2A	I000-2A	Y030-1E
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	1703	166	166			1537	
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	1887	120	120			1767	
20100500	TREE REMOVAL, ACRES	ACRE	10.00	1.25	1.25			8.75	
20200100	EARTH EXCAVATION	CU YD	570670	66365	66365			504305	
20200200	ROCK EXCAVATION	CU YD	177965	1960	1960			176005	
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	939	939	208	731			
20600110	GRANULAR EMBANKMENT, SPECIAL	TON	3483	713	713			2770	
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	405	405			405		
21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	33855	5920	5920			27935	
21301052	EXPLORATION TRENCH 52" DEPTH	FOOT	32500	7500	7500			25000	
* 25000210	SEEDING, CLASS 2A	ACRE	36.75	5.50	5.50			31.25	
* 25000312	SEEDING, CLASS 4A	ACRE	45.75	8.25	8.25			37.50	
* 25000322	SEEDING, CLASS 5A	ACRE	45.75	8.25	8.25			37.50	
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	7425	1238	1238			6187	
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	7425	1238	1238			6187	
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	7425	1238	1238			6187	
* 25100105	MULCH, METHOD 1	ACRE	100.00	25.00	25.00			75.00	
* 25100115	MULCH, METHOD 2	ACRE	82.50	13.75	13.75			68.75	
25100630	EROSION CONTROL BLANKET	SQ YD	35249	4237	4237			31012	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	20000	5000	5000			15000	
28000300	TEMPORARY DITCH CHECKS	EACH	229	52	52			177	
28000400	PERIMETER EROSION BARRIER	FOOT	3170	2085	2085			1085	
28000500	INLET AND PIPE PROTECTION	EACH	47	7	7			40	
28001000	AGGREGATE (EROSION CONTROL)	TON	4.8	3.6	3.6			1.2	
28100109	STONE RIPRAP, CLASS A5	SQ YD	5334	5334			5334		
28100205	STONE RIPRAP, CLASS A3	TON	1009	351.2	351.2			657.8	
28100207	STONE RIPRAP, CLASS A4	TON	438.4	305.7	305.7			132.7	
28100209	STONE RIPRAP, CLASS A5	TON	3012.2	3012.2	3012.2				
28100225	STONE RIPRAP, CLASS B3	TON	9995.1	153.2	153.2			9841.9	
28101700	RIPRAP, SPECIAL	TON	274.1	68.2	68.2			205.9	
28200200	FILTER FABRIC	SQ YD	24838	10900	5258		5642	13938	
28300400	AGGREGATE DITCH	TON	120.1					120.1	
28500100	FABRIC FORMED CONCRETE REVETMENT MAT	SQ YD	1033.3	1033.3	1033.3				
30200650	PROCESSING MODIFIED SOIL 12"	SQ YD	138054	36649	36649			101405	
30201050	PROCESSING MODIFIED SOIL 20"	SQ YD	4821					4821	

* SPECIALTY ITEM

* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
SHEET 1 OF 8

SCALE: VERT. N/A
HORIZ. N/A
DATE 11/7/05

DRAWN BY BDS
CHECKED BY SRD