

EROSION CONTROL BLANKET																	
LOCATION STATION TO STATION	SIDE	BLANKET DIMENSIONS			EROSION CONTROL BLANKET SQ YD	LOCATION STATION TO STATION	SIDE	BLANKET DIMENSIONS			EROSION CONTROL BLANKET SQ YD						
		LENGTH	WIDTH*	SQ YD				LENGTH	WIDTH*	SQ YD							
		FOOT	FOOT					FOOT	FOOT								
HANCOCK COUNTY					STA 32+00.00 TO STA 48+00.00					RT	1600.00	20.00	3556				
IL 336					STA 72+95.00 TO STA 74+00.00					RT	105.00	10.00	117				
STA 1409+75.00 TO STA 1415+36.00					RT	561.00	10.00	623	STA 76+00.00 TO STA 80+85.00					RT	485.00	12.00	647
STA 1410+00.00 TO STA 1414+00.00					LT	400.00	18.00	800	STA 80+85.00 TO STA 83+00.00					RT	215.00	14.00	334
STA 1414+00.00 TO STA 1415+23.45					LT	123.45	10.00	137	STA 81+26.18 TO STA 83+00.00					LT	173.82	12.00	232
STA 1416+42.00 TO STA 1420+00.00					RT	358.00	10.00	398	STA 117+00.00 TO STA 123+00.00					LT	600.00	14.00	906
STA 1416+80.00 TO STA 1417+00.00					LT	20.00	10.00	22	TR 257								
STA 1420+00.00 TO STA 1424+00.00					RT	400.00	8.00	356	STA 301+80.00 TO STA 302+50.00					LT	70.00	4.00	31
STA 1433+29.28 TO STA 1434+00.00					LT	70.72	12.00	94	FR 02								
STA 1434+25.00 TO STA 1438+75.00					LT	450.00	12.00	600	STA 204+26.00 TO STA 204+76.00					RT	50.00	8.00	44
STA 1439+25.00 TO STA 1440+00.00					LT	75.00	8.00	67	STA 204+76.00 TO STA 206+77.00					RT	201.00	10.00	223
STA 1441+00.00 TO STA 1441+75.00					LT	75.00	8.00	67	FR 03								
STA 1441+00.00 TO STA 1442+88.62					MEDIAN	188.62	10.00	210	STA 604+17.00 TO STA 604+75.00					LT	58.00	4.00	26
STA 1442+00.00 TO STA 1442+88.62					LT	VARIABLE	VARIABLE	469	TR 64								
STA 1442+00.00 TO STA 1442+88.62					RT	VARIABLE	VARIABLE	394	STA 696+75.00 TO STA 698+88.35					RT	213.35	14.00	332
SUBTOTAL HANCOCK COUNTY								4237	FRONTAGE ROAD 2 DRIVEWAY								
MCDONOUGH COUNTY									STA 10+00.00 TO STA 13+80.00					LT	VARIABLE	VARIABLE	5491
IL 336									SUBTOTAL MCDONOUGH COUNTY								31012
STA 1442+88.62 TO STA 1444+00.00					LT	VARIABLE	VARIABLE	719	PROJECT TOTAL								35249
STA 1442+88.62 TO STA 1444+00.00					RT	VARIABLE	VARIABLE	347									
STA 1442+88.62 TO STA 1449+00.00					MEDIAN	611.38	10.00	679									
STA 1449+00.00 TO STA 12+27.00					MEDIAN	1469.35	12.00	1959									
STA 2+50.00 TO STA 15+00.00					LT	VARIABLE	VARIABLE	11478									
STA 12+27.00 TO STA 21+60.00					MEDIAN	933.00	10.00	1037									
STA 12+30.00 TO STA 14+75.00					RT	245.00	20.00	544									
STA 23+00.00 TO STA 30+00.00					RT	700.00	16.00	1244									
STA 23+00.00 TO STA 31+00.00					MEDIAN	800.00	10.00	889									
STA 31+00.00 TO STA 32+00.00					RT	100.00	16.00	178									

* WIDTH INCLUDES DITCH BOTTOM AND SLOPES

PERIMETER EROSION BARRIER			
LOCATION STATION TO STATION	SIDE	PERIMETER EROSION BARRIER FOOT	
HANCOCK COUNTY			
IL 336			
STA 1400+50.00 TO STA 1409+29.76	RT	896	
STA 1405+25.00 TO STA 1407+00.00	LT	178	
STA 1408+00.00 TO STA 1409+28.08	LT	136	
STA 1428+00.00 TO STA 1430+00.00	LT	206	
STA 1429+15.18 TO STA 1431+59.78	RT	265	
STA 1436+00.00 TO STA 1438+42.00	RT	218	
STA 1441+00.00 TO STA 1443+00.00	RT	186	
SUBTOTAL HANCOCK COUNTY			2085
MCDONOUGH COUNTY			
IL 336			
STA 12+00.00 TO STA 15+58.75	RT	382	
STA 106+00.00 TO STA 113+00.00	RT	703	
SUBTOTAL MCDONOUGH COUNTY			1085
PROJECT TOTAL			3170

*** SEE SHEET 29 FOR ADDITIONAL EROSION CONTROL ITEMS FOR WHITMIRE ACCESS ROAD

CONCRETE CURB AND GUTTER										
LOCATION STATION TO STATION	SIDE	COMBINATION CONCRETE CURB AND GUTTER TYPE M-4.06	COMBINATION CONCRETE CURB AND GUTTER TYPE M-4.24	CONCRETE GUTTER, TYPE A (MODIFIED)	CLASS SI CONCRETE (OUTLET) SPECIAL	CONCRETE MEDIAN SURFACE (4 INCH)	PROTECTIVE COAT	COMBINATION CURB AND GUTTER REMOVAL	GUTTER REMOVAL	ISLAND PAVEMENT REMOVAL
		FOOT	FOOT	FOOT	CU YD	SQ YD	SQ YD	FOOT	FOOT	SQ YD
MCDONOUGH COUNTY										
IL 336										
STA 49+23.83 TO STA 49+41.14	RT							52		12
STA 49+24.32	RT					108	12			
STA 49+26.20	RT							42		
STA 87+03.06 TO STA 87+14.85	RT									
IL 61										
STA 397+74.92 TO STA 399+40.85	LT		201				57			
STA 399+16.95 TO STA 399+41.00	RT		62				20			
STA 399+22.73 TO STA 399+34.22	RT	15					3			
FRONTAGE ROAD 2										
STA 187+32.40 TO STA 189+21.17	LT								191	
STA 194+07.42 TO STA 194+80.00	RT				11.0		35			
STA 194+85.62 TO STA 198+22.70	LT								337	
STA 194+80.00 TO STA 199+75.88	RT			496			165			
SUBTOTAL MCDONOUGH COUNTY		15	263	496	11.0	108	292	94	528	12
PROJECT TOTAL		15	263	496	11.0	108	292	94	528	12

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES
EROSION CONTROL BLANKET,
PERIMETER EROSION BARRIER &
CONCRETE CURB AND GUTTER

SCALE: VERT. N/A
HORIZ. N/A
DATE 11/9/05

DRAWN BY BDS
CHECKED BY SRD

Plot Date: 8/20/2006
Plot Time: 12:45:43 PM
Plotted By: sdrachue
Pen Table: Idot.tbl
Plotname: R:\030523\cadd\1\count\1\eroc\eroc.dgn