F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
315	(34-6,55-1)	HANCOCK/ McDONOUGH	433	48
STA. 1437+50		TO STA. 1451+00		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

STATE CONTRACT NO. 68206

LEGEND OF NON-STANDARD SYMBOLS

PROPOSED A/C LINE WITH WOVEN WIRE FENCE

PROPOSED ROW & A/C LINE WITH WOVEN WIRE FENCE

PROP. CURVE IL336-2
PI STA. = 1443+91.46
Δ = 43° 08′ 03″ (RT)
D = 2° 43′ 42″
R = 2,100.00′
T = 830.05′
L = 1,580.95′
E = 158.09′
e = 6.0%
T.R. = 39′
S.E. RUN = 270′
P.C. STA = 1435+61.40
P.T. STA = 1451+42.35

JAMES A. & VIRGINIA JEAN NORRIS, TRUSTEES

TEMP ESMNT

1440+20.00 275′ LT

1440+80.00 275′ LT

1442+00.00 190′ LT

1440+00.00 180.00′ LT

1439+80.00 179.07′ LT

1438+00.00 180′ LT

PR ROW & A/C

CONST LIMIT

1446+00.00 185′ LT

PERMANENT FENCE BEING ERECTED BY PROPERTY OWNER. CONSTRUCT TEMPORARY FENCE IF PROPERTY OWNER HAS NOT CONSTRUCTED PERMANENT FENCE AT START OF CONSTRUCTION.

HANCOCK COUNTY

McDONOUGH COUNTY

℄ PROPOSED FAP ROUTE 315 (IL 336)

1445+00

1440+00

1450+00

MATCHLINE STA 1437+50

MATCHLINE STA 1451+00

RANDELL A. & SANDRA S. WHITMIRE

1442+00.00 160′ RT

EX ROW

1444+03.44 200.61′ RT

1444+95.20 191.92′ RT

JAMES A. & VIRGINIA JEAN NORRIS, TRUSTEES

8′ x 4′ CONC. BOX CULVERT

US 136

1440+54.59 182.69′ RT

BM#CB-407

℄ PROPOSED FRONTAGE RD #2

1439+00.00 200′ RT

1170+00

1438+00.00 204′ RT

1439+00.00 206′ RT

1440+00.00 203.17′ RT

1438+00.00 325′ RT

RANDELL A. & SANDRA S. WHITMIRE

50 25 0 50 100

SCALE IN FEET

555 550 545 540 535 530 525

600.00′ V.C.

+2.47%

+0.50%

+2.47%

VPI STA. 1438+00.00
ELEVATION 546.99

PROPOSED FAP ROUTE 315 (IL 336) PROFILE AT ℄

EXISTING FAP ROUTE 315 (IL 336) PROFILE AT ℄

USE LEFT DATUM

USE RIGHT DATUM

575 570 565 560 555 550 545 540 535

5′ 50′

EXISTING FAP ROUTE 315 (IL 336) PROFILE AT ℄

+2.47%

PROPOSED FAP ROUTE 315 (IL 336) PROFILE AT ℄

	1438+00	1439+00	1440+00	1441+00	1442+00	1443+00	1444+00	1445+00	1446+00	1447+00	1448+00	1449+00	1450+00	1451+00
	527.67	529.56	529.39	530.98	548.18	566.73	579.73	590.20	589.81	580.91	572.46	567.04	565.16	568.60
	548.47	550.12	552.10	554.41	556.89	559.36	561.84	564.31	566.78	569.26	571.73	574.21	576.68	579.15

ROADWAY PLAN & PROFILE – FAP ROUTE 315 (IL 336) STA 1437+50 TO STA 1451+00

PLAN: SURVEYED; PLOTTED; ALIGNMENT CHECKED; R.I. OF WAY CHECKED; CADD FILE NAME; NOTE BOOK; NO.; BY; DATE

PROFILE: SURVEYED; PLOTTED; PROFILE CHECKED; GEN. NOTES; STRUCTURE NOTATNS CHKD; NOTE BOOK; NO.; BY; DATE

Plot Date: 8/20/2006
Plot Time: 12:46:49 PM
Plotted By: ssmith
Plot Table: 16bit.tbl
Filename: i:\03033\cadd\1_construction_plans\09_pp04all437.dgn