

ROUTE		SECTION	COUNTY	SHEET	
MKD.	FAP	D-4 SHLDR. REPAIR 2007	KNOX	TOTAL	NO.
US 34	313			10	7

D-94-120-06  
CONTRACT NO. 68651

LOCATION	LENGTH	WIDTH	AREA	BITUMINOUS SURFACE REMOVAL 1 1/2"	BITUMINOUS MATERIALS (PRIME COAT)	BITUMINOUS SHOULDERS SUPERPAVE 2"
OUTSIDE SHOULDERS	FEET	FEET	SQ. YD.	SQ. YD.	TON	TON
EAST BOUND LANES						
STA. 477+00-481+00	400	10	444.4	444.4	0.2	49.8
STA. 482+67-491+55	888	10	986.7	986.7	0.4	110.5
STA. 491+55-494+35	280	10	311.1	311.1	0.1	34.8
STA. 497+35-499+35	200	10	222.2	222.2	0.1	24.9
STA. 500+30-507+06	676	10	751.1	751.1	0.3	84.1
STA. 507+06-536+95	2989	10	3321.1	3321.1	1.3	372
STA. 539+24-564+52	2528	10	2808.9	2808.9	1.1	314.6
STA. 564+52-607+17	4265	10	4738.9	4738.9	1.9	530.8
WEST BOUND LANES						
STA. 477+00-484+95	795	10	883.3	883.3	0.4	98.9
STA. 484+95-491+70	675	10	750	750	0.3	84.0
STA. 492+00-494+95	295	10	327.8	327.8	0.1	36.7
STA. 497+35-500+86	351	10	390	390	0.2	43.7
STA. 500+86-509+25	839	10	932.2	932.2	0.4	104.4
STA. 510+85-539+75	2890	10	3211.1	3211.1	1.3	359.6
STA. 539+75-566+68	2693	10	2992.2	2992.2	1.2	335.1
STA. 569+21-607+17	3796	10	4217.8	4217.8	1.7	472.4
TOTAL				27289	11	3056

RATES:

BITUMINOUS CONCRETE SUPER PAVE=112 LB/SQ YD/IN  
BITUMINOUS BITUMINOUS MATERIAL (PRIME COAT)=0.1 GAL/SQ YD

ILLINOIS DEPARTMENT OF TRANSPORTATION

TABULATION OF  
BITUMINOUS SHLDR.  
QUANTITIES