

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
735	*	MACOUPIN	5	3
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
* 6RS-3; 7RS-6				

Application Rates

Bituminous Materials (Prime Coat) 0.00038 Tons / Sq Yd (0.10 Gal / Sq Yd)
 Aggregate Materials (Prime Coat) 0.002 Tons / Sq Yd

<u>Station Range</u>		<u>Width</u> (FT)	<u>Length</u> (FT)	<u>Area</u> (SY)	<u>Micro-Surfacing</u> (SY)	<u>CAPE Seal</u> (SY)	<u>Aggregate</u> (Prime) (TONS)	<u>Bituminous</u> (Prime) (TONS)	<u>Raised</u> <u>Reflective Markers</u> <u>Removal</u> (EACH)	<u>Raised</u> <u>Reflective Markers</u> <u>Installation</u> (EACH)
252+91	TO 283+97	24	3,106	8,283	--	8,283	16.6	3.1	39	39
285+03	TO 292+00	24	697	1,859	--	1,859	3.7	0.7	9	9
292+00	TO 379+28	20	8,728	19,396	--	19,396	38.8	7.4	109	109
385+32	TO 399+75	20	1,443	3,207	--	3,207	6.4	1.2	18	18
558+58	TO 655+54	20	9,696	21,547	21,547	--	43.1	8.2	121	121
655+94	TO 790+58	20	13,464	29,920	29,920	--	59.8	11.4	168	168
<i>Totals</i>			<i>37,134</i>	<i>84,211</i>	<i>51,467</i>	<i>32,744</i>	<i>168</i>	<i>32.0</i>	<i>464</i>	<i>464</i>
			<i>7,033</i>							

Paint Pavement Marking Line, 5"

<u>Location</u>	<u>Length</u> (FT)	<u>Edge Line</u> (FT)	<u>Center Dash</u> (FT)	<u>Center Solid</u> (FT)
Passing Zone	13,728	27,456	3,432	0
No Passing - One Way	8,448	16,896	2,112	8,448
No Passing Zones	11,616	23,232	0	23,232
<i>Total</i>		<i>67,584</i>	<i>5,544</i>	<i>31,680</i>
<i>Total</i>		<i>104,808</i>		

Notes:

The Fine Aggregate used with the A-1 treatment for the CAPE seal shall be CA-16.

PLOT DATE = 9/1/2006
 FILE NAME = c:\p\projects\6550187\hhtseq.dgn
 PLOT SCALE = 1/8"=1'-0"
 USER NAME = laughlin-1

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SUMMARY OF QUANTITIES
		FAP 735
		SECTION 6RS-3; 7RS-6
		MACOUPIN COUNTY
SCALE:	VERT. DRAWN BY	CHECKED BY
DATE	HORIZ.	