CONTRACT NO. 76558

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
805	122-VBR-I	ST. CLAIR	58	4
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE: 80% FEDERAL 20% STATE X071-2A	80% FEDERAL 20% STATE SFTY-3N	
78200410	GUARDRAIL MARKERS, TYPE A	EACH	9	9		
78200530	BARRIER WALL MARKERS, TYPE C	EACH	8	8		
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	2	2		
78300100	PAVEMENT MARKING REMOVAL	SQ FT	982	982		
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	23	23		
89000105	TEMPORARY TRAFFIC SIGNAL INSTALLATION (SPECIAL)	EACH	1	1		
X0321072	BRIDGE FENCE RAILING	FOOT	360	360		
X0323557	BRIDGE JOINT SYSTEM (EXPANSION), 1"	FOOT	87	87		
X0323558	BRIDGE JOINT SYSTEM (EXPANSION), 1-5/8"	FOOT	87	87		
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	57.5	57.5		
X4066538	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "E", N90	TON	166	166		
X4066618	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N90	TON	180	180		
X7015000	CHANGEABLE MESSAGE SIGN	CAL MO	24	24		
Z0002600	BAR SPLICERS	EACH	814	814		
Z0018800	DRAINAGE SYSTEM	L SUM	1	1		
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	1		1	
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	1		1	
Z0032300	JACKING EXISTING SUPERSTRUCTURE	L SUM	1	1		
Z0047300	PROTECTIVE SHIELD	SQ YD	1692	1692		
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1		
21000300	GRANULAR EMBANKMENT, SPECIAL	TON	400	400		
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	427	427		

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		

##DATE##
10/19/2006
c:\pw_projects\ed07702\plan\plan807a.dgn
*REF-
*REF-
*REF-