

| F.A.P. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|---------------------|-----------|---------------------------|--------------|-----------|
| 805 | 122-VBR-1 | ST. CLAIR | 58 | 6 |
| STA. | | TO STA. | | |
| FED. ROAD DIST. NO. | | ILLINOIS FED. AID PROJECT | | |

PAVING SCHEDULE

| STATION | BIT. MAT'L.S. PRIME COAT (TON) | AGGREGATE PRIME COAT (TON) | POLYMERIZE BIT. CONC. SURF. CSE., SUPER. MIX "E" N90 (TON) | BIT. CONC. BIND. CSE., SUPER. IL-19.0, N90 (TON) | TEMPORARY RAMP. (SQ. YDS.) | PCC BASE CSE. - 8 (SQ. YDS.) | SUBBASE GRAN. MAT. TYPE, A -12" (SQ. YDS.) | SUBBASE GRAN. MAT. TYPE, A (TON) | BITUMINOUS SURFACE REM. - 2 1/2" (SQ. YDS.) |
|----------------------|--------------------------------|----------------------------|--|--|----------------------------|------------------------------|--|----------------------------------|---|
| 65+00.00 TO 67+00.00 | .12 | .48 | 29.7 | 20.0 | | 310.0 | 310.0 | 83.2 | |
| 67+00.00 TO 73+00.00 | .55 | 2.52 | 133.8 | 158.0 | | 494.0 | 494.0 | 89.6 | 1032 |
| 73+00.00 TO 79+00.00 | .03 | .10 | 2.5 | 2.0 | 60.0 | 168.0 | 168.0 | 41.2 | |
| TOTAL | .70 | 3.10 | 166.0 | 180.0 | 60.0 | 972.0 | 972.0 | 214.0 | 1032 |

GUARDRAIL SCHEDULE

| LOCATION | GUARDRAIL REMOVAL FOOT | SPBGR TY A FOOT | TBT TY1 (SPEC) TANG EACH | GUARDRAIL MKRS., TY A EACH | TERM. MKR DIR. APPL. EACH | TBT TY 6 EACH | BARRIER WALL MKRS., TY C EACH |
|-----------------------------------|------------------------|-----------------|--------------------------|----------------------------|---------------------------|---------------|-------------------------------|
| STA. 64+25.13 TO STA. 68+81.24 LT | 463 | | | | | | |
| STA. 64+65.83 TO STA. 68+53.33 LT | | 387.5 | | 5 | | | |
| STA. 64+65.83 LT | | | 1 | | 1 | | |
| STA. 68+53.33 LT | | | | | | 1 | |
| STA. 70+99.27 TO STA. 72+91.95 RT | 201 | | | | | | |
| STA. 71+40.16 TO STA. 72+90.42 RT | | 150.0 | | 4 | | | |
| STA. 71+40.16 RT | | | | | | 1 | |
| STA. 72+90.42 RT | | | 1 | | 1 | | |
| STA. 69+04.50 TO STA. 70+89.08 | | | | | | | 8 |
| TOTAL | 664 | 537.5 | 2 | 9 | 2 | 2 | 8 |

MEDIAN SCHEDULE

| STATIONING | CONCRETE MEDIAN SURFACE REM. SQUARE FOOT | CONCRETE MEDIAN REMOVAL SQUARE FOOT | CONCRETE MEDIAN SURFACE-4" SQUARE FOOT | CONCRETE MEDIAN TYPE SB6.12 SQUARE FOOT |
|--------------------------------|--|-------------------------------------|--|---|
| STA. 65+14.95 TO STA 69+04.50 | 5647 | | 4763 | |
| STA. 68+68.50 TO STA 69+04.50 | | | | 216 |
| STA. 70+89.08 TO STA 71+60.50 | 755 | | | 429 |
| STA. 71+60.50 TO STA. 75+51.67 | | 2347 | | 1951 |
| TOTAL | 6402 | 2347 | 4763 | 2596 |

CURB AND GUTTER SCHEDULE

| STATIONING | CURB AND GUTTER REMOVAL FOOT | COMB. CONC. CURB AND GUTTER TYPE B6.12 FOOT | COMB. CONC. CURB AND GUTTER TYPE B6.24 FOOT | REMOVAL REMARKS |
|-------------------------------|------------------------------|---|---|-----------------------------|
| STA. 65+14.95 TO STA 68+74.50 | 779 | 779 | | ADJACENT TO MEDIAN |
| STA. 64+25.00 TO STA 68+74.50 | 537 | | 537 | ADJACENT TO EOP (LT AND RT) |
| STA. 71+19.08 TO STA 75+51.67 | 866 | 866 | | ADJACENT TO MEDIAN |
| STA. 71+19.08 TO STA 72+00.00 | 162 | | 162 | ADJACENT TO EOP (LT AND RT) |
| TOTAL | 2344 | 1645 | 699 | |

PAVEMENT MARKING SCHEDULE

| STATIONING | SHORT-TERM PAVEMENT MARKING FOOT | WORK ZONE PVT. MRK. REMOVAL SQ FT | THERMOPLASTIC PAVEMENT MARKING - LINE 4" FOOT | THERMPOLASTIC PVT. MRK. LTRS. & SYM. SQ FT | POLYUREA PAVEMENT MARKING - LINE 4" FOOT | RAISED REFLECTIVE PAVEMENT MARKER REMOVAL EACH | RAISED REFLECTIVE PAVEMENT MARKER EACH | RAISED REFLECTIVE PAVEMENT MARKER EACH | PAVEMENT MARKING REMOVAL SQUARE FOOT |
|-------------------------------|----------------------------------|-----------------------------------|---|--|--|--|--|--|--------------------------------------|
| STA. 62+50.00 TO STA 67+00.00 | | | 759.0 | | | 5 | | 5 | 251 |
| STA. 67+00.00 TO STA 73+00.00 | 321.0 | 108.0 | 1545.8 | 26.1 | 1155.0 | 14 | 6 | 8 | 343 |
| STA. 73+00.00 TO STA 79+00.00 | | | 1138.0 | 8.7 | | 3 | | 3 | 379 |
| STA. 79+00.00 TO STA 80+00.00 | | | 27.2 | | | 1 | | 1 | 9 |
| | 321.0 | 108.0 | 3470.0 | 34.8 | 1155.0 | 23 | 6 | 17 | 982 |

| | | |
|------|----|----------------|
| DATE | BY | REVISIONS |
| | | ALIGNED |
| | | CHECKED |
| | | CADD FILE NAME |
| | | NO. |
| | | PLAN |

10/19/2006
 c:\p\proj\ta\ed0782\plan\p1817.dgn
 REF-

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULES

FAP ROUTE 805 (IL 161)
 SECTION 122 VBR-1
 ST. CLAIR COUNTY

DRAWN BY:

| REVISIONS | |
|-----------|------|
| NAME | DATE |
| | |
| | |
| | |
| | |
| | |

PLOT DATE: 10/19/2006