

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
600	1-1BR-1	ST. CLAIR	29	7
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

PAVEMENT MARKING SCHEDULE

LOCATION	TEMPORARY PAVEMENT MARKING LINE - 4"				TEMPORARY PAVEMENT MARKING LINE - 12"	SHORT-TERM PAVEMENT MARKING	WORK ZONE PAVEMENT MARKING SQ FT	THERMOPLASTIC PAVEMENT MARKING -4"				THERMOPLASTIC PAVEMENT MARKING -12"		PAVEMENT MARKING REMOVAL					POLYUREA PAVEMENT MARKING TYPE I-LINE 4"	POLYUREA PAVEMENT MARKING TYPE I-LINE 12"	
	STAGE I	STAGE II	STAGE III	FINAL				SOLID LINE	SKIP-DASH LANE LINE	SKIP-DASH LANE LINE	EDGE LINE WHITE	YELLOW	WHITE	4" YELLOW	4" WHITE	EDGE LINE	SOLID 12"	YELLOW			WHITE
	FOOT	FOOT	FOOT	FOOT				FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	SQ FT	SQ FT	SQ FT	SQ FT	SQ FT			SQ FT
STA 154+02.0 TO STA 156+50.0	248.0		203.0	226.0	62.5	12	292.3			11.0	215		62.5			3.7	71.8		62.5		
STA 156+50.0 TO STA 157+00.0	50.0	100.0	100.0	163.5	25.5	20	170.0	100.0		13.5	50.0		25.5	33.3		4.5	16.7		25.5		
STA 157+00.0 TO STA 157+21.0	21.0	42.0	42.0	69.3	14.4	36	76.5	42.0		6.3	21.0		14.4	14.0		2.1	7.0		14.4		
STA 157+21.0 TO STA 157+53.7		39.0	65.4	107.4	32.0	36	106.6	65.4		9.2	32.8		32.1	21.8		3.1	10.9		32.1		
STA 157+53.7 TO STA 158+62.5			217.6	546.5	127.3	36	394.1				1.5						36.9			545.0	127.0
STA 158+62.5 TO STA 158+85.0			45.0	65.6	26.9	36	67.8	45.0			20.6	7.7	19.2	15.0			6.9	7.7	19.2		
STA 158+85.0 TO STA 159+15.0	30.0		60.0	90.0	39.2	36	103.2	60.0			30.0	13.9	25.5	20.0			10.0	13.9	25.5		
STA 159+15.0 TO STA 160+05.0	141.0		328.0	293.9	28.2	24	290.5	183.9	20.0		90.0	28.2		61.3	6.7		30.0	28.2			
STA 160+05.0 TO STA 160+33.0	24.0		112.0	25.0		4	55.0				25.0						8.3				
SUB-TOTAL	514.0	181.0	1173.0	1587.0				496.3	20.0	39.9	485.9	49.8	179.2	165.4	6.7	13.4	198.5	49.8	179.2		
TOTAL	3455				356	240	1556	1042				229		613					545	127	

STAGING SCHEDULE

LOCATION	TRAFFIC BARRIER TERMINAL, TYPE 11	TEMPORARY CONCRETE BARRIER	RELOCATE TEMPORARY CONCRETE BARRIER	TEMPORARY PAVEMENT MARKING LINE 6"	TEMPORARY BRIDGE RAIL	IMPACT ATTENUATOR, TEMPORARY (NON-REDIRECTIVE)	IMPACT ATTENUATOR, RELOCATE (NON-REDIRECTIVE)	IMPACT ATTENUATOR, TEMPORARY (FULLY-REDIRECTIVE)	IMPACT ATTENUATOR, RELOCATE (FULLY-REDIRECTIVE)
	EACH	FOOT	FOOT	FOOT	FOOT	EACH	EACH	EACH	EACH
STAGE I		500		500		2			
STAGE II	4	37.5	262.5	475	220		1	1 *	
STAGE III			75				1		1
TOTAL	4	537.5	337.5	975	220	2	2	1	1

\* MAXIMUM WIDTH OF 2'-11" AND A MAXIMUM LENGTH OF 24'.

RESURFACING SCHEDULE

LOCATION	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	BITUMINOUS SURFACE REMOVAL 1 1/2"	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE	LEVEL BINDER (MACHINE METHOD), SUPERPAVE
STATION TO STATION	TON	TON	SQ YD	TON	TON
STA 157+00.00 TO STA 157+53.70	0.1	0.5	286.8	24.1	17.3
BRIDGE OMISSION					
STA 158+62.80 TO STA 159+15.00	0.1	0.5	260.2	21.9	15.7
TOTAL	0.2	1	547	46	33

RAISED REFLECTIVE PAVEMENT MARKERS SCHEDULE

LOCATION	RAISED REFLECTIVE PAVEMENT MARKER		RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)		REPLACEMENT REFLECTOR		RAISED REFLECTIVE PAVEMENT MARKER REMOVAL
	2-WAY AMBER	WHITE	2-WAY AMBER	AMBER	WHITE		
	EACH	EACH	EACH	EACH	EACH		
STA 154+02.0 TO STA 156+50.0					1	1	
STA 156+50.0 TO STA 157+00.0				1	1	2	
STA 157+00.0 TO STA 157+21.0		1				1	
STA 157+21.0 TO STA 157+53.7	2					2	
STA 157+53.7 TO STA 158+62.5			6			6	
STA 158+62.5 TO STA 158+85.0	2					2	
STA 158+85.0 TO STA 159+15.0	2					2	
STA 159+15.0 TO STA 160+05.0				4		4	
STA 160+05.0 TO STA 160+33.0							
SUB-TOTAL	6	1		5	2		
TOTAL	7		6	7		20	

SIDEWALK AND CURB & GUTTER SCHEDULE

LOCATION	SIDEWALK REMOVAL	PCC SIDEWALK 4 IN	COMBINATION CURB & GUTTER REMOVAL	COMBINATION CURB & GUTTER, TYPE B-6.24	INLETS TO BE ADJUSTED
STATION TO STATION	SQ FT	SQ FT	FT	FT	EACH
NORTHEAST QUADRANT					
STA 157+00.00 TO STA 157+51.00	328.6	328.6	51.0	51.0	
NORTHWEST QUADRANT					
STA 157+00.00 TO STA 157+57.70	358.2	358.2	58.0	57.8	
BRIDGE OMISSION					
SOUTHEAST QUADRANT					
STA 158+58.80 TO STA 159+15.00	315.4	315.4	56.5	56.3	1
SOUTHWEST QUADRANT					
STA 158+65.60 TO STA 159+15.00	287.8	287.8	49.5	49.4	1
TOTAL	1290	1290	215	214.5	2

TEMPORARY RAMP SCHEDULE

LOCATION	WIDTH FOOT	LENGTH FOOT	TEMPORARY RAMP SQ YD
STA 157+00.0	48	5	26.8
STA 159+10.0	41.75	5	23.3
STA 157+41.6	48	12.1	64.7
STA 158+62.8	47.6	12.1	64.2
TOTAL			179

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION SCHEDULES
NAME	DATE	
		FAP ROUTE 600 SECTION 1-1BR-1 ST. CLAIR COUNTY  SCALE: VERT. / HORIZ. DATE  DRAWN BY / CHECKED BY

PLOT DATE = 10/11/2006  
 FILE NAME = c:\projects\600\1-1BR-1\plan\103065.dgn  
 PLOT SCALE = 50.0000 / IN.  
 REFERENCE = BREF4

Rev. 10-16-06