

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
600	1-1BR-1	ST. CLAIR	29	7
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

PAVEMENT MARKING SCHEDULE

LOCATION	TEMPORARY PAVEMENT MARKING LINE - 4"				TEMPORARY PAVEMENT MARKING LINE - 12"	SHORT-TERM PAVEMENT MARKING	WORK ZONE PAVEMENT MARKING REMOVAL	THERMOPLASTIC PAVEMENT MARKING -4"				THERMOPLASTIC PAVEMENT MARKING -12"		PAVEMENT MARKING REMOVAL					POLYUREA PAVEMENT MARKING TYPE I-LINE 4"	POLYUREA PAVEMENT MARKING TYPE I-LINE 12"			
	STAGE I	STAGE II	STAGE III	FINAL				SOLID LINE	SKIP-DASH LANE LINE	SKIP-DASH LANE LINE	EDGE LINE WHITE	YELLOW	WHITE	SOLID LINE	SKIP-DASH LANE LINE	SKIP-DASH LANE LINE	EDGE LINE	SOLID 12"					
	FOOT	FOOT	FOOT	FOOT				FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT			FOOT		
STA 154+02.0 TO STA 156+50.0	248.0		232.0	219.3	62.5		295.8			11.0	2+15.00		62.5				3.3	69.5		62.5			
STA 156+50.0 TO STA 157+00.0	50.0	100.0	118.0	163.3	25.5		169.6	100.0		13.5	50.0		25.5	33.3			4.5	16.7		25.5			
STA 157+00.0 TO STA 157+21.0	21.0	42.0	42.0	69.1	14.4	12	74.2	42.0		6.3	21.0		14.4	14.0			2.2	7.0		14.4			
STA 157+21.0 TO STA 157+53.7		39.0	65.4	106.7	32.0	12	103.9	65.4		9.2	32.7		32.1	21.8			3.1	10.9		32.1			
STA 157+53.7 TO STA 158+62.5			217.6	544.3	127.3	12	382.8											0.5			545.0	127.0	
STA 158+62.5 TO STA 158+85.0			45.0	68.0	26.9	12	66.3	45.0					20.6	7.7	19.2	15.0		6.9	7.7	19.2			
STA 158+85.0 TO STA 159+15.0	30.0		90.0	90.0	39.2	12	110.7	60.0					30.0	13.9	25.5	20.0		10.0	13.9	25.5			
STA 159+15.0 TO STA 160+05.0	141.0		418.0	294.5	28.2		312.9	183.9	20.0		90.0	28.2		61.3	6.7			30.0	28.2				
STA 160+05.0 TO STA 160+33.0	24.0		112.0	25.0			53.9				25.0							8.3					
SUB-TOTAL	514.0	181.0	1340.0	1580.0				496.3	20.0	40.0	485.8	49.8	179.2	165.4	6.7	13.1	159.8	49.8	179.2				
TOTAL		3615			356	60	1570			1042		229				574		545		127			

STAGING SCHEDULE

LOCATION	TRAFFIC BARRIER TERMINAL, TYPE 11	TEMPORARY CONCRETE BARRIER	RELOCATE TEMPORARY CONCRETE BARRIER	TEMPORARY PAVEMENT MARKING LINE 6"	TEMPORARY BRIDGE RAIL	IMPACT ATTENUATOR, TEMPORARY (NON-REDIRECTIVE)	IMPACT ATTENUATOR, RELOCATE (NON-REDIRECTIVE)	IMPACT ATTENUATOR, TEMPORARY (FULLY-REDIRECTIVE)	IMPACT ATTENUATOR, RELOCATE (FULLY-REDIRECTIVE)
	EACH	FOOT	FOOT	FOOT	FOOT	EACH	EACH	EACH	EACH
STAGE I				500		2			
STAGE II	4	550	262.5	475	220		1	1 *	
STAGE III			75				1		1
TOTAL	4	550	337.5	975	220	2	2	1	1

\* MAXIMUM WIDTH OF 2'-11" AND A MAXIMUM LENGTH OF 24'.

RESURFACING SCHEDULE

LOCATION	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	BITUMINOUS SURFACE REMOVAL 1 1/2"	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE	LEVEL BINDER (MACHINE METHOD), SUPERPAVE
STATION TO STATION	TON	TON	SQ YD	TON	TON
STA 157+00.00 TO STA 157+53.70	0.1	0.5	286.8	24.1	17.3
BRIDGE OMISSION					
STA 158+62.80 TO STA 159+15.00	0.1	0.5	260.2	21.9	15.7
TOTAL	0.2	1	547	46	33

RAISED REFLECTIVE PAVEMENT MARKERS SCHEDULE

LOCATION	RAISED REFLECTIVE PAVEMENT MARKER		RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	REPLACEMENT REFLECTOR		RAISED REFLECTIVE PAVEMENT MARKER REMOVAL
	2-WAY AMBER	WHITE		2-WAY AMBER	WHITE	
	EACH	EACH		EACH	EACH	
STA 154+02.0 TO STA 156+50.0				1	1	
STA 156+50.0 TO STA 157+00.0				3	1	4
STA 157+00.0 TO STA 157+21.0	1	1				2
STA 157+21.0 TO STA 157+53.7	2					2
STA 157+53.7 TO STA 158+62.5			11			11
STA 158+62.5 TO STA 158+85.0	3					3
STA 158+85.0 TO STA 159+15.0	3					3
STA 159+15.0 TO STA 160+05.0				11		11
STA 160+05.0 TO STA 160+33.0						0
SUB-TOTAL	9	1		14	2	
TOTAL	10		11	16		37

SIDEWALK AND CURB & GUTTER SCHEDULE

LOCATION	SIDEWALK REMOVAL	PCC SIDEWALK 4 IN	COMBINATION CURB & GUTTER REMOVAL	COMBINATION CURB & GUTTER, TYPE B-6.24
STATION TO STATION	SQ FT	SQ FT	FT	FT
NORTHEAST QUADRANT				
STA 157+00.00 TO STA 157+51.00	328.6	328.6	51.0	51.0
NORTHWEST QUADRANT				
STA 157+00.00 TO STA 157+57.70	358.2	358.2	57.8	57.8
BRIDGE OMISSION				
SOUTHEAST QUADRANT				
STA 158+58.80 TO STA 159+15.00	315.4	315.4	56.3	56.3
SOUTHWEST QUADRANT				
STA 158+65.60 TO STA 159+15.00	287.8	287.8	49.4	49.4
TOTAL	1290	1290	214.5	214.5

TEMPORARY RAMP SCHEDULE

LOCATION	WIDTH FOOT	LENGTH FOOT	TEMPORARY RAMP SQ YD
STA 157+00.0	48	5	26.8
STA 159+10.0	41.75	5	23.3
STA 157+41.6	48	12.1	64.7
STA 158+62.8	47.6	12.1	64.2
TOTAL			179

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION SCHEDULES
NAME	DATE	
		FAP ROUTE 600 SECTION 1-1BR-1 ST. CLAIR COUNTY  SCALE: VERT. _____ HORIZ. _____ DATE _____

DRAWN BY \_\_\_\_\_  
CHECKED BY \_\_\_\_\_