F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	50TS-1, 2TS	GREENE	6	3

STA.		TO STA.	
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT	

* FAS 733 / FAP 566

ELECTRICAL GENERAL NOTES

1. ALL TRAFFIC SIGNAL HEADS SHALL HAVE 12"
SECTIONS. MOUNTING HARDWARE SHALL BE UNPAINTED ALUMINUM.
ALL BOLTS, SCREWS, NUTS AND WASHERS SHALL BE STAINLESS STEEL.
ANTI-SEIZE PASTE COMPOUND SHALL BE USED ON ALL MOUNTING
HARDWARE FIELD CONNECTIONS.

2. ALL PROPOSED TRAFFIC SIGNAL CABLES SHALL BE #14 AWG STRANDED COPPER
UNLESS OTHERWISE SPECIFIED. TERMINAL ENDS SHALL HAVE CRIMPED-ON
RING TONGUE CONNECTORS.

3. ILLINOIS STATE LAW REQUIRES A 48 HOUR NOTICE BE GIVEN TO UTILITIES BEFORE
DIGGING. FIELD MARKING OF FACILITIES MAY BE OBTAINED BY CONTACTING J.U.L.I.E.
OR FOR NON-MEMBERS, THE UTILITY COMPANY DIRECTLY. AGENCIES KNOWN TO
HAVE FACILITIES WITHIN THE PROJECT AREA ARE AS FOLLOWS:

   ### US 67 @ IL 106
   * AMEREN CIPS (ELECT)
   * GREENE COUNTY CABLEVISION (CABLE TV)
   * VERIZON NORTH, INC. (COMM)
   * CITY OF WHITEHALL (GAS)
   * CITY OF WHITEHALL (WTR. & SANITARY SEWER)

   (MEMBERS OF J.U.L.I.E. PHONE (800) - 892-0123 ARE INDICATED BY *)
   NON-J.U.L.I.E. MEMBERS MUST BE NOTIFIED INDIVIDUALLY.

4. THE CONTRACTOR SHALL DRILL TWO 1 1/2" DIAMETER HOLES IN EXISTING/PROPOSED
WOOD SIGN SUPPORT IN ACCORDANCE WITH ARTICLE 730.03 OF THE STANDARD SPECIFICATIONS.
THE COST SHALL BE INCLUDED IN PAY ITEM, "SIGNAL HEAD, POLY, LED, 1-FACE, 1-SECTION, P.M.".

5. UNDERGROUND MARKING TAPE SHALL BE INSTALLED WITH ALL TRENCH AND BACKFILL FOR ELECTRICAL
WORK ACCORDING TO ARTICLE 815.03 (d) AND 1066.05 OF THE STANDARD SPECIFICATIONS.

6. THE QUANTITY SHOWN FOR PAINT PAVEMENT MARKING REMOVAL IS APPROXIMATE. THE REMOVAL
SHALL BE AT THE DISCRETION OF THE ENGINEER. ACTUAL QUANTITY MAY DIFFER FROM SHOWN
ON THE PLANS.

TRAFFIC SIGNALS LEGEND

GSC	GALVANIZED STEEL CONDUIT
PVCC	POLYVINYL CHLORIDE CONDUIT
◼	PROPOSED HANDHOLE
◼	PROPOSED CONTROLLER
—"—	PROPOSED CONDUIT: "T" TRENCH, "P" PUSH, SIZE SPECIFIED
◼	PROPOSED SERVICE INSTALLATION
►	PROPOSED SIGNAL HEAD, POST MOUNTED ('R'-RED, 'Y'-YELLOW)
◼	PROPOSED SIGN POST
⊓	EXISTING SIGN POST

COMMITMENT

NOTIFY MS. SUE RENO, CIRCUIT CLERK, CITY OF WHITE HALL
(PH. # 217-374-2345) TWO WEEKS PRIOR TO INSTALLATION OF
NEW STOP SIGN ALONG IL-106.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

GENERAL NOTES, COMMITMENT, AND LEGEND

ROUTE: FAS 733 / FAP 566
SECTION: 50TS-1, 2TS
GREENE COUNTY

SCALE:	VERT.		DRAWN BY
	HORIZ.		
DATE			CHECKED BY

PLOT DATE = #DATE#
FILE NAME = #FILE#
PLOT SCALE = #SCALE#
REFERENCE = #REF#