CONTRACT NO. 83869

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1441	00-00059-00-BR	KANE	154	7
STA. N/A		TO STA. N/A		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	HBRRP - H/O 80%				ITEP - Q22 80%					CITY OF BATAVIA - NON-PARTICIPATING AND SECTION 112					
				BRIDGE	ROADWAY CONCRETE	LIGHTING	SIGNALS	BRIDGE	ROADWAY CONCRETE	LIGHTING	MIXED-USE PATH	LANDSCAPING	ROADWAY BITUMINOUS	ROADWAY CONCRETE	LIGHTING	SIGNALS	MIXED-USE PATH	WATER/ SEWER
				X020-2A	J000-2A	Y030-1E	Y031-1F	X020-2A	J000-2A	Y030-1E	Y042	Y003	I000-2A	J000-2A	Y030-1E	Y031-1F	Y042	Y060
• X0323859	DOWNSPOUT CONNECTION	EACH	1														1	
• X0323988	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	3,100	3,100														
•+X0539800	TREE GRATES	EACH	10									10						
•+X0840000	SANITARY SEWER REMOVAL 8"	FOOT	242															242
• X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	TON	15														15	
• X4066740	LEVELING BINDER (HAND METHOD), SUPERPAVE N70	TON	1										1					
• X4066770	LEVELING BINDER (MACHINE METHOD), SUPERPAVE N70	TON	121										121					
• X5000800	FLOATING BEARINGS, FIXED, 800K	EACH	10	10														
• X5005800	FLOATING BEARINGS, GUIDED EXPANSION, 800K	EACH	10	10														
• X7015000	CHANGEABLE MESSAGE SIGN	CAL MO	20	20														
•+X8710020	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM12F	FOOT	870				870											
•+X8900010	TEMPORARY TRAFFIC SIGNAL INTERCONNECT	EACH	1				1											
• XX001490	GATE VALVES, 8"	EACH	2															2
• XX004145	DRINKING FOUNTAIN RELOCATED	EACH	1															1
• XX004782	TEMPORARY BITUMINOUS PAVEMENT	SQ YD	302		270									32				
• XX005043	ORNAMENTAL SIGN POST	EACH	10						4		6							
•+XX005077	SANITARY SEWER 8" TYPE 2, DUCTILE IRON, CL 52	FOOT	155															155
• X4066426	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX D, N70	TON	146										146					
• XX005534	SIDEWALK DRAIN	EACH	5														5	
• XX005953	TEMPORARY CHAIN LINK FENCE, 8'	FOOT	800		800													
• XX005968	TURBIDITY CURTAIN	SQ YD	728	728														
• XX104800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-V.12	FOOT	572											572				
• Z0002600	BAR SPLICERS	EACH	1,162	1,162														
• Z0006100	BRIDGE DECK LATEX CONCRETE OVERLAY	SQ YD	1,322	1,322														
• Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1														
• Z0018900	DRILL AND GROUT DOWEL BARS	EACH	108	108														
• Z0030260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	4	4														
• Z0030330	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE),TEST LEVEL 3	EACH	2	2														
•Δ Z0076600	TRAINEES	HOUR	2,000	2,000														
• XX006737	REINFORCED PORTLAND CEMENT CONCRETE SIDEWALK, VARIABLE DEPTH	SQ FT	636								636							
• XX006739	CONCRETE PAVERS, TYPE A	SQ FT	4,064						452		3,612							
• XX006740	CONCRETE PAVERS, TYPE B	SQ FT	5,441					3,343	2,098									
• XX006741	CONCRETE PAVERS, TYPE C	SQ FT	43						43									
• XX006742	REMOVE EXISTING CONCRETE ARCH BRIDGE	L SUM	1	1														
• 50200510	COFFERDAMS (SPECIAL)	EACH	3	3														
• XX006743	BAR COUPLERS	EACH	190	190														
• XX006744	MICROPILE, 200 TON	EACH	45	45														
• XX005128	STRIP SEAL EXPANSION JOINT ASSEMBLY	FOOT	159	159														
• XX005517	CONCRETE FILL	CU YD	354	354														
• XX006745	FURNISHING, INSTALLING AND STRESSING POST-TENSIONING STRANDS	POUND	133,690	125,669				8,021										
• XX006746	RUSTICATION FINISH TYPE I	SQ FT	2,299					2,299										
• XX006747	RUSTICATION FINISH TYPE II	SQ FT	1,465					1,465										
• XX006748	RIVERWALK RAILING	FOOT	442								442							
• XX006749	BRIDGE RAILING	FOOT	416	208				208										
• XX006750	OUTLOOK RAILING	FOOT	140	70				70										
• XX006751	STAIR RAILING	FOOT	202	202														
• XX006752	REMOVE, STORE AND RE-INSTALL EXISTING MONUMENT	L SUM	1	1														
• XX006753	DROP MANHOLES, TYPE A2-2, 4'-DIAMETER, SPECIAL FRAME AND LID	EACH	1											1				
• XX006754	DROP MANHOLES, TYPE A2-3, 5'-DIAMETER, SPECIAL FRAME AND LID	EACH	1											1				
• XX006585	CURB STOP AND BOX, 3/4"	EACH	2															2
• XX006755	STOP VALVE 3/4" AND VALVE BOX	EACH	2															2
•+XX006756	WALL HYDRANTS	EACH	2															2
•+XX006757	LUMINAIRE, SODIUM VAPOR, PEDESTRIAN, PHOTO-CELL CONTROL, 100 WATT	EACH	8							8								
•+XX006758	LUMINAIRE, SODIUM VAPOR, PEDESTRIAN, PHOTO-CELL CONTROL, 50 WATT	EACH	9							9								
•+XX006759	UNDERPASS LUMINAIRE, FLUORESCENT, 60 WATT	EACH	8							8								
•+XX006760	UNDER STAIR LUMINAIRE, INCANDESCENT, 75 WATT	EACH	2							2								
•+XX006761	JUNCTION BOX EMBEDDED IN STRUCTURE, 4"X4"X3"	EACH	14							14								
•+XX006762	LIGHT POLE FOUNDATION, 15" DIAMETER	FOOT	8925							8925								
•+83006300	LIGHT POLE, ALUMINUM, 30 FT. M.H., 8 FT. MAST ARM	EACH	10			4									6			
•+XX006763	LIGHT POLE, ALUMINUM, 14 FT., POST TOP, WITH PLANTER ARMS	EACH	8							8								
•+XX006764	LIGHT POLE, ALUMINUM, 14 FT., POST TOP	EACH	6							6								
•+XX006765	LIGHT POLE, ALUMINUM, 10 FT., POST TOP	EACH	3							3								
•+XX006766	GFI RECEPTACLE AND BOX, 120V	EACH	14							14								
•+XX006767	LIQUIDTIGHT FLEXIBLE METAL CONDUIT, 3/4"	FOOT	50							50								
•+XX006768	MAINTAIN LIGHTING SYSTEM	L SUM	1			1												
• XX006769	TREE REMOVAL (SPECIAL)	EACH	9											9				
• +YX006770	TREE, GINKGO BILOBA (AUTUMN GOLD), 3" CALIPER, BALLED AND BURLAPPED	EACH	4									4						
• XX006771	ARCHITECTURAL PRE-CAST CONCRETE - DIES (SPECIAL)	EACH	35	18				17										
• XX006772	ARCHITECTURAL PRE-CAST CONCRETE - BRIDGE CURB (SPECIAL)	FOOT	405	203				202										
• XX006773	ARCHITECTURAL PRE-CAST CONCRETE - OUTLOOK CURB (SPECIAL)	FOOT	119	60				59										
• XX006774	ARCHITECTURAL PRE-CAST CONCRETE - POST BASE (SPECIAL)	EACH	16	8				8										
• XX006775	ARCHITECTURAL PRE-CAST CONCRETE - BENCH PLANTER SYSTEM (SPECIAL)	EACH	4					4										
• XX006776	ARCHITECTURAL PRE-CAST CONCRETE - SOUTHWEST STAIR SYSTEM (SPECIAL)	L SUM	1	1														
• XX006777	ARCHITECTURAL PRE-CAST CONCRETE - SOUTHEAST STAIR SYSTEM (SPECIAL)	L SUM	1	1														
• XX006778	ARCHITECTURAL PRE-CAST CONCRETE - NORTHEAST STAIR SYSTEM (SPECIAL)	L SUM	1	1														

Δ = Y080 + SPECIALTY ITEMS

Revised 11-8-06

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

WILSON STREET

SUMMARY OF QUANTITIES

SCALE: NTS DRAWN BY WAJ

DATE 07/28/2006 CHECKED BY AKK

PLOT DATE = 09/28/2006
FILE NAME = #FILE#
PLOT SCALE = #SCALE#
USER NAME = #USER#

E:\2006\CIVIL\TYPICALS\1441-00-BR_SUMMARY OF QUANTITIES.dgn 09/28/2006 04:49:49 PM