CONTRACT NO. 83869

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1441	00-00059-00-BR	KANE	154	5
STA. N/A		TO STA. N/A		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	HBRRP- H/O 80%				ITEP- Q22 80%					CITY OF BATAVIA - NON-PARTICIPATING AND SECTION 112					
				BRIDGE	ROADWAY CONCRETE	LIGHTING	SIGNALS	BRIDGE	ROADWAY CONCRETE	LIGHTING	MIXED-USE PATH	LANDSCAPING	ROADWAY BITUMINOUS	ROADWAY CONCRETE	LIGHTING	SIGNALS	MIXED-USE PATH	WATER/ SEWER
				X020-2A	J000-2A	Y030-1E	Y031-1F	X020-2A	J000-2A	Y030-1E	Y042	Y003	I000-2A	J000-2A	Y030-1E	Y031-1F	Y042	Y060
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	862														862	
20400800	FURNISHED EXCAVATION	CU YD	12											12				
20700220	POROUS GRANULAR EMBANKMENT	CU YD	3,015	2,165													850	
• 20800150	TRENCH BACKFILL	CU YD	135		56									79				
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	421		40									210			171	
• 21300010	EXPLORATION TRENCH, SPECIAL	FOOT	25															25
+ 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	8		1									4			3	
+ 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	8		1									4			3	
+ 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	8		1									4			3	
25100630	EROSION CONTROL BLANKET	SQ YD	1,438		120									200			1,118	
+ 25200110	SODDING SALT TOLERANT	SQ YD	421		40									210			171	
+ 28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	100		10									10			80	
28000400	PERIMETER EROSION BARRIER	FOOT	840		100									93			647	
28000510	INLET FILTERS	EACH	26	8	1								3	14				
31100300	SUB-BASE GRANULAR MATERIAL, TYPE A 4"	SQ YD	81										81					
31100700	SUB-BASE GRANULAR MATERIAL, TYPE A 8"	SQ YD	1,320											1,320				
31101400	SUB-BASE GRANULAR MATERIAL, TYPE B 6"	SQ YD	130														130	
31200100	STABILIZED SUB-BASE 4"	SQ YD	1,320											1,320				
35300300	PORTLAND CEMENT CONCRETE BASE COURSE 8"	SQ YD	149										149					
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	200										157				43	
42000400	PORTLAND CEMENT CONCRETE PAVEMENT 9"	SQ YD	1,182											1,182				
42001300	PROTECTIVE COAT	SQ YD	275	275														
• 42001400	BRIDGE APPROACH PAVEMENT (SPECIAL)	SQ YD	342	342														
• 42400430	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH, SPECIAL	SQ FT	11,152		1,048				1,979		3,454			4,671				
• 42400800	DETECTABLE WARNINGS	SQ FT	40						40									
• 44000030	BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	1,693										1,693					
44000100	PAVEMENT REMOVAL	SQ YD	1,613		188								181	1,244				
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	679		72									607				
44000600	SIDEWALK REMOVAL	SQ FT	8,490		584									5,244			2,662	
48101600	AGGREGATE SHOULDERS, TYPE B 8"	SQ YD	20														20	
50102400	CONCRETE REMOVAL	CU YD	140	140														
50102700	MASONRY REMOVAL	CU YD	55	55														
50200100	STRUCTURE EXCAVATION	CU YD	773	773														
50200400	ROCK EXCAVATION FOR STRUCTURES	CU YD	310	310														
50300225	CONCRETE STRUCTURES	CU YD	1,520	1,520														
50300254	RUBBED FINISH	SQ FT	967	967														
50300255	CONCRETE SUPERSTRUCTURE	CU YD	179	156				23										
50300260	BRIDGE DECK GROOVING	SQ YD	1,264	1,264														
50300320	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	28	28														
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	438,470	412,162				26,308										
51500100	NAME PLATES	EACH	1	1														
55019500	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 12"	FOOT	8		8													
55019700	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 18"	FOOT	8		8													
55021600	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 12"	FOOT	200		25									175				
55023700	STORM SEWERS, TYPE 3, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 12"	FOOT	40		35									5				
55026000	STORM SEWERS, TYPE 4, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS V 18"	FOOT	40		35									5				
55100300	STORM SEWER REMOVAL 8"	FOOT	88		39									49				
55100400	STORM SEWER REMOVAL 10"	FOOT	101		39									62				
55100500	STORM SEWER REMOVAL 12"	FOOT	29		26									3				
55100700	STORM SEWER REMOVAL 15"	FOOT	54		14									40				
55100900	STORM SEWER REMOVAL 18"	FOOT	81		81													
•+56103000	DUCTILE IRON WATER MAIN 6"	FOOT	251															251
•+ 56103100	DUCTILE IRON WATER MAIN 8"	FOOT	135															135
•+56103200	DUCTILE IRON WATER MAIN 10"	FOOT	472															472
•+56104900	WATER VALVES 6"	EACH	11															11
•+56108900	TAPPING VALVES AND SLEEVES 8"	EACH	2															2
•+56109000	TAPPING VALVES AND SLEEVES 10"	EACH	2															2
•+56200600	WATER SERVICE LINE 3/4"	FOOT	81															81
•+56201300	CORPORATION STOPS 3/4"	EACH	2															2
•+56400500	FIRE HYDRANTS TO BE REMOVED	EACH	2															2
•+56400820	FIRE HYDRANT WITH AUXILIARY VALVE AND VALVE BOX	EACH	2															2
58700200	BRIDGE SEAT SEALER	SQ FT	1,041	1,041														
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	403	403														
• 60101605	PIPE DRAINS 4" (SPECIAL)	FOOT	90														90	
• 60101705	PIPE DRAINS 6" (SPECIAL)	FOOT	9														9	
60109582	PIPE UNDERDRAINS FOR STRUCTURES 6"	FOOT	539	539														
• 60213300	CATCH BASINS, SPECIAL	EACH	5											5				
• 60228200	MANHOLES, SANITARY, WITH SPECIAL FRAME AND CLOSED LID	EACH	3											3				
• 60235800	INLETS, TYPE A, TYPE 4 FRAME AND GRATE	EACH	1		1													
• 60240100	INLETS, TYPE A, SPECIAL, WITH SPECIAL FRAME AND GRATE	EACH	3											3				
• 60249110	VALVE VAULTS, 4'-DIAMETER	EACH	6															6
• 60249400	VALVE BOXES 6"	EACH	11															11
60255500	MANHOLES TO BE ADJUSTED	EACH	1										1					
60260100	INLETS TO BE ADJUSTED	EACH	3										3					
60265700	VALVE VAULTS TO BE ADJUSTED	EACH	3										3					

+ SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
WILSON STREET
SUMMARY OF QUANTITIES

SCALE: NTS
DRAWN BY WAJ
DATE 07/28/2006
CHECKED BY AKK

PLOT DATE = 09/28/2006
FILE NAME = #FILE#
PLOT SCALE = #SCALE#
USER NAME = #USER#

L:\DRGS\1141\Wilson\sht 09/28/2006 14:08:45 PM