

SUMMARY OF QUANTITIES

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1441	00-00059-00-BF	KANE	154	6
STA. N/A		TO STA. N/A		
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	HBRP - H/O 80%				ITEP - Q22 80%				CITY OF BATAVIA - NON-PARTICIPATING AND SECTION 112						
				BRIDGE	ROADWAY CONCRETE	LIGHTING	SIGNALS	BRIDGE	ROADWAY CONCRETE	LIGHTING	MIXED-USE PATH	LANDSCAPING	ROADWAY BITUMINOUS	ROADWAY CONCRETE	LIGHTING	SIGNALS	MIXED-USE PATH	WATER/SEWER
				X020-2A	J000-2A	Y030-1E	Y031-1F	X020-2A	J000-2A	Y030-1E	Y042	Y003	I000-2A	J000-2A	Y030-1E	Y031-1F	Y042	Y060
60500040	REMOVING MANHOLES	EACH	4		3													
60500060	REMOVING INLETS	EACH	6		4													
* 60600105	CONCRETE CURB	FOOT	390							100		290						
* 60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	64											64				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	22	22														
67000600	ENGINEER'S FIELD LABORATORY	CAL MO	22	22														
67100100	MOBILIZATION	L SUM	1	1														
* 70101700	TRAFFIC CONTROL AND PROTECTION	L SUM	1	1														
* 70101900	TRAFFIC CONTROL AND PROTECTION (DETOUR 1)	L SUM	1	1														
* 70103816	TRAFFIC CONTROL SURVEILLANCE	CAL MO	22	22														
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	437									437						
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	9,292		1,200							6,592	1,500					
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	981									981						
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	333									333						
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	225									225						
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	4,807		400							3,907	500					
70400100	TEMPORARY CONCRETE BARRIER	FOOT	710	710														
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	355	355														
72000100	SIGN PANEL - TYPE 1	SQ FT	97		13								48		36			
72400900	REMOVE SIGN PANEL	EACH	21		3								18					
73700100	REMOVE GROUND-MOUNTED SIGN SUPPORT	EACH	6										6					
73700200	REMOVE CONCRETE FOUNDATION - GROUND MOUNT	EACH	6										6					
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	292									292						
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	1,977									1,977						
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1,234									1,234						
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	322									322						
78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	233									233						
+ 78005100	EPOXY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	146		109								37					
+ 78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	1,378		816								562					
+ 78005130	EPOXY PAVEMENT MARKING - LINE 6"	FOOT	575		252								323					
+ 78005150	EPOXY PAVEMENT MARKING - LINE 12"	FOOT	59		29								30					
78200530	BARRIER WALL MARKERS, TYPE C	EACH	28	28														
78300100	PAVEMENT MARKING REMOVAL	SQ FT	1,868		100							1,468	300					
+ 80700110	GROUND ROD, 3/4" DIA. X 10 FT.	EACH	16			4								6				
+ 80800425	TEMPORARY WOOD POLE, 50 FT., CLASS 4, 15 FT. MAST ARM	EACH	2			2												
+ 81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	325				60								265			
+ 81012300	CONDUIT IN TRENCH, 1" DIA., PVC	FOOT	725									170						
+ 81012500	CONDUIT IN TRENCH, 1 1/2" DIA., PVC	FOOT	780			120						60			555			
+ 81016100	CONDUIT IN TRENCH, 1/2" DIA., HIGH DENSITY POLYETHYLENE, COILABLE	FOOT	140									140			600			
+ 81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	60											60				
+ 81100200	CONDUIT ATTACHED TO STRUCTURE, 3/4" DIA., GALVANIZED STEEL	FOOT	200									200						
+ 81200120	CONDUIT EMBEDDED IN STRUCTURE, 2" DIA., GALVANIZED STEEL	FOOT	240				240											
+ 81200200	CONDUIT EMBEDDED IN STRUCTURE, 3/4" DIA., PVC	FOOT	375									375						
+ 81200210	CONDUIT EMBEDDED IN STRUCTURE, 1" DIA., PVC	FOOT	590									110			480			
+ 81200220	CONDUIT EMBEDDED IN STRUCTURE, 1 1/2" DIA., PVC	FOOT	480			480												
+ 81300320	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 8"X8"X6"	EACH	4									4						
+ 81300980	JUNCTION BOX, STAINLESS STEEL, EMBEDDED IN STRUCTURE, 8"X8"X6"	EACH	4									4						
+ 81303950	JUNCTION BOX EMBEDDED IN STRUCTURE, 6"X6"X6"	EACH	4									4						
+ 81400400	CONCRETE HANDHOLE	EACH	3											3				
+ 81500200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	1,365			120	60							920	265			
+ 81700120	ELECTRIC CABLE IN CONDUIT, 600V (EPR-TYPE RHW) 1/C NO. 6	FOOT	700									700						
+ 81700315	ELECTRIC CABLE IN CONDUIT, 600V (EPR-TYPE RHW) 3-1/C NO. 10	FOOT	330									330						
+ 81700325	ELECTRIC CABLE IN CONDUIT, 600V (EPR-TYPE RHW) 3-1/C NO. 8	FOOT	400									400						
+ 81700355	ELECTRIC CABLE IN CONDUIT, 600V (EPR-TYPE RHW) 3-1/C NO. 2	FOOT	1,200			600								600				
+ 81701125	ELECTRIC CABLE IN CONDUIT, 600V (EPR-TYPE RHW) 1/C NO. 1/0	FOOT	800									800						
+ 81701145	ELECTRIC CABLE IN CONDUIT, 600V (EPR-TYPE RHW) 1/C NO. 3/0	FOOT	600									600						
+ 81800320	AERIAL CABLE, 3-1/C NO. 4 WITH MESSENGER WIRE	FOOT	540			540												
+ 82103250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, PHOTO-CELL CONTROL, 250 WATT	EACH	10			4								6				
+ 82103400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, PHOTO-CELL CONTROL, 400 WATT	EACH	2			2												
+ 83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	70											70				
+ 84100110	REMOVAL OF TEMPORARY LIGHTING UNITS	EACH	2			2												
+ 84200500	REMOVAL OF EXISTING LIGHTING UNIT, SALVAGE	EACH	22			9								13				
+ 85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	2												2			
+ 89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	2												2			
+ 89502350	REMOVE AND REINSTALL ELECTRIC CABLE FROM CONDUIT	FOOT	1,296												1,296			
+ 82004824	TREE, GLEDITSIA TRIACANTHOS INERMIS SKYLINE (SKYLINE THORNLESS COMMON HONEYLOCUST), 3" CALIPER, BALLED AND BURLAPPED	EACH	6											6				
* X0301766	DRILL AND GROUT #6 TIE BARS	EACH	79										79					
+ X0320591	SANITARY MANHOLES TO BE REMOVED	EACH	1													1		
* X0321907	STORM SEWERS, TYPE 2, WATER MAIN QUALITY PIPE, 12"	FOOT	70											70				
* X0321908	STORM SEWERS, TYPE 2, WATER MAIN QUALITY PIPE, 15"	FOOT	39											39				
* X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	80	80														
* X0322671	STABILIZED CONSTRUCTION ENTRANCE	SQ YD	260		260													
+ X0322782	SANITARY SEWER, PVC (D3034) SDR 26, 8"	FOOT	75													75		
+ X0322925	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	870													870		
* X0323353	GATE VALVES, 10"	EACH	2													2		
* X0323396	HIGH PERFORMANCE CONCRETE STRUCTURES	CU YD	1,698	68						1,630								
* X0323830	DRAINAGE SCUPPERS, DS-11	EACH	8	8														

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 WILSON STREET
 SUMMARY OF QUANTITIES

SCALE: NTS
 DATE: 07/28/2006

DRAWN BY: WAJ
 CHECKED BY: AKK

PLOT DATE: 08/28/2006
 FILE NAME: #FILEL#
 PLOT SCALE: #SCALE#
 USER NAME: #USER#

+ SPECIALTY ITEMS

C:\PROGRA~1\Autocad\acad... 08/28/2006 04:03:48 PM