

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1441	00-00059-00-BR	KANE	154	10
STA. N/A		TO STA. N/A		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

THERMOPLASTIC PAVEMENT MARKINGS

FROM STATION	TO STATION	LETTERS & SYMBOLS	LINE 4"			LINE 6"		LINE 12"	LINE 24"
			SOLID WHITE	SKIP-DASH WHITE	SOLID DOUBLE YELLOW	SOLID WHITE	DOTTED WHITE	SOLID WHITE	SOLID WHITE
		SQ. FT.	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT
7+00.00	10+37.42	145.6	156.1	213.5	409.1	661.1	143.8	78.6	101.2
15+72.69	20+00.00	145.6	271.1		339.0	478.6	229.6	243.3	131.3
FACTOR:		1	1	0.25	2	1	.25	1	1
PROJECT TOTAL:		291.2	427.2	53.4	1,496.2	1,139.7	93.4	321.9	232.5
COMBINED PROJECT TOTAL:		291.2			1,976.8		1,233.1	321.9	232.5

EPOXY PAVEMENT MARKINGS

FROM STATION	TO STATION	LETTERS & SYMBOLS	LINE 4"			LINE 6"		LINE 12"	LINE 24"
			SOLID WHITE	SKIP-DASH WHITE	SOLID DOUBLE YELLOW	SOLID WHITE	DOTTED WHITE	SOLID WHITE	SOLID WHITE
		SQ. FT.	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	
10+37.42	15+72.69	145.6	306.7		535.5	462.9	447.2	59.0	
FACTOR:		1	1	.25	2	1	0.25	1	
PROJECT TOTAL:		145.6	306.7		1,071.0	462.9	111.8	59.0	
COMBINED PROJECT TOTAL:		145.6			1,377.7		574.7	59.0	

PAVEMENT MARKING REMOVAL

FROM STATION	TO STATION	PAVEMENT MARKING REMOVAL
		SQ. FT.
7+00.00	10+37.42	740.7
10+37.42	15+72.69	88.4
15+72.69	20+00.00	1,038.9
PROJECT TOTAL:		1,868.0
COMBINED PROJECT TOTAL:		1,868.0

TEMPORARY PAVEMENT MARKINGS

	LETTERS & SYMBOLS	LINE 4"			LINE 6"		LINE 12"		LINE 24"	WORK ZONE PAVEMENT MARKING REMOVAL			
		SOLID WHITE	SKIP-DASH WHITE	DOTTED WHITE	DOTTED YELLOW	SOLID DOUBLE YELLOW	SOLID WHITE	DOTTED WHITE	SOLID WHITE		SOLID YELLOW	SOLID WHITE	
		SQ. FT.	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	SQ. FT.		
STAGE 1		109.2	1,188.3	116.4		209.5	1,306.8	176.6	346.1	52.3	36.8	78.7	1,781.7
STAGE 2		109.2	1,096.8	61.6	66.4	87.0	1,030.1	240.9	305.6	111.6		79.3	1,608.3
STAGE 3		218.4	781.9	214.7		87.0	670.2	307.5	369.7	105.1	27.2		66.6
FACTOR:		1	1	0.25		0.25	0.25	2	1	0.25	1		1
PROJECT TOTAL:		436.8	3,067.0	98.2	16.6	95.9	6,014.2	725.0	255.4	269.0	64.0	224.6	4,806.5
COMBINED PROJECT TOTAL:		436.8					9,292.0		980.4		333.0	224.6	4,806.5

PLOT DATE = 09/14/2006
 FILE NAME = 8FILEL
 PLOT SCALE = 8SCALE
 USER NAME = 8USER

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 WILSON STREET
 PAVEMENT MARKINGS
 SCHEDULE

SCALE: NTS
 DATE 07/28/2006

DRAWN BY WAJ
 CHECKED BY AKK

I:\2006\ACT11\TEMP\MARKING.DWG 09/14/2006 10:28:38 AM