



- LEGEND**
- ① CONCRETE PAVERS, TYPE A
 - ② COMPACTED BEDDING SAND, 1"
 - ③ P.C.C. SIDEWALK, 5"
 - ④ REINFORCED P.C.C. SIDEWALK, VARIABLE DEPTH
 - ⑤ REINFORCED P.C.C. SIDEWALK, VARIABLE DEPTH WITH DEPRESSION FOR PAVERS
 - ⑥ P.C.C. CURB, 6"x18"
 - ⑦ GRANULAR SUBBASE, TYPE B, 4"
 - ⑧ 2" DIA. WEEP HOLE
 - ⑨ PREFORMED JOINT FILLER, 3/4"
 - ⑩ SELF-LEVELING SILICONE SEALANT
 - ⑪ PROPOSED RETAINING WALL
 - ⑫ PROPOSED BRIDGE ABUTMENT
 - ⑬ PROPOSED STAIRS
 - ⑭ EXISTING BUILDING
 - ⑮ EXISTING PAVEMENT
 - ⑯ LANDSCAPING
 - ⑰ SIDEWALK DRAIN
 - ⑱ PVC UNDERDRAIN, 4"
- NOTES:**
1. CONTRACTOR TO VERIFY DIMENSIONS FOR TOTAL DEPTH OF CONCRETE PAVERS AND COMPACTED SAND LAYER WITH CONCRETE PAVER MANUFACTURER FOR EACH STYLE OF CONCRETE PAVER PRIOR TO CONSTRUCTION.
 2. STEEL REINFORCED P.C.C. SIDEWALK TO HAVE REINFORCEMENT CONSISTING OF NO. 5 EPOXY COATED DEFORMED STEEL REINFORCING BARS PLACED AT 6" CENTERS IN THE LONGITUDINAL AND TRANSVERSE DIRECTIONS AT THE TOP AND BOTTOM OF THE SIDEWALK WITH A MINIMUM COVER OF 3" FROM THE CONCRETE SURFACE.
 3. STEEL REINFORCED P.C.C. SIDEWALK TO HAVE FULL-DEPTH DOWELED JOINTS SPACED AT 15' MINIMUM. THE REINFORCING STEEL SHALL NOT CONTINUE THROUGH THE JOINTS, A COVER OF 3" FROM THE JOINT SHALL BE MAINTAINED.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 WILSON STREET
 RIVERWALK DETAILS AND SECTIONS

SCALE: NTS
 DATE 07/28/2006

DRAWN BY WAJ
 CHECKED BY AKK

PLOT DATE: 7/28/2006
 FILE NAME: T:\2006\1441\144100059-00-BH\144100059-00-BH.dgn
 PLOT SCALE: 1/8"=1'-0"
 USER: WAJ