INDEX OF SHEETS

INDI	EX OF SHEETS		
CUEET NO		000001-04	ABBREVIATIONS, SYMBOLS AND PATTERNS LIST STANDARDS FOR ALL TRAFFIC BARRIER TERMINALS
SHEET NO.	TITLE	280001-02 420401-05	TEMPORARY EROSION CONTROL SYSTEMS BRIDGE APPROACH PAVEMENT NAME PLATE FOR BRIDGES CONCRETE HEADWALL FOR PIPE DRAIN STEEL PLATE BEAM GUARD RAIL PCC/BITUMINOUS STABILIZATION AT STEEL BEAM GUARDRAIL SHOULDER WIDENING FOR TYPE I (SPECIAL) GUARDRAIL TERMINALS TRAFFIC BARRIER TERMINAL, TYPE 2 TRAFFIC BARRIER TERMINAL, TYPE 6A REFLECTOR & TERMINAL MARKER PLACEMENT REFLECTOR MARKING & MOUNTING DETAILS TRAFFIC CONTROL DEVICES
1	COVER SHEET	515001-02	
2	INDEX OF SHEETS/GENERAL NOTES	601101 630001-06 630201-03	
3	SUMMARY OF QUANTITIES	630201-03 630301-03 631011-02 631032-02 635006-02	
4-7	TYPICAL SECTIONS		
8	SCHEDULES OF QUANTITIES	635006-02 635011-01 702001-0%	
9	CONTROL POINT TIE-OFFS	102001-00	TRAFFIC CONTROL DEVICES
10	ALIGNMENT AND BENCHMARKS		
11-13	PLAN AND PROFILE SHEETS		
14	DETOUR SIGNING		DISTRICT ONE STANDARDS
15	DETOUR PLAN	BD 32	BUTT JOINT AND BITUMINOUS TAPER
16-17	EROSION AND SEDIMENT CONTROL PLAN	BD 34	DETAILS FOR STEEL PLATE BEAM GUARDRAIL ADJACENT TO CURB AND GUTTER STABILIZATION AT TBT TY 1 SPL.
18-22	RIGHT-OF-WAY PLAT	BD 51 TC 22	BENCHING DETAIL FOR EMBANKMENT WIDENING TEMPORARY INFORMATION SIGNING
23	BRIDGE GENERAL PLAN		
24	SUPERSTRUCTURE PLAN AND DETAILS		
25	SUPERSTRUCTURE		BUREAU OF LOCAL ROADS STANDARDS
26	ABUTMENT AND WINGWALL DETAILS	BLR 21-6	TYPICAL APPLICATION OF TRAFFIC CONTROL DEVICES FOR CONSTRUCTION ON RURAL LOCAL HIGHWAYS
27	PILE DETAILS	BLR 22-4	TYPICAL APPLICATION OF TRAFFIC CONTROL DEVICES FOR CONSTRUCTION ON RURAL LOCAL HIGHWAYS (TWO-LANE
28	RAILING	RI D 25	TWO WAY RURAL TRAFFIC)  BLR 25 TYPE 1A BARRICADE FOR NON-NHS ROUTES
29-32	DISTRICT DETAILS	DEN 23	
33-37	CROSS SECTIONS		
(38)	EXISTING BRIDGE DRAWING		$\vec{s}$

HIGHWAY STANDARDS

Added 10-20-06

## GENERAL NOTES

- ALL CLEARING AND GRUBBING AND REMOVAL OF EXISTING DRAINAGE STRUCTURES AND PIPES ENCOUNTERED ARE TO BE INCLUDED IN THE UNIT PRICE BID FOR EARTH EXCAVATION EXCEPT AS NOTED ON THE PLANS.
- THE LOCATIONS AND ELEVATION OF THE VARIOUS UNDERGROUND UTILITIES AS SHOWN ON THE PLANS ARE APPROXIMATE. THE CONTRACTOR SHALL USE SPECIAL CARE WHEN CONDUCTING CONSTRUCTION OPERATIONS NEAR THEM AND IS RESPONSIBLE FOR ANY DAMAGE THAT MAY BE CAUSED. PLEASE REFER TO THE SPECIAL PROVISIONS FOR COOPERATION WITH UTILITIES (LR 105) IN THE SPECIAL PROVISIONS SECTION OF THE CONTRACT.
- 48 HOURS PRIOR TO THE START OF ANY EXCAVATION, THE CONTRACTOR SHALL CALL J.U.L.I.E. FOR VERIFICATION OF ALL UTILITY LOCATIONS IN THE FIELD.
- THE CONTRACTOR SHALL COORDINATE WITH ALL ABOVE AND UNDERGROUND UTILITY COMPANIES IF UTILITIES NEED TO BE RELOCATED.
- WHERE SECTION OR SUB-SECTION MONUMENTS ARE ENCOUNTERED, THE ENGINEER SHALL BE NOTIFIED BEFORE SUCH MONUMENTS ARE REMOVED. THE CONTRACTOR SHALL PROTECT AND CAREFULLY PRESERVE ALL PROPERTY MARKS AND MONUMENTS UNTIL THE OWNER, AN AUTHORIZED SURVEYOR OR AGENT HAS WITNESSED OR OTHERWISE REFERENCED THEIR LOCATION. THE CONTRACTOR WILL BE RESPONSIBLE FOR HAVING AN AUTHORIZED SURVEYOR REESTABLISH ANY SECTION OR SUB-SECTION MONUMENTS DISRUPTED BY HIS/HER
- THE AREA TO BE SEEDED SHALL CONSIST OF ALL DISTURBED EARTH SURFACES WITHIN THE RIGHT-OF-WAY AS DIRECTED BY THE ENGINEER. SEEDING SHALL BE PLACED WITHIN 7 DAYS OF THE CESSATION OF EARTHWORK.
- 7. THE FOLLOWING RATES OF APPLICATION HAVE BEEN USED IN CALCULATING PLAN QUANTITIES BITUMINOUS CONCRETE 112 LB./IN./SQ.YD AGGREGATE SHOULDERS, TYPE B 2.05 TON/CU.YD BITUMINOUS MATERIALS (PRIME COAT) O.10 GAL/SQ YD
- 8. ALL AGGREGATES SHALL BE 100% CRUSHED MATERIAL.
- ALL EXISTING TOPSOIL WITHIN THE LIMITS OF EARTH EXCAVATION AND/OR EMBANKMENT SHALL BE STRIPPED, STOCKPILED AND RESPREAD. THIS WORK SHALL BE IN ACCORDANCE
- BARRICADES: ALL UNBALLASTED TYPE I AND TYPE II BARRICADES SHALL HAVE A MINIMUM OF TWO (2) SANDBAGS ON THE BOTTOM RAIL. A TYPE III BARRICADE SHALL REQUIRE A MINIMUM OF FOUR (4) SANDBAGS.
- 11. THE CONTRACTOR SHALL BE REQUIRED TO MAINTAIN ACCESS TO ALL PRIVATE AND COMMERICIAL PROPERTIES AT ALL TIMES DURING THE CONSTRUCTION OF THIS PROJECT.
- POROUS GRANULAR EMBANKMENT, SUBGRADE (PGE) HAS BEEN PROVIDED FOR SOILS THAT TEND TO BE UNSTABLE WHEN WET. THE ACTUAL NEED FOR THE REMOVAL AND REPLACEMENT WITH PGE WILL BE DETERMINED IN THE FIELD AT THE TIME OF CONSTRUCTION BY THE ENGINEER. IF UNSUITABLE SOILS ARE NOT ENCOUNTERED, THEN THE QUANTITY WILL BE DEDUCTED AND NO ADDITIONAL COMPENSATION WILL BE DUE THE CONTRACTOR.

NOTE: BOXED NOTES ARE INCIDENTAL ITEMS

Tevised 10/20/06

