


SUMMARY OF QUANTITIES						
CODE NO.	ITEM	UNIT	TOTAL QUANTITIES	ROADWAY 1000-2A	STRUCTURAL X071-2A	CITY OF NAPERVILLE (100% NON-PARTICIPATING)
50800515	BAR SPLICERS	EACH	186		186	
50900105	ALUMINUM RAILING, TYPE L	FOOT	154		154	
50901720	BICYCLE RAILING	FOOT	158.7	16.4	142.3	
50901750	PARAPET RAILING	FOOT	150		150	
51300205	TEMPORARY BRIDGE COMPLETE NO. 1	EACH	1		1	
51500100	NAME PLATES	EACH	1		1	
51602000	PERMANENT CASING	FOOT	82		82	
51603000	DRILLED SHAFT IN SOIL	CU YD	14.8		14.8	
51604000	DRILLED SHAFT IN ROCK	CU YD	1.5		1.5	
52000110	PREFORMED JOINT STRIP SEAL	FOOT	114		114	
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	14		14	
52100520	ANCHOR BOLTS, 1"	EACH	56		56	
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTION 12"	EACH	1	1		
550A0340	STORM SEWERS, CLASS A, TYPE 2, 12"	FOOT	282	282		
55100500	STORM SEWER REMOVAL 12"	FOOT	26	26		
55100700	STORM SEWER REMOVAL 15"	FOOT	5	5		
58700200	BRIDGE SEAT SEALER	SQ FT	200		200	
58700300	CONCRETE SEALER	SQ FT	1317		1317	
59000200	EPOXY CRACK INJECTION	FOOT	205		205	
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	116		116	
59300100	CONTROLLED LOW-STRENGTH MATERIAL	CU YD	30			30
60200105	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	1	1		
60201105	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 11 FRAME AND GRATE	EACH	6	6		
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1		
60250200	CATCH BASINS TO BE ADJUSTED	EACH	4	4		
60255500	MANHOLES TO BE ADJUSTED	EACH	1	1		
60500060	REMOVING INLETS	EACH	1	1		
60604200	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12 (SPECIAL)	FOOT	458.5	458.5		
60609500	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.12 (SPECIAL)	FOOT	61.0	61.0		
63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	1	1		
63100167	TRAFFIC BARRIER TERMINAL, TYPE 1, SPECIAL (TANGENT)	EACH	1	1		
66410300	CHAIN LINK FENCE REMOVAL	FOOT	25	25		
66411900	TEMPORARY FENCE	FOOT	387	387		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	10		10	
67100100	MOBILIZATION	L SUM	1		0.8	0.2
70101800	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1		0.6	0.4
70102550	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	EACH	1	1		
70104490	TRAFFIC CONTROL AND PROTECTION (SPECIAL), LOCATION 1	EACH	2	1		1
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	20	20		
70300220	TEMPORARY PAVEMENT MARKING LINE - 4"	FOOT	3663	3663		
70300240	TEMPORARY PAVEMENT MARKING LINE - 6"	FOOT	96	96		
70300260	TEMPORARY PAVEMENT MARKING LINE - 12"	FOOT	3	3		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1272	1272		
70400100	TEMPORARY CONCRETE BARRIER	FOOT	400	400		
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	725	725		
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTER AND SYMBOLS	SQ FT	74	37		37
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	654	501		153
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	238	160		78
78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	26			26
78003110	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 4"	FOOT	336	336		
78003130	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 6"	FOOT	30	30		
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	20	20		
78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	6	6		
78200100	MONODIRECTIONAL PRISMATIC BARRIER REFLECTOR	EACH	22	22		
78300100	PAVEMENT MARKING REMOVAL	SQ FT	460	460		
87900100	DRILL EXISTING FOUNDATION	EACH	1			1
X0322102	TEMPORARY SIDEWALK RAMP	EACH	2	2		
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	450	450		
X0322671	STABILIZED CONSTRUCTION ENTRANCE	SQ YD	170	170		
X0322923	SEGMENTAL CONCRETE BLOCK WALLS	SQ FT	190		30	160
X0323080	DRAINAGE SCUPPERS, DS-12	EACH	12		12	
X0323426	SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER CLEANING	EACH	14	14		
X0323988	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	933		933	
X0324973	REMOVE AND REPLACE BITUMINOUS SURFACE, SPECIAL	SQ FT	6360			6360
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	28		28	

• - SPECIALTY ITEM

<b>REVISIONS</b> NAME      DATE      		BRIDGE REHABILITATION BAILEY ROAD OVER WEST BRANCH OF THE DUPAGE RIVER  <b>SUMMARY OF QUANTITIES</b> (2 OF 3)	City of  <b>Naperville</b>
CONSULTANT <b>TYLIN INTERNATIONAL</b>			DRAWN: RTM CHECKED: SP APPROVED: DATE: OCTOBER 4, 2007 SCALE: NONE JOB NO.: C-91-062-04
			SHEET NO. <div style="font-size: 2em; text-align: center;">4</div> PROJECT NO.: BHM-8003(343)