


SUMMARY OF QUANTITIES

| CODE NO. | ITEM | UNIT | TOTAL QUANTITIES | ROADWAY 1000-2A | STRUCTURAL X071-2A | CITY OF NAPERVILLE (100% NON-PARTICIPATING) |
|----------|---|-------|------------------|-----------------|--------------------|---|
| X0329891 | SILT CURTAIN | SQ YD | 76 | 76 | | |
| X4021000 | TEMPORARY ACCESS (PRIVATE ENTRANCE) | EACH | 3 | 1 | | 2 |
| X4022000 | TEMPORARY ACCESS (COMMERCIAL ENTRANCE) | EACH | 4 | 1 | | 3 |
| X5020501 | UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 1 | EACH | 1 | | 1 | |
| X5020502 | UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 2 | EACH | 1 | | 1 | |
| XX000372 | TEMPORARY AGGREGATE | TON | 71 | 71 | | |
| XX000504 | RESTORATION WORK | L SUM | 1 | | | 1 |
| XX003435 | PORTLAND CEMENT CONCRETE DRIVEWAY REMOVAL AND REPLACEMENT | SQ YD | 250 | 85 | | 165 |
| XX004102 | CONCRETE RIPRAP REMOVAL | SQ YD | 14 | 14 | | |
| XX004238 | BITUMINOUS DRIVEWAY REMOVAL AND REPLACEMENT | SQ YD | 250 | | | 250 |
| XX004804 | CONDUIT IN TRENCH, TRANSITION | EACH | 2 | | | 2 |
| XX004809 | UNDER BRIDGE CONDUIT SYSTEM | L SUM | 1 | | | 1 |
| XX005581 | VIDEO TAPE | UNIT | 1 | | | 1 |
| XX005593 | NEW SWITCH GEAR VAULT | EACH | 4 | | | 4 |
| XX005594 | FA-2 ENCASEMENT | CU YD | 200 | | | 200 |
| XX005595 | TRENCH BACKFILL, CA-6 | CU YD | 320 | | | 320 |
| XX005596 | CONNECTING TO EXISTING SWITCHGEAR VAULTS OR FUSE CANS | EACH | 1 | | | 1 |
| XX005598 | ADDITIONAL GROUND ROD INSTALLATION | EACH | 5 | | | 5 |
| XX005600 | COUNTERPOISE, UNPAVED | FOOT | 250 | | | 250 |
| XX005601 | COUNTERPOISE, PAVED | FOOT | 30 | | | 30 |
| XX005602 | HAND DIGGING, 0 FT TO 5 FT IN PAVEMENT | CU YD | 20 | | | 20 |
| XX005603 | HAND DIGGING, 5 FT TO 20 FT IN PAVEMENT | CU YD | 10 | | | 10 |
| XX005604 | HAND DIGGING, 0 FT TO 5 FT IN UNPAVED AREAS | CU YD | 45 | | | 45 |
| XX005605 | HAND DIGGING, 5 FT TO 20 FT IN UNPAVED AREAS | CU YD | 20 | | | 20 |
| XX005612 | HANDHOLE, DEH8 | EACH | 4 | | | 4 |
| XX006223 | PERIMETER EROSION BARRIER, MODIFIED | FOOT | 830 | 830 | | |
| XX006444 | MULCH, SPECIAL | ACRE | 0.25 | | | 0.25 |
| XX007052 | CONDUIT RISER ASSEMBLY - 5 INCH | EACH | 1 | | | 1 |
| XX007053 | CONDUIT RISER ASSEMBLY - 6 INCH | EACH | 2 | | | 2 |
| XX007054 | HANDHOLE, DEH5 | EACH | 2 | | | 2 |
| XX007055 | HANDHOLE, DEH6 | EACH | 3 | | | 3 |
| Z0001900 | ASBESTOS BEARING PAD REMOVAL | EACH | 120 | | 120 | |
| Z0013798 | CONSTRUCTION LAYOUT | L SUM | 1 | | 0.8 | 0.2 |
| Z0030020 | IMPACT ATTENUATORS, (FULLY REDIRECTIVE, NARROW), TEST LEVEL 2 | EACH | 1 | 1 | | |
| Z0030255 | IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 2 | EACH | 2 | 2 | | |
| Z0030320 | IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 2 | EACH | 2 | 2 | | |
| Z0053700 | RESETTING SURVEY MONUMENTS | EACH | 1 | | 1 | |
| Z0076600 | TRAINEES | HOUR | 1000 | 1000 | | |
| XX007130 | 2 WAY - 3" PVC DUCT BANK - 1 HIGH BY 2 WIDE | FOOT | 180 | | | 180 |
| XX007139 | 4 WAY - 3" PVC DUCT BANK - 1 HIGH BY 4 WIDE | FOOT | 55 | | | 55 |
| XX007140 | 2 WAY - 5" PVC DUCT BANK - 1 HIGH BY 2 WIDE | FOOT | 660 | | | 660 |
| XX007141 | 2 WAY - 6" PVC DUCT BANK - 1 HIGH BY 2 WIDE | FOOT | 1555 | | | 1555 |
| XX007142 | 4 WAY - 6" PVC DUCT BANK - 1 HIGH BY 4 WIDE | FOOT | 760 | | | 760 |
| XX007143 | 6 WAY - 6" PVC DUCT BANK - 1 HIGH BY 6 WIDE | FOOT | 490 | | | 490 |
| XX007144 | 6 WAY - 2-6", 2-5", 2-3" PVC DUCT BANK - 2 HIGH BY 3 WIDE | FOOT | 150 | | | 150 |
| XX007145 | 6 WAY - 2-5", 4-3" PVC DUCT BANK - 2 HIGH BY 3 WIDE | FOOT | 50 | | | 50 |

△ Y080

* - SPECIALTY ITEM

| <table border="1"> <thead> <tr><th colspan="2">REVISIONS</th></tr> <tr><th>NAME</th><th>DATE</th></tr> </thead> <tbody> <tr><td> </td><td> </td></tr> <tr><td> </td><td> </td></tr> <tr><td> </td><td> </td></tr> <tr><td> </td><td> </td></tr> </tbody> </table> | REVISIONS | | NAME | DATE | | | | | | | | | BRIDGE REHABILITATION BAILEY ROAD OVER WEST BRANCH OF THE DUPAGE RIVER SUMMARY OF QUANTITIES (3 OF 3) | City of |  Naperville |
|---|---------------------|----------------------|-------------|----------|-----------|-----------------------|-------------|----------------------------|--|--|--|--|--|---------|--|
| | REVISIONS | | | | | | | | | | | | | | |
| | NAME | DATE | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| <table border="1"> <tr><td>DRAWN: RTM</td><td>SHEET NO.</td></tr> <tr><td>CHECKED: SP</td><td rowspan="4" style="text-align: center; font-size: 2em;">5</td></tr> <tr><td>APPROVED:</td></tr> <tr><td>DATE: OCTOBER 4, 2007</td></tr> <tr><td>SCALE: NONE</td></tr> </table> | DRAWN: RTM | SHEET NO. | CHECKED: SP | 5 | APPROVED: | DATE: OCTOBER 4, 2007 | SCALE: NONE | PROJECT NO.: BHM-8003(343) | | | | | | | |
| DRAWN: RTM | SHEET NO. | | | | | | | | | | | | | | |
| CHECKED: SP | 5 | | | | | | | | | | | | | | |
| APPROVED: | | | | | | | | | | | | | | | |
| DATE: OCTOBER 4, 2007 | | | | | | | | | | | | | | | |
| SCALE: NONE | | | | | | | | | | | | | | | |
| CONSULTANT | TYLIN INTERNATIONAL | JOB NO.: C-91-062-04 | | | | | | | | | | | | | |