

SPECIALTY ITEM &/OR SPECIAL PROVISION	CODE NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE		
					X571-2A	Y030-1E	Y080
Δ	60228120	MANHOLES, SANITARY, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	3	3	0	0
Δ	60234200	INLETS, TYPE A, TYPE 1 FRAME, OPEN LID	EACH	2	2	0	0
Δ	60235700	INLETS, TYPE A, TYPE 3 FRAME AND GRATE	EACH	2	2	0	0
Δ	60236700	INLETS, TYPE A, TYPE 10 FRAME AND GRATE	EACH	5	5	0	0
Δ	60236800	INLETS, TYPE A, TYPE 11 FRAME AND GRATE	EACH	16	16	0	0
Δ	60240210	INLETS, TYPE B, TYPE 1 FRAME, OPEN LID	EACH	1	1	0	0
Δ	60240215	INLETS, TYPE B, TYPE 1 FRAME, CLOSED LID	EACH	4	4	0	0
Δ	60240220	INLETS, TYPE B, TYPE 3 FRAME AND GRATE	EACH	2	2	0	0
Δ	60240305	INLETS, TYPE B, TYPE 10 FRAME AND GRATE	EACH	1	1	0	0
Δ	60240310	INLETS, TYPE B, TYPE 11 FRAME AND GRATE	EACH	9	9	0	0
Δ	60247130	DRAINAGE STRUCTURES, TYPE 1 WITH ONE TYPE 20 FRAME AND GRATE	EACH	4	4	0	0
Δ	60247160	DRAINAGE STRUCTURES, TYPE 1 WITH TWO TYPE 20 FRAMES AND GRATES	EACH	4	4	0	0
Δ	60260050	SANITARY MANHOLES TO BE RECONSTRUCTED	EACH	4	4	0	0
Δ	60260100	INLETS TO BE ADJUSTED	EACH	1	1	0	0
Δ	60500040	REMOVING MANHOLES	EACH	1	1	0	0
Δ	60500060	REMOVING INLETS	EACH	7	7	0	0
Δ	60602800	CONCRETE GUTTER, TYPE B	FOOT	445	445	0	0
Δ	60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	2414	2414	0	0
Δ	60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	412	412	0	0
Δ	60618320	CONCRETE MEDIAN SURFACE, 6"	SQ FT	2034	2034	0	0
	67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	24	24	0	0
	67100100	MOBILIZATION	L SUM	1	1	0	0
*	70101700	TRAFFIC CONTROL AND PROTECTION	L SUM	1	1	0	0
	70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DAY	40	40	0	0
	70300100	SHORT TERM PAVEMENT MARKING	FOOT	564	564	0	0
	70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	2365	2365	0	0
	70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	777	777	0	0
	70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	97	97	0	0
	70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1488	1488	0	0
Δ	78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	2659	2659	0	0
Δ	78005130	EPOXY PAVEMENT MARKING - LINE 6"	FOOT	777	777	0	0
Δ	78005180	EPOXY PAVEMENT MARKING - LINE 24"	FOOT	97	97	0	0

SPECIALTY ITEM &/OR SPECIAL PROVISION	CODE NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE		
					X571-2A	Y030-1E	Y080
Δ	80400100	ELECTRIC SERVICE INSTALLATION	EACH	1	0	1	0
Δ	81012600	CONDUIT IN TRENCH, 2" DIA. PVC	FOOT	90	0	90	0
	81200230	CONDUIT EMBEDDED IN STRUCTURE, 2" DIA. PVC	FOOT	1100	0	1100	0
Δ	81301200	JUNCTION BOX, STAINLESS STEEL, EMBEDDED IN STRUCTURE 12"x10"x6"	EACH	2	0	2	0
Δ	81702120	ELECTRIC CABLE IN CONDUIT, 600V (XLP TYPE USE) 1/C NO. 8	FOOT	610	0	610	0
Δ	81702130	ELECTRIC CABLE IN CONDUIT, 600V (XLP TYPE USE) 1/C NO. 6	FOOT	2650	0	2650	0
Δ	81702140	ELECTRIC CABLE IN CONDUIT, 600V (XLP TYPE USE) 1/C NO. 4	FOOT	3925	0	3925	0
Δ	82104500	LUMINAIRE, SODIUM VAPOR, RECTILINEAR TYPE, 250 WATT	EACH	9	0	9	0
Δ	X0321072	BRIDGE FENCE RAILING	FOOT	380	0	380	0
Δ	X0321598	MANHOLES, TYPE A, 6"-DIAMETER, WITH 2 TYPE 1 FRAME, CLOSED LID, RESTRICTOR PLATE	EACH	1	1	0	0
	X0323558	BRIDGE JOINT SYSTEM (EXPANSION), 1-5/8"	FOOT	39	39	0	0
	X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N=50	TON	61	61	0	0
	X5000350	FLOATING BEARINGS, FIXED 350K	EACH	6	6	0	0
	X5005350	FLOATING BEARINGS GUIDE EXPANSION 350K	EACH	6	6	0	0
* Δ	X5510100	STORM SEWER REMOVAL	FOOT	243	243	0	0
Δ	XX002082	SANITARY SEWER REMOVAL 24"	FOOT	127	127	0	0
	XX004056	MECHANICALLY STABILIZED EARTH RETAINING WALL	SQ FT	24680	24680	0	0
* Δ	XX005084	LIGHTING CONTROLLER FOUNDATION	EACH	1	0	1	0
* Δ	XX005810	LIGHTING CONTROLLER, TYPE CB-RCS, 200A - 240 DUAL	EACH	1	0	1	0
	Z0002600	BAR SPLICERS	EACH	908	908	0	0
	Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	0	0
*	Z0022800	FENCE REMOVAL	FOOT	58	58	0	0
	Z0036600	PARAPET RAILING	FOOT	1747	1747	0	0
	Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1	0	0
Δ	Z0060200	SANITARY SEWER, TYPE 2 24"	FOOT	140	140	0	0
	Z0076600	TRAINEES	FOOT	1000	0	0	1000
Δ	XX006617	LIGHT POLE, ALUMINUM, 30 FT. MH, 1.5 FT. MAST ARM	EACH	9	0	9	0
	XX006628	FILTER FABRIC - INLET PROTECTION	EACH	43	43	0	0
* Δ	X0321907	STORM SEWERS, TYPE 2, WATER MAIN QUALITY PIPE, 12"	FOOT	694	694	0	0

Δ = SPECIALTY ITEM / \* = SPECIAL PROVISION

SUMMARY OF QUANTITIES (SHEET 2 OF 2)