F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
6145	01-00590-00-BR	LaSALLE	168	18
STA. N/A		TO STA. N/A		
FED. ROAD DIST. NO. 3	ILLINOIS	FEDERAL AID PROJECT		

CONTRACT NO. 87293

STORM SEWER

STATION	OFFSET	TYPE	STORM SEWERS: RUBBER GASKET, CLASS A: TYPE 1 12"	STORM SEWERS: RUBBER GASKET, CLASS A: TYPE 1 48"	STORM SEWERS: RUBBER GASKET, CLASS A: TYPE 2 12"	STORM SEWERS: RUBBER GASKET, CLASS A: TYPE 2 18"	STORM SEWERS: RUBBER GASKET, CLASS A: TYPE 2 24"	STORM SEWERS: PVC (WATER MAIN QUALITY) TYPE 2, SPECIAL 12"	MANHOLES: TYPE A, 4' DIA.: TYPE 1 FRAME CLID	MANHOLES: TYPE A, 4' DIA.: TYPE 10 F & G	MANHOLES: TYPE A, 4' DIA.: TYPE 11 F & G	MANHOLES: TYPE A, 5' DIA.: TYPE 1 FRAME CLID	MANHOLES: TYPE A, 6' DIA.: TYPE 1 FRAME CLID	MANHOLES: TYPE A, 6' DIA.: W/2 - TYPE 1 FRAMES CLID RESTRICTOR PLATE	INLETS: TYPE A, 2' DIA.: TYPE 1 FRAME OLID	INLETS: TYPE A, 2' DIA.: TYPE 3 F & G	INLETS: TYPE A, 2' DIA.: TYPE 10 F & G	INLETS: TYPE A, 2' DIA.: TYPE 11 F & G	INLETS: TYPE B, 3' DIA.: TYPE 1 FRAME OLID	INLETS: TYPE B, 3' DIA.: TYPE 1 FRAME CLID	INLETS: TYPE B, 3' DIA.: TYPE 3 F & G	INLETS: TYPE B, 3' DIA.: TYPE 10 F & G	INLETS: TYPE B, 3' DIA.: TYPE 11 F & G	DRAINAGE STRUCTURES TYPE 1: W/1 - TYPE 20 F & G	DRAINAGE STRUCTURES TYPE 1: W/2 - TYPE 20 F & G	TRENCH BACKFILL
			FOOT						EACH						EACH										CU YD
N.W. FRONTAGE RD.																									
18+60.00	35.08 LT.	INLET																1							
		SS			10																				3
18+70.00	38.58 LT.	INLET																	1						
		SS			92.00																				34
19+65.00	38.58 LT.	MANHOLE							1																
		SS			68																				27
19+30.00	35.08 LT.	INLET																1							
		SS	14																						3
19+45.00	35.08 LT.	INLET																					1		
		SS	12																						3
19+60.00	35.08 LT.	INLET																					1		
		SS			4																				1
S.W. FRONTAGE RD.																									
18+75.00	42.58 RT.	INLET																1							
		SS			14.00																				4
18+90.00	46.08 RT.	INLET																	1						
		SS			58.00																				34
19+50.00	46.08 RT.	MANHOLE							1																
		SS			24																				14
19+45.00	42.58 LT.	INLET																1							
		SS			4																				1
19+75.00	56.54 LT.	MANHOLE							1																
		SS			56																				31
19+60.00	43.61 RT.	INLET														1									
		SS			14																				4
19+75.00	47.34 RT.	INLET																		1					
		SS			6																				3
ILLINOIS ST.																									
84+44.06	31.17 RT.	EXIST. M.H.																							
		SS					10.00																		
84+52.50	19.00 RT.	MANHOLE										1													
		SS					8.00																		
84+64.56	19.00 RT.	MANHOLE												1											
		SS		340.00																					
88+10.00	19.00 RT.	MANHOLE											1												
		SS			8.00																				
88+20.00	13.75 RT.	MANHOLE								1															
		SS			26.00																				7
88+20.00	15.00 LT.	INLET																		1					
		SS	34.00																						7
88+55.00	25.00 LT.	INLET													1										
		SS					76.0																		
88+90.00	19.00 RT.	MANHOLE										1													
		SS			8.0																				
89+00.00	13.75 RT.	INLET															1								
		SS					46.0																		
89+40.00	19.00 RT.	MANHOLE										1													
		SS				98.0																			
90+40.00	23.50 RT.	MANHOLE							1																
91+08.00	23.00 LT.	INLET														1									
		SS	12.0																						2

STORM SEWER SCHEDULE CONTINUED ON NEXT SHEET