

80% FED
20% STATE

80% FED
10% STATE
10% CITY

80% FED
20% STATE

80% FED
10% STATE
10% CITY

CODE NUMBER	SUMMARY OF QUANTITIES ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	URBAN CONSTRUCTION TYPE CODE	
				I000-2A	Y031-1F
				ROADWAY	TRAFFIC SIGNALS
M2010110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	657	657	
M2010210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	1921	1921	
M2010500	TREE REMOVAL, HECTARES	HA	0.043	0.043	
M2020010	EARTH EXCAVATION	CU M	23361	23361	
M2060110	GRANULAR EMBANKMENT, SPECIAL	M TON	1,555	1,555	
M2080150	TRENCH BACKFILL	CU M	207.4	207.4	
M2112500	TOPSOIL EXCAVATION AND PLACEMENT	CU M	2243	2243	
M2113100	TOPSOIL FURNISH AND PLACE, 100 MM	SQ M	12,740	12,740	
* M2500100	SEEDING, CLASS 1	HA	0.360	0.360	
* M2500210	SEEDING, CLASS 2A	HA	2.94	2.94	
* M2500400	NITROGEN FERTILIZER NUTRIENT	KG	345	345	
* M2500500	PHOSPHOROUS FERTILIZER NUTRIENT	KG	345	345	
* M2500600	POTASSIUM FERTILIZER NUTRIENT	KG	345	345	
* M2510120	MULCH, METHOD 2	M TON	19.7	19.7	
M2510630	EROSION CONTROL BLANKET	SQ M	9141	9141	
* M2520100	SODDING	SQ M	660	660	
* M2520110	SODDING, SALT TOLERANT	SQ M	1485	1485	
M2520200	SUPPLEMENTAL WATERING	UNIT	98.1	98.1	
M2800255	TEMPORARY EROSION CONTROL SEEDING	HA	2.0	2.0	
28000300	TEMPORARY DITCH CHECKS	EACH	110	110	
M2800400	PERIMETER EROSION BARRIER	METER	1989	1989	
28000500	INLET AND PIPE PROTECTION	EACH	70	70	
M2810807	STONE DUMPED RIPRAP, CLASS A4	M TON	21.4	21.4	
M2820200	FILTER FABRIC	SQ M	30	30	
M3110300	SUB-BASE GRANULAR MATERIAL, TYPE A 300MM	SQ M	21,787	21,787	
M3110460	SUB-BASE GRANULAR MATERIAL, TYPE A 460MM	SQ M	14,420	14,420	
M4021010	AGGREGATE SURFACE COURSE, TYPE B	M TON	346	346	
M4060200	BITUMINOUS MATERIALS (PRIME COAT)	M TON	22.1	22.1	
M4060300	AGGREGATE (PRIME COAT)	M TON	152.5	152.5	
M4060855	CONSTRUCTING TEST STRIP	EACH	6	6	
M4060980	BITUMINOUS SURFACE REMOVAL-BUTT	SQ M	1135.9	1135.9	
M4060990	TEMPORARY RAMP	SQ M	76.7	76.7	
40702700	FURNISH PROFILOGRAPH	L SUM	1	1	
M4205200	PROTECTIVE COAT	SQ M	3178	3178	
M4230200	PCC DRIVEWAY PAVEMENT, 300MM	SC M	512	512	
M4401000	BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)	SQ M	3761.2	3761.2	
M4402000	PAVEMENT REMOVAL	SQ M	1601.7	1601.7	
M4402010	DRIVEWAY PAVEMENT REMOVAL	SQ M	1540.1	1540.1	

CODE NUMBER	SUMMARY OF QUANTITIES ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	URBAN CONSTRUCTION TYPE CODE	
				I000-2A	Y031-1F
				ROADWAY	TRAFFIC SIGNALS
M4402030	GUTTER REMOVAL	METER	59	59	
M4402040	COMBINATION CURB AND GUTTER REMOVAL	METER	116.7	116.7	
M4402050	SIDEWALK REMOVAL	SQ M	115	115	
M4402210	BITUMINOUS SHOULDER REMOVAL	METER	1190	1190	
M4402530	PAVED SHOULDER REMOVAL	SQ M	1738.4	1738.4	
M4428220	CLASS D PATCHES, TYPE II, 200MM	SQ M	30.9	30.9	
M4428440	CLASS D PATCHES, TYPE IV, 300MM	SQ M	54.0	54.0	
M4430020	STRIP REFLECTIVE CRACK CONTROL TREATMENT	METER	2023	2023	
M4812000	AGGREGATE SHOULDERS, TYPE B	M TON	1404	1404	
M4812150	AGGREGATE SHOULDERS, TYPE B 150MM	SQ M	1077.4	1077.4	
50104400	CONCRETE HEADWALL REMOVAL	EACH	6	6	
X5013800	PIPE CULVERT REMOVAL	EACH	25	25	
M5010521	REMOVE EXISTING CULVERTS	METER	64.5	64.5	
M542E012	END SECTIONS 300MM	EACH	2	2	
M542E020	END SECTIONS 450MM	EACH	8	8	
M542E028	END SECTIONS 600MM	EACH	4	4	
M542E112	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 300MM	EACH	5	5	
M542E116	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 375MM	EACH	1	1	
M542E120	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 450MM	EACH	8	8	
M542E128	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 600MM	EACH	4	4	
M542E628	PRECAST REINFORCED CONCRETE FLARED SECTIONS-ELLIPTICAL, EQUIVALENT ROUND SIZE 600MM	EACH	4	4	
M542E644	PRECAST REINFORCED CONCRETE FLARED SECTIONS- ELLIPTICAL, EQUIVALENT ROUND SIZE 900MM	EACH	2	2	
M542H030	PIPE CULVERTS, CLASS A, TYPE 1 450MM	METER	48	48	
M542H040	PIPE CULVERTS, CLASS A, TYPE 1 600MM	METER	40	40	
M542H220	PIPE CULVERTS, CLASS C, TYPE 1 300MM	METER	7	7	
M542H230	PIPE CULVERTS, CLASS C, TYPE 1 450MM	METER	48	48	
M542H240	PIPE CULVERTS, CLASS C, TYPE 1 600MM	METER	23.5	23.5	
M5421920	PIPE CULVERTS, TYPE 1, REINFORCED CONCRETE-ELLIPTICAL, EQUIVALENT ROUND-SIZE 600MM	METER	68	68	
M5421935	PIPE CULVERTS, TYPE 1, REINFORCED CONCRETE-ELLIPTICAL, EQUIVALENT ROUND-SIZE 900MM	METER	37	37	
M5500030	STORM SEWERS, CLASS A, TYPE 1 300MM	METER	132	132	
M5500050	STORM SEWERS, CLASS A, TYPE 1 450MM	METER	92	92	

RTE NO. FA 646	SECTION (Y)W-1, RS-3	COUNTY PEORIA	TOTAL 142	SHEET # 4
-------------------	-------------------------	------------------	--------------	--------------

* SPECIALTY ITEMS

† REFER TO THE JOINT CITY OF PEORIA - STATE AGREEMENT DATED _____ OF MONETARY PARTICIPATION OF EACH PARTY.

0-1

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

DRAWN BY: JDU
CHECKED BY: ECM

DATE: 09/01/06



Engineering As.

Macomb, IL

F.A. 646 IL RTE 40