

SIGNING				
LOCATION		SIGN STANDARD	SIGN PANEL-TYPE 1	WOOD SIGN SUPPORT
STATION	LT/RT		SQ M	METER
IL RTE 40				
14+010	LT	R2-1	0.5	5.0
14+029	RT	D1	0.2	4.6
14+072	LT	M1-I100	0.4	5.2
		M3-3	0.2	
14+131	RT	M1-I100	0.4	5.2
		M3-3	0.2	
14+178	LT	D-1	0.2	4.6
14+194	RT	R2-1	0.5	5.0
14+674	LT	R2-1	0.5	5.0
14+688	RT	D-1	0.2	4.6
14+737	LT	M1-I100	0.4	5.2
		M3-3	0.2	
14+795	RT	M1-I100	0.4	5.2
		M3-3	0.2	
14+842	LT	D-1	0.2	4.6
14+854	RT	R2-1	0.5	5.0
15+264	RT	R1-1	0.6	4.6
		R6-3A	0.3	
15+268	RT	2-D1	0.5	4.6
15+282	RT	W9-1	0.6	5.2
15+348	RT	W4-2	0.8	5.2
15+404	RT	W6-3	0.8	5.2
15+484	RT	W6-3	0.8	5.2
		D5-3	0.2	
15+715	LT.	R2-1	0.5	5.0
RICHMAR ROAD				
0+912	RT.	R1-1	0.6	4.6
FRONTAGE RD. #2				
2+012	LT	D5-3	0.2	4.6
2+014	LT	R1-1	0.6	4.6
2+403	RT	R1-1	0.6	4.6
SERVICE DRIVE #1				
12+462	LT	R1-1	0.6	4.6
MAST ARM SIGNS				
ALTA ROAD /				
FRONTAGE ROAD #2				
LOCATION G		D2-1	0.7	
LOCATION H		D2-1	0.7	
LOCATION I		2-D3-1	0.8	
LOCATION J		4-R10-12	1.5	
TOTALS			16.6	117.2

THERMOPLASTIC PAVEMENT MARKING QUANTITIES											
LOCATION	THERMOPLASTIC PAVEMENT MARKING - LINE 100MM		INLAID TAPE PAVEMENT MARKING - LINE 150MM		INLAID TAPE PAVEMENT MARKING - LINE 100MM		THERMOPLASTIC PAVEMENT MARKING - LINE 200MM	THERMOPLASTIC PAVEMENT MARKING - LINE 300MM	THERMOPLASTIC PAVEMENT MARKING - LINE 600MM	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS SQ M	
	SOLID		SKIP-DASH		SKIP-DASH		SOLID	SOLID	DIAGONAL		
	YELLOW	WHITE	WHITE	YELLOW	YELLOW	WHITE	YELLOW WHITE	WHITE	YELLOW		
STA. - STA.	METER	METER	METER	METER	METER	METER	METER	METER	METER		
IL RTE 40											
13+707 - 13+750	95	127		27			88	31	8.5	15.8	4.41
13+750 - 14+000	1002	501		128			34		30		1.47
14+000 - 14+200	581	402		91.5			248	21	27	48.1	13.23
14+200 - 14+450	1000	500		128					30		
14+450 - 14+700	1002	501		128			19		27		1.5
14+700 - 14+900	530	467		91.5			395	21	20	42	22.0
14+900 - 15+150	1000	500		128					30	8	
15+150 - 15+350	670	415		95	16		126	10.5	25		5.9
15+350 - 15+600	1000	505		30.5					16		
15+600 - 15+735	466	285					48.5			11.6	5.9
RICHMAR											
	96					42			8.5		
F.R. #2											
						94.6				3.6	
SERVICE DR. #1											
	52					24.4				4	
ALTA											
	620	415				3.1			44.6		1.47
SUB-TOTAL											
	8114	4618	847.5	16	164.1	958.5	89.5	303.2	137.1	137.1	55.9
TOTALS											
	12732		863.5		164.1	958.5	392.7		137.1		55.9

LOCATION	RAISED REFLECTIVE PAVEMENT MARKER EACH	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL EACH
IL RTE 40		
13+707 - 13+750	17	0
13+750 - 14+000	65	0
14+000 - 14+200	59	23
14+200 - 14+450	62	0
14+450 - 14+700	61	14
14+700 - 14+900	67	46
14+900 - 15+150	64	12
15+150 - 15+350	54	0
15+350 - 15+600	39	8
15+600 - 15+735	27	32
ALTA		
	25	0
TOTALS		
	540	135

REVISIONS	
NAME	DATE