

WORK ZONE PAVEMENT MARKINGS (REFER TO STAGING PLAN SHEETS)						
LOCATION & DESCRIPTION	SHORT TERM PAVEMENT MARKING 100MM	TEMPORARY PAVEMENT MARKING - LINE 100MM	TEMPORARY PAVEMENT MARKING - LINE 200MM	TEMPORARY PAVEMENT MARKING- LETTERS & SYMBOLS	WORK ZONE PAVEMENT MARKING REMOVAL	TEMPORARY PAVEMENT MARKING - LINE 600MM
	METER	METER	METER	SQ M	SQ M	METER
IL RTE 40 - AFTER PRIME						
STA 13+707 TO 14+260 - - STRIPE						
AS 3 LANE W/ BI-DIRECTIONAL TURN LANE						ALTA - 15
- DOUBLE SKIP DASH	113					
- LT. SHOULDER DIAGONAL	22					
STA 14+260 TO 14+600 CENTERLINE	34					
STA 14+600 TO 14+900 - - STRIPE						MOSS./WILH.-15
AS TURN LANES FOR MOSS./WILH. ROAD						
- DOUBLE SKIP DASH	52					
STA 14+900 TO 15+730 CENTERLINE	83					
STA 15+670 TO 15+730	60					
IL RTE 40 - AFTER LEVELING BINDER						
STA 13+707 TO 14+260 - STRIPE						
AS 3 LANE W/ BI-DIRECTIONAL TURN LANE						
1-DOUBLE YELLOW - 13+716 TO 13+762	92					
2-DOUBLE YELLOW - 13+762 TO 13+777	60					
1-DOUBLE YELLOW - 13+777 TO 14+025	496					
2-YELLOW SKIP-DASH - 13+777 TO 14+025	50					
2-DOUBLE YELLOW 14+025 TO 14+086	112					
1-SOLID WHITE 14+025 TO 14+086			61			
1-DOUBLE YELLOW 14+016 TO 14+260	308					
2-SKIP-DASH YELLOW 14+106 TO 14+260	31					ALTA - 15
RIGHT EDGE LINE 13+916 TO 14+260	544					
LEFT EDGE DIAGONAL LINES	22					
TURN ARROWS (12)				45.6		
STA 14+260 TO 14+600 CENTERLINE	34					
STA 14+260 TO 14+600 - - 2 EDGE LINES	680					
STA 14+600 TO 14+900 - STRIPE TURN LANES FOR MOSS./WILH. ROAD						MOSS./WILH. -15
DOUBLE SKIP DASH	52					
DOUBLE SOLID YELLOW			475			
SOLID WHITE			46			
EDGE LINES	560					
TURN ARROWS (2)				7.6		
IL RTE 40 - AFTER BINDER IN DETAIL III-A						ALTA - 7.5
N.B. LANE - NO CHANGES						MOSS./WILH. - 7.5
S.B. LANES						
RT SHOULDER DIAGONALS						
STA 13+707 TO 15+600		72				
RT SHOULDER EDGE 15+600 TO 15+714		114				
13+707 TO 15+600 CENTERLINE SKIP-DASH		148				
13+707 TO 15+600 - SOLID WHITE			488			
TURN ARROWS (12)				45.6		
IL RTE 40 - AFTER BINDER IN DETAIL III-B						
S.B. LANE - NO CHANGES						
N.B. LANE						
RT EDGE LINE - 13+707 TO 15+730		1,875				
LT EDGE LINE - 13+707 TO 15+730		1,670				
SOLID WHITE FOR TURN LANES			365			
TURN ARROWS (6)				22.8		
IL RTE 40 - AFTER DETAIL III-C & ALL BINDER IS IN PLACE, PRIOR TO SURFACE						ALTA - 15
ASSUME PRIME COAT						MOSS./WILH.-22.5
DOUBLE YELLOW SKIP-DASH	407					
CENTERLINE LANE SKIP-DASH	407					
IL RTE 40 - DURING SURFACE COURSE REPLACEMENT						
13+707 TO 15+730						
SAME AS AFTER BINDER COURSE						
IN DETAIL III-A	698					
RT EDGE DIAGONAL LINES	75					
CENTERLINE SKIP-DASH FOR N.B. LANES	167					
2-DOUBLE SKIP-DASH FOR MEDIAN	668					
SOLID WHITE FOR TURN LANES	427					
IL RTE 40						
REMOVAL OF SHORT TERM PAVEMENT MARKINGS ON SURFACE COURSE					204	
RICHMAR ROAD						7.5
0+805 TO 0+975 CENTERLINE (2)	24				1.2	7.5
						7.5
ALTA ROAD						15
0+777 TO 0+980 CENTERLINE (3)	61				2.0	
FRONTAGE ROAD #2 - SERVICE DRIVE #1						7.5
2+020 TO 2+460 CENTERLINE (3)	132				4.5	
12+465 TO 12+540 CENTERLINE (3)	23				1	
TOTAL	6494	3879	1435	121.6	212.7	150

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

TABULATION OF PLAN SHEET QUANTITIES

DATE: 09/10/05

DRAWN BY: JDU
CHECKED BY: ECM