CONTRACT NO. 94783

S.B.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
IE	(8C)B-2	WABASH	36	3
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES

	CODE NO	ITEM	UNIT	80% FED. 20% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE X071-2A
	20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	253	253
	20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	135	135
	20200100	EARTH EXCAVATION	CU YD	156	156
	20400800	FURNISHED EXCAVATION	CU YD	569	569
	20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	82	82
*	25000200	SEEDING, CLASS 2	ACRE	0.3	0.3
*	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	20	20
*	25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	20	20
*	25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	20	20
*	25000700	AGRICULTURAL GROUND LIMESTONE	TON	0.4	0.4
*	25100115	MULCH, METHOD 2	ACRE	0.3	0.3
	28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	22	22
	28000300	TEMPORARY DITCH CHECKS	EACH	4	4
	28000400	PERIMETER EROSION BARRIER	FOOT	250	250
	28000500	INLET AND PIPE PROTECTION	EACH	1	1
	28100107	STONE RIPRAP, CLASS A4	SQ YD	1209	1209
	28200200	FILTER FABRIC	SQ YD	1209	1209
	35101400	AGGREGATE BASE COURSE, TYPE B	TON	19	19
	35650700	BASE COURSE WIDENING	SQ YD	145	145
	40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	63	63
	40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	125	125
	40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	216	216
	42001165	BRIDGE APPROACH PAVEMENT	SQ YD	196	196
	42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	39	39
	44000100	PAVEMENT REMOVAL	SQ YD	58	58
	44000700	APPROACH SLAB REMOVAL	SQ YD	160	160
	48202000	BITUMINOUS SHOULDERS SUPERPAVE	TON	103	103
	50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1	1
	50105220	PIPE CULVERT REMOVAL	FOOT	30	30

SUMMARY OF QUANTITIES (Cont'd)

	CODE NO	ITEM	UNIT	80% FED. 20% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE X071-2A
	50200100	STRUCTURE EXCAVATION	CU YD	377	377
	50300100	FLOOR DRAINS	EACH	12	12
	50300225	CONCRETE STRUCTURES	CU YD	183	183
	50300255	CONCRETE SUPERSTRUCTURE	CU YD	279	279
	50300260	BRIDGE DECK GROOVING	SQ YD	787	787
	50300300	PROTECTIVE COAT	SQ YD	1061	1061
	50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1	1
	50500505	STUD SHEAR CONNECTORS	EACH	3636	3636
	50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	84260	84260
	51201300	FURNISHING STEEL PILES HP8X36	FOOT	427	427
	51201600	FURNISHING STEEL PILES HP12X53	FOOT	762	762
	51201700	FURNISHING STEEL PILES HP 12 X 74	FOOT	660	660
	51202305	DRIVING PILES	FOOT	1849	1849
	51203600	TEST PILE STEEL HP12X53	EACH	2	2
	51203700	TEST PILE STEEL HP 12 X 74	EACH	1	1
	51500100	NAME PLATES	EACH	1	1
	54215547	METAL END SECTIONS 12"	EACH	6	6
	542D0217	PIPE CULVERTS, CLASS D, TYPE 1 12"	FOOT	31	31
*	56200700	WATER SERVICE LINE 2"	FOOT	200	200
	59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	52	52
	60100945	PIPE DRAINS 12"	FOOT	60	60
	60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	126	126
	60900140	TYPE B INLET BOX, STANDARD 609006	EACH	4	4
	60900515	CONCRETE THRUST BLOCKS	EACH	4	4
*	63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	87.5	87.5
*	63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	1	1
*	63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4
*	63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	3	3
	63200310	GUARDRAIL REMOVAL	FOOT	413	413
*	63300725	STEEL PLATE BEAM GUARDRAIL (SHORT RADIUS)	FOOT	12.5	12.5

*SPECIALTY ITEMS

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. HORIZ.

DATE

DRAWN BY

CHECKED BY

PLOT DATE = 8/23/2006
FILE NAME = $FILE$
PLOT SCALE = $SCALE$
USER NAME = district