CONTRACT NO. 94785

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	(25-4 HB-1)B	EFFINGHAM	67	3
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* FAI RTE. 57/70

SUMMARY OF QUANTITIES

	CODE NO	ITEM	UNIT	90% FED. 10% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE 1000	X771-2A
△	X0325572	IMPACT ATTENUATORS, TEMPORARY (PARTIALLY REDIRECTIVE), TEST LEVEL 3	EACH	2	2	
△	X0325573	IMPACT ATTENUATORS, RELOCATE (PARTIALLY REDIRECTIVE), TEST LEVEL 3	EACH	2	2	
	X0325283	BITUMINOUS SHOULDER REMOVAL AND REPLACEMENT 8"	SQ YD	51	51	
	20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	36	36	
	20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	170	170	
	20200100	EARTH EXCAVATION	CU YD	859	859	
	20400800	FURNISHED EXCAVATION	CU YD	30809	30809	
	20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	225.8		225.8
	21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	4288	4288	
*	25000200	SEEDING, CLASS 2	ACRE	6	6	
*	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	528	528	
*	25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	528	528	
*	25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	528	528	
*	25000700	AGRICULTURAL GROUND LIMESTONE	TON	12	12	
*	25100115	MULCH, METHOD 2	ACRE	6	6	
	28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	587	587	
	28000300	TEMPORARY DITCH CHECKS	EACH	12	12	
	28000500	INLET AND PIPE PROTECTION	EACH	3	3	
	30200650	PROCESSING MODIFIED SOIL 12"	SQ YD	5847	5847	
	30201500	LIME	TON	147	147	
	40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	199	199	
	42001400	BRIDGE APPROACH PAVEMENT (SPECIAL)	SQ YD	251	251	
	42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	58	58	

△ SFTY-3N
* SPECIALTY ITEMS

SUMMARY OF QUANTITIES (Cont'd)

CODE NO	ITEM	UNIT	90% FED. 10% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE 1000	X771-2A
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	177	177	
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	7696	7696	
44000100	PAVEMENT REMOVAL	SQ YD	4132	4132	
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1
50105220	PIPE CULVERT REMOVAL	FOOT	73	73	
50200100	STRUCTURE EXCAVATION	CU YD	151.6		151.6
50300225	CONCRETE STRUCTURES	CU YD	184.3		184.3
50300255	CONCRETE SUPERSTRUCTURE	CU YD	350.1		350.1
50300260	BRIDGE DECK GROOVING	SQ YD	780.8		780.8
50300300	PROTECTIVE COAT	SQ YD	1163		1163
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1		1
50500505	STUD SHEAR CONNECTORS	EACH	2448		2448
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	93,670		93,670
51100100	SLOPE WALL 4 INCH	SQ YD	485.8		485.8
51201600	FURNISHING STEEL PILES HP12X53	FOOT	615		615
51202700	DRIVING STEEL PILES	FOOT	615		615
51203600	TEST PILE STEEL HP12X53	EACH	1		1
51204600	METAL SHOES	EACH	12		12
51500100	NAME PLATES	EACH	1		1
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	1	1	
54215547	METAL END SECTIONS 12"	EACH	8	8	
54215553	METAL END SECTIONS 18"	EACH	2	2	
54215559	METAL END SECTIONS 24"	EACH	2	2	

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. HORIZ.
DATE

DRAWN BY
CHECKED BY

PLOT DATE = 8/24/2006
FILE NAME = $FILEN$
PLOT SCALE = $SCALE$
USER NAME = $LUSVCE$