

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	(25-4 HB-1)B	EFFINGHAM	67	10
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

* FAI RTE. 57/70

EARTHWORK SCHEDULE	EARTH EXCAVATION	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (25%)	EARTH FILL	EARTHWORK BALANCE, WASTE (+) OR SHORTAGE (-)	TOPSOIL EXCAVATION AND PLACEMENT
39+50.0 TO 40+00.0	23.4	17.6	3.1	14.5	5.1
40+00.0 TO 40+50.0	5.0	3.8	36.0	-32.3	19.6
40+50.0 TO 41+00.0	16.1	12.1	133.0	-120.9	40.6
41+00.0 TO 41+50.0	26.4	19.8	173.1	-153.3	60.6
41+50.0 TO 42+00.0	26.3	19.7	265.6	-245.9	76.6
42+00.0 TO 42+50.0	47.3	35.5	408.0	-372.6	83.1
42+50.0 TO 43+00.0	48.2	36.2	531.9	-495.7	94.1
43+00.0 TO 43+50.0	32.7	24.5	674.5	-650.0	104.7
43+50.0 TO 44+00.0	29.6	22.2	726.5	-704.3	113.1
44+00.0 TO 44+50.0	25.7	19.3	768.6	-749.3	122.4
44+50.0 TO 45+00.0	25.6	19.2	863.6	-844.4	132.3
45+00.0 TO 45+50.0	28.6	21.5	1006.0	-984.5	142.3
45+50.0 TO 46+00.0	28.6	21.4	1195.8	-1174.4	151.7
46+00.0 TO 46+50.0	31.3	23.5	1419.5	-1396.0	161.5
46+50.0 TO 47+00.0	43.4	32.6	1615.3	-1582.7	171.6
47+00.0 TO 47+50.0	57.9	43.4	1770.9	-1727.4	181.3
47+50.0 TO 48+00.0	64.8	48.6	1875.5	-1826.9	188.6
48+00.0 TO 48+50.0	32.7	24.5	1341.0	-1316.4	190.8
48+50.0 TO 48+81.8	0.0	0.0	494.0	-494.0	121.1
51+15.9 TO 51+50.0	0.0	0.0	637.4	-637.4	127.9
51+50.0 TO 52+00.0	56.5	42.4	1387.5	-1345.1	192.5
52+00.0 TO 52+50.0	100.6	75.5	1817.0	-1741.6	193.7
52+50.0 TO 53+00.0	53.3	39.9	1751.3	-1711.3	180.0
53+00.0 TO 53+50.0	12.9	9.7	1604.4	-1594.7	165.6
53+50.0 TO 54+00.0	5.0	3.8	1422.0	-1418.2	156.5
54+00.0 TO 54+50.0	10.1	7.6	1228.0	-1220.4	148.8
54+50.0 TO 55+00.0	9.3	6.9	1048.4	-1041.5	137.8
55+00.0 TO 55+50.0	0.5	0.3	927.2	-926.9	123.2
55+50.0 TO 56+00.0	0.0	0.0	829.2	-829.2	112.5
56+00.0 TO 56+50.0	0.0	0.0	758.4	-758.4	104.4
56+50.0 TO 57+00.0	0.0	0.0	697.7	-697.7	95.3
57+00.0 TO 57+50.0	0.0	0.0	608.0	-608.0	85.4
57+50.0 TO 58+00.0	2.5	1.9	502.5	-500.6	76.5
58+00.0 TO 58+50.0	6.7	5.0	406.7	-401.7	68.3
58+50.0 TO 59+00.0	6.2	4.7	297.3	-292.6	74.7
59+00.0 TO 59+50.0	2.0	1.5	170.6	-169.1	60.2
59+50.0 TO 60+00.0	0.0	0.0	54.8	-54.8	20.1
60+00.0 TO 60+65.0	0.0	0.0	3.6	-3.6	3.1
TOTALS	859.0	644.0	31454.0	-30809.0	4288.0

SEEDING SCHEDULE	SEEDING, CLASS 2	TEMPORARY EROSION CONTROL SEEDING	NITROGEN FERTILIZER NURTIENT	PHOSPHORUS FERTILIZER NURTIENT	POTASSIUM FERTILIZER NURTIENT	MULCH, METHOD 2	AGRICULTURAL GROUND LIMESTONE
39+50.0 TO 40+00.0	0.02	2.00	1.80	1.80	1.80	0.02	0.04
40+00.0 TO 40+50.0	0.03	3.00	2.70	2.70	2.70	0.03	0.06
40+50.0 TO 41+00.0	0.02	2.00	1.80	1.80	1.80	0.02	0.04
41+00.0 TO 41+50.0	0.05	5.00	4.50	4.50	4.50	0.05	0.10
41+50.0 TO 42+00.0	0.07	7.00	6.30	6.30	6.30	0.07	0.14
42+00.0 TO 42+50.0	0.08	8.00	7.20	7.20	7.20	0.08	0.16
42+50.0 TO 43+00.0	0.10	10.00	9.00	9.00	9.00	0.10	0.20
43+00.0 TO 43+50.0	0.13	13.00	11.70	11.70	11.70	0.13	0.26
43+50.0 TO 44+00.0	0.15	15.00	13.50	13.50	13.50	0.15	0.30
44+00.0 TO 44+50.0	0.16	16.00	14.40	14.40	14.40	0.16	0.32
44+50.0 TO 45+00.0	0.19	19.00	17.10	17.10	17.10	0.19	0.38
45+00.0 TO 45+50.0	0.22	22.00	19.80	19.80	19.80	0.22	0.44
45+50.0 TO 46+00.0	0.24	24.00	21.60	21.60	21.60	0.24	0.48
46+00.0 TO 46+50.0	0.27	27.00	24.30	24.30	24.30	0.27	0.54
46+50.0 TO 47+00.0	0.29	29.00	26.10	26.10	26.10	0.29	0.58
47+00.0 TO 47+50.0	0.32	32.00	28.80	28.80	28.80	0.32	0.64
47+50.0 TO 48+00.0	0.34	34.00	30.60	30.60	30.60	0.34	0.68
48+00.0 TO 48+50.0	0.21	21.00	18.90	18.90	18.90	0.21	0.42
48+50.0 TO 48+81.8	0.13	13.00	11.70	11.70	11.70	0.13	0.26
51+15.9 TO 51+50.0	0.00	0.00	0.00	0.00	0.00	0.00	0.00
51+50.0 TO 52+00.0	0.14	14.00	12.60	12.60	12.60	0.14	0.28
52+00.0 TO 52+50.0	0.30	30.00	27.00	27.00	27.00	0.30	0.60
52+50.0 TO 53+00.0	0.36	36.00	32.40	32.40	32.40	0.36	0.72
53+00.0 TO 53+50.0	0.30	30.00	27.00	27.00	27.00	0.30	0.60
53+50.0 TO 54+00.0	0.27	27.00	24.30	24.30	24.30	0.27	0.54
54+00.0 TO 54+50.0	0.24	24.00	21.60	21.60	21.60	0.24	0.48
54+50.0 TO 55+00.0	0.23	23.00	20.70	20.70	20.70	0.23	0.46
55+00.0 TO 55+50.0	0.19	19.00	17.10	17.10	17.10	0.19	0.38
55+50.0 TO 56+00.0	0.16	16.00	14.40	14.40	14.40	0.16	0.32
56+00.0 TO 56+50.0	0.13	13.00	11.70	11.70	11.70	0.13	0.26
56+50.0 TO 57+00.0	0.12	12.00	10.80	10.80	10.80	0.12	0.24
57+00.0 TO 57+50.0	0.10	10.00	9.00	9.00	9.00	0.10	0.20
57+50.0 TO 58+00.0	0.09	9.00	8.10	8.10	8.10	0.09	0.18
58+00.0 TO 58+50.0	0.07	7.00	6.30	6.30	6.30	0.07	0.14
58+50.0 TO 59+00.0	0.06	6.00	5.40	5.40	5.40	0.06	0.12
59+00.0 TO 59+50.0	0.05	5.00	4.50	4.50	4.50	0.05	0.10
59+50.0 TO 60+00.0	0.03	3.00	2.70	2.70	2.70	0.03	0.06
60+00.0 TO 60+65.0	0.01	1.00	0.90	0.90	0.90	0.01	0.02
TOTAL =	6.00	587.00	528.00	528.00	528.00	6.00	12.00

PLOT DATE = 8/24/2006
 FILE NAME = WFL1E1
 PLOT SCALE = #SCALE#
 USER NAME = dstricot

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULES
(Cont'd)

SCALE: VERT.
HORIZ.
DATE

DRAWN BY
CHECKED BY