

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
821	13B-1	JEFFERSON	39	4
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

SUMMARY OF QUANTITIES (Cont'd)			80% FED. 20% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE X071-2A
CODE NO	ITEM	UNIT		
70400500	TEMPORARY CONCRETE BARRIER (STATE OWNED)	FOOT	610	610
70400600	RELOCATE TEMPORARY CONCRETE BARRIER (STATE OWNED)	FOOT	610	610
70500100	TEMPORARY STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	37.5	37.5
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	2250	2250
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	10	10
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4
78300500	PAINT PAVEMENT MARKING REMOVAL	SQ FT	2044	2044
* A2005316	TREE, LIQUIDAMBAR STYRACIFLUA (AMERICAN SWEETGUM), 2" CALIPER, BALLED AND BURLAPPED	EACH	5	5
* A2005416	TREE, LIRIODENDRON TULIPIFERA (TULIP TREE), 2" CALIPER, BALLED AND BURLAPPED	EACH	5	5
* A2005816	TREE, PLATANUS OCCIDENTALIS (SYCAMORE), 2" CALIPER, BALLED AND BURLAPPED	EACH	5	5
* A2006514	TREE, QUERCUS BICOLOR (SWAMP WHITE OAK), 1-3/4" CALIPER, BALLED AND BURLAPPED	EACH	5	5
* A2016814	TREE, QUERCUS SHUMARDII (SHUMARD RED OAK), 1-3/4" CALIPER, BALLED AND BURLAPPED	EACH	5	5
X0300136	BRIDGE APPROACH SHOULDER REMOVAL	SQ YD	67	67
X0323988	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	444	444
X4024000	TEMPORARY ACCESS (FIELD ENTRANCE)	EACH	2	2
X4066428	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N90	TON	122	122
X4066618	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N90	TON	222	222
X5020501	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 1	EACH	1	1
Z0002600	BAR SPLICERS	EACH	583	583
Δ Z0030240	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 2	EACH	2	2
Δ Z0030340	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 2	EACH	2	2

Δ SFTY-BN  
\* SPECIALTY ITEMS

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SUMMARY OF QUANTITIES (Cont'd)

SCALE: VERT. \_\_\_\_\_  
HORIZ. \_\_\_\_\_  
DATE \_\_\_\_\_ DRAWN BY \_\_\_\_\_  
CHECKED BY \_\_\_\_\_