90% FEDERAL
10% STATE

	CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	CONSTR. CODE TRAFFIC SIGNALS 0021
	42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	26	26
	44000600	SIDEWALK REMOVAL	SQ FT	26	26
	60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	494	494
*	66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	20	20
*	66900450	SPECIAL WASTE PLANS AND REPORTS	LSUM	1	1
*	66900530	SOIL DISPOSAL ANALYSIS	EACH	4	4
	67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	20	20
	67100100	MOBILIZATION	LSUM	1	1
	70102637	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	EACH	44	44
	70102642	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	EACH	23	23
	80300100	LOCATING UNDERGROUND CABLE	FOOT	275	275
	81028340	UNDERGROUND CONDUIT, PVC, 1 1/2" DIA.	FOOT	312	312
	81400700	HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	1	1
	87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	23460	23460
	87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	21641	21641
	87502680	TRAFFIC SIGNAL POST, ALUMINUM 14 FT.	EACH	18	18
	87800100	CONCRETE FOUNDATION, TYPE A	FOOT	54	54
	87900100	DRILL EXISTING FOUNDATION	EACH	4	4
	87900200	DRILL EXISTING HANDHOLE	EACH	13	13
	88040070	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	49	49
	88040090	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	1	1
	88040110	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 4-SECTION, BRACKET MOUNTED	EACH	14	14
	88040120	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 4-SECTION, MAST ARM MOUNTED	EACH	1	1

90% FEDERAL
10% STATE

CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	CONSTR. CODE TRAFFIC SIGNALS 0021
88040150	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	25	25
88040250	SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, 1-3 SECTION, 1-4 SECTION, BRACKET MOUNTED	EACH	43	43
88040260	SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, 1-3-SECTION, 1-5-SECTION, BRACKET MOUNTED	EACH	49	49
89501250	RELOCATE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	4	4
89502100	REBUILD EXISTING SIGNAL HEAD	EACH	21	21
89502200	MODIFY EXISTING CONTROLLER	EACH	44	44
89502210	MODIFY EXISTING CONTROLLER CABINET	EACH	44	44
89502350	REMOVE AND REINSTALL ELECTRIC CABLE FROM CONDUIT	FOOT	220215	220215
89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1	1
X4402020	CONCRETE MEDIAN SURFACE REMOVAL	SQ FT	494	494
X8100863	INTERCEPT EXISTING CONDUIT	EACH	1	1

* SPECIALTY ITEM

Rev. 10-26-17

FILE NAME = pw:\\IL084EBIDINTEG.illinois.gov:PWIDOT\Documents\IDOT Offices\District 8\Projects\D876J24\Project Data\EAOsheets\D876J24-sht-tsplan.dgn	USER NAME = prestonma	DESIGNED -	REVISED -
	PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED -
	PLOT DATE = 8/24/2017	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET OF SHEETS STA. TO STA.

RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	DIST 8 TS 2018-1	*	120	5
*=VARIOUS		CONTRACT NO. 76J24		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

REV