

MODEL: Default
 FILE NAME: p:\work\housese01\HDR_US_Central_01\Documents\1\DOT\DOT_Pls II_Spec_Various TO's_199-13\DOT_PTB_199-13_T07_18016.0_CAD_BIM6.2_VIP6.2.3_CADD_StreetRoadway\Summary of Quantities

CODE NO.	DESCRIPTION	UNIT	TOTAL QUANTITY URBAN	0006 ROADWAY 90% FED/ 10% STATE	0047 016-0074 BRIDGE REHABILITATION 90% FED/ 10% STATE	0047 016-0075 BRIDGE REHABILITATION 90% FED/ 10% STATE	0047 016-0076 BRIDGE REHABILITATION 90% FED/ 10% STATE	0047 016-0077 BRIDGE REHABILITATION 90% FED/ 10% STATE	0047 016-0078 BRIDGE REHABILITATION 90% FED/ 10% STATE	0047 016-0079 BRIDGE REHABILITATION 90% FED/ 10% STATE	0047 BRIDGE REHABILITATION 100% STATE
50102400	CONCRETE REMOVAL	CU YD	154.6		21.5	22.5	38.3	35.7	18.3	18.3	
50104650	SLOPE WALL REMOVAL	SQ YD	382				382				
50157300	PROTECTIVE SHIELD	SQ YD	4,636		792	792	846	846	680	680	
50300225	CONCRETE STRUCTURES	CU YD	138.0		32.1	36.4			36.2	33.3	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	175.7 175.4		24.2	25.5	43.2	40.7	21.0	21.1	
50300300	PROTECTIVE COAT	SQ YD	13,837		2,211	2,210	2,791	2,808	1,907	1,910	
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	31,460		11,940	18,300			610	610	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	41,120		7,840	8,130	4,850	4,840	7,810	7,650	
50800515	BAR SPLICERS	EACH	144		24	24	24	24	24	24	
51100100	SLOPE WALL 4 INCH	SQ YD	382				382				
52000110	PREFORMED JOINT STRIP SEAL	FOOT	750.0		139.0	139.0	116.0	116.0	120.0	120.0	
52000340	NEOPRENE EXPANSION JOINT 4"	FOOT	232.0				116.0	116.0			
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	1					1			
52100020	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	2				2				
52100520	ANCHOR BOLTS, 1"	EACH	6				4	2			
59000200	EPOXY CRACK INJECTION	FOOT	300		50	50	50	50	50	50	
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	66	66							
* 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	700	700							

LEGEND
 *- DENOTES SPECIALTY ITEM

REVISED SHEET 10/26/2023

 HDR ENGINEERING, INC. 9450 W. BRYN MAWR AVE. ROSEMONT, IL 60018	USER NAME = RAZEVEDO	DESIGNED - NSA	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES I-80	F.A.I. RTE. 80	SECTION 2021-059-RS&B/R	COUNTY COOK	TOTAL SHEETS 185	SHEET NO. 4			
	PLOT SCALE = 100.0000' / in.	CHECKED - DJP	REVISED -			SCALE:	SHEET 2 OF 7 SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT			
	PLOT DATE = 6/13/2023	DATE - 06/16/2023	REVISED -										

MODEL: D:\default\...
 FILE NAME: p:\work\housen01\HDR_US_Central_01\Documents\11\DOT\DOT_P18_199-15\DOT_P18_199-15_T07_18016.0_CAD_BIM6.2_WIP6.2.3_CADD_SheetRoadway\Summary of Quantities


CODE NO.	DESCRIPTION	UNIT	TOTAL QUANTITY URBAN	0006 ROADWAY 90% FED/ 10% STATE	0047 016-0074 BRIDGE REHABILITATION 90% FED/ 10% STATE	0047 016-0075 BRIDGE REHABILITATION 90% FED/ 10% STATE	0047 016-0076 BRIDGE REHABILITATION 90% FED/ 10% STATE	0047 016-0077 BRIDGE REHABILITATION 90% FED/ 10% STATE	0047 016-0078 BRIDGE REHABILITATION 90% FED/ 10% STATE	0047 016-0079 BRIDGE REHABILITATION 90% FED/ 10% STATE	0047 BRIDGE REHABILITATION 100% STATE
* 63000003	STEEL PLATE BEAM GUARDRAIL, TYPE A, 9 FOOT POSTS	FOOT	1,662.5	1662.5							
* 63000017	STEEL PLATE BEAM GUARDRAIL, TYPE D, 6 FOOT POSTS	FOOT	287.5	287.5							
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	4	4							
* 63100070	TRAFFIC BARRIER TERMINAL, TYPE 5	EACH	11	11							
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	12	12							
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	5	5							
63200310	GUARDRAIL REMOVAL	FOOT	3,475	3,475							
64200116	SHOULDER RUMBLE STRIPS, 16 INCH	FOOT	13,317	13,317							
* 66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	12	12							
* 66900530	SOIL DISPOSAL ANALYSIS	EACH	1	1							
* 66901001	REGULATED SUBSTANCES PRE-CONSTRUCTION PLAN	LSUM	1	1							
* 66901003	REGULATED SUBSTANCES FINAL CONSTRUCTION REPORT	LSUM	1	1							
* 66901006	REGULATED SUBSTANCES MONITORING	CAL DA	3	3							
67100100	MOBILIZATION	L SUM	1	1							
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	12	12							
X7010238	CHANGEABLE MESSAGE SIGN (SPECIAL)	CAL MO	12	12							
70300150	SHORT TERM PAVEMENT MARKING REMOVAL	SQ FT	34,229	34,229							
70400100	TEMPORARY CONCRETE BARRIER	FOOT	5,262.5	5262.5							
70400125	PINNING TEMPORARY CONCRETE BARRIER	EACH	858	858							



LEGEND

* - DENOTES SPECIALTY ITEM

REVISED SHEET 10/26/2023



USER NAME = RAZEVEDO	DESIGNED - NSA	REVISED -
DRAWN - NSA	CHECKED - DJP	REVISED -
PLOT SCALE = 100.0000' / in.	DATE - 06/16/2023	REVISED -
PLOT DATE = 6/30/2023		

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**


**SUMMARY OF QUANTITIES
I-80**

SCALE: SHEET 3 OF 7 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80	2021-059-R5&BJR	COOK	185	5
			CONTRACT NO. 62N96	
(ILLINOIS FED. AID PROJECT)				

MODEL: D:\6\11
 FILE NAME: dw:\p\hdms\sec01-HDR_US_Central_01\Documents\DOT\DOT_Phs_II_Ser_Various_TO_s_199-15\DOT_PTB_199-15_TOT_18016.0_CAD_BIM\6.2_3_CADD_SheetRoadway\Summary_of_Quantities


CODE NO.	DESCRIPTION	UNIT	TOTAL QUANTITY URBAN	0006 ROADWAY 90% FED/ 10% STATE	0047 016-0074 BRIDGE REHABILITATION 90% FED/ 10% STATE	0047 016-0075 BRIDGE REHABILITATION 90% FED/ 10% STATE	0047 016-0076 BRIDGE REHABILITATION 90% FED/ 10% STATE	0047 016-0077 BRIDGE REHABILITATION 90% FED/ 10% STATE	0047 016-0078 BRIDGE REHABILITATION 90% FED/ 10% STATE	0047 016-0079 BRIDGE REHABILITATION 90% FED/ 10% STATE	0047 BRIDGE REHABILITATION 100% STATE
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	4,862.5	4862.5							
70600260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	6	6							
70600332	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	4	4							
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	30,193	30,193							
* 78000300	THERMOPLASTIC PAVEMENT MARKING - LINE 5"	FOOT	8,533	8,533							
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	10,027	10,027							
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1,642	1,642							
* 78004640	PREFORMED PLASTIC PAVEMENT MARKING, TYPE D - LINE 8"	FOOT	697	697							
* 78009004	MODIFIED URETHANE PAVEMENT MARKING - LINE 4"	FOOT	2,785	2,785							
* 78009012	MODIFIED URETHANE PAVEMENT MARKING - LINE 12"	FOOT	117	117							
* 78011045	GROOVING FOR RECESSED PAVEMENT MARKING 9"	FOOT	697	697							
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	196	196							
* 78200005	GUARDRAIL REFLECTORS, TYPE A	EACH	70	70							
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	196	196							
78300202	PAVEMENT MARKING REMOVAL - WATER BLASTING	SQ FT	22,585	22,585							
X0323491	SLOPE WALL CRACK SEALING	FOOT	1,023		164	209	650				
X6420100 X0325201	SHOULDER RUMBLE STRIP REMOVAL	SQ YD	3,201	3,201							



LEGEND

* - DENOTES SPECIALTY ITEM

1 REVISED SHEET 10/26/2023



USER NAME = RAZEVEDO	DESIGNED - NSA	REVISED -
	DRAWN - NSA	REVISED -
PLOT SCALE = 100.0000' / in.	CHECKED - DJP	REVISED -
PLOT DATE = 6/30/2023	DATE - 06/16/2023	REVISED -

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES
 I-80**

SCALE: SHEET 4 OF 7 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80	2021-059-R5&BJR	COOK	185	6
CONTRACT NO. 62N96			ILLINOIS FED. AID PROJECT	

MODEL: D:\draft\...
 FILE NAME: p:\work\house01\HDR_US_Centrol_01\Documents\1\DOT\DOT_Phs II_Spec_Various TO_s_199-13\DOT_PTB_199-13_T07-18016.0_CAD_BIM6.2_WIP6.2.3_CADD_SheetRoadway\Summary of Quantities

CODE NO.	DESCRIPTION	UNIT	TOTAL QUANTITY URBAN	0006 ROADWAY 90% FED/ 10% STATE	0047 016-0074 BRIDGE REHABILITATION 90% FED/ 10% STATE	0047 016-0075 BRIDGE REHABILITATION 90% FED/ 10% STATE	0047 016-0076 BRIDGE REHABILITATION 90% FED/ 10% STATE	0047 016-0077 BRIDGE REHABILITATION 90% FED/ 10% STATE	0047 016-0078 BRIDGE REHABILITATION 90% FED/ 10% STATE	0047 016-0079 BRIDGE REHABILITATION 90% FED/ 10% STATE	0047 BRIDGE REHABILITATION 100% STATE
Z0012755	STRUCTURAL REPAIR OF CONCRETE (DEPTH GREATER THAN 5 INCHES)	SQ FT	110		6	13	19	67		5	
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1							
Z0016001	DECK SLAB REPAIR (FULL DEPTH, TYPE I)	SQ YD	18		3	3	3	3	3	3	
Z0018051	DRAINAGE SCUPPERS TO BE ADJUSTED	EACH	24		4	4	4	4	4	4	
Z0029090	DIAMOND GRINDING (BRIDGE SECTION)	SQ YD	8,356		1,288	1,288	1,784	1,784	1,106	1,106	
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	206	206							
* X7830052	RAISED REFLECTIVE PAVEMENT MARKER, REFLECTOR REPLACEMENT	EACH	381	381							
Z0065700	SLOPE WALL REPAIR	SQ YD	20				20				
Z0065730	SLOPE WALL SLURRY PUMPING	CU YD	160				160				
Z0073200	TEMPORARY SHORING AND CRIBBING	EACH	6		2	4					
Z0073350	TEMPORARY SLAB SUPPORT SYSTEM	EACH	5		2	3					
Ø Z0076600	TRAINEES	HOURS	500	500							
Ø Z0076604	TRAINEES - TRAINING PROGRAM GRADUATE	HOURS	500	500							



REVISÉ SHEET 10/26/2023

Ø 0042

LEGEND

* - DENOTES SPECIALTY ITEM

HDR
 HDR ENGINEERING, INC.
 9450 W. BRYN MAWR AVE.
 ROSEMONT, IL 60018

USER NAME = RAZEVEDO	DESIGNED - NSA	REVISED -
DRAWN - NSA	REVISÉ -	
PLOT SCALE = 100.0000' / in.	CHECKED - DJP	REVISED -
PLOT DATE = 6/30/2023	DATE - 06/16/2023	REVISED -

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES
 I-80**

SCALE: SHEET 7 OF 7 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80	2021-059-R5&BJR	COOK	185	9
CONTRACT NO. 62N96			ILLINOIS FED. AID PROJECT	