

MODEL: Default
 FILE: \\saw.bentley.com\PI\DOT\Documents\DOT_Offices\Burlington\Program_Development\Studies & Plans\Drawings\CAAD\CAAD\Drawings\02-64918-01-500.dwg

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE		
				80% Federal 20% State	50% State 50% City	100% City
				ROADWAY	ROADWAY	ROADWAY
				0005 URBAN	0005 URBAN	0005 URBAN
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	7345	7345		
* 42400800	DETECTABLE WARNINGS	SQ FT	507	507		
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	17875	17778	97	
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	134	134		
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1972	1972		
44000600	SIDEWALK REMOVAL	SQ FT	6381	6381		
44200050	WELDED WIRE REINFORCEMENT	SQ YD	969	969		
44200970	CLASS B PATCHES, TYPE II, 10 INCH	SQ YD	662	662		
44200982	CLASS B PATCHES, TYPE II, 11 INCH	SQ YD	662	662		
44200974	CLASS B PATCHES, TYPE III, 10 INCH	SQ YD	377	377		
44200986	CLASS B PATCHES, TYPE III, 11 INCH	SQ YD	377	377		
44200976	CLASS B PATCHES, TYPE IV, 10 INCH	SQ YD	592	592		
44200988	CLASS B PATCHES, TYPE IV, 11 INCH	SQ YD	592	592		
44201299	DOWEL BARS 1 1/2"	EACH	2134	2134		
44201298	DOWEL BARS 1 1/4"	EACH	2134	2134		
44213200	SAW CUTS	FOOT	6873	6873		
44213204	TIE BARS 3/4"	EACH	123	123		
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	5	5		

* SPECIALTY ITEMS

USER NAME = Brad.Cushman	DESIGNED - _____	REVISED - _____
DRAWN - _____	REVISIONS - _____	
PLOT SCALE = 100.0000' / in.	CHECKED - _____	REVISED - _____
PLOT DATE = Aug-09-2023 03:14:25 PM	DATE - _____	REVISED - _____

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: _____ SHEET ____ OF ____ SHEETS STA. _____ TO STA. _____

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
642	108 RS-3	CARROLL	75	4
CONTRACT NO. 64918				
ILLINOIS FED. AID PROJECT				

MODEL: Default
 FILE: \\paw.bentley.com\paw\DOT\Documents\DOT_Offices\Bartlett_2\Projects\649\BProgram_Development\Studies_&_Plans\Drawings\CADD\CAD\Drawings\12-64918-18-18-500.dwg

FIELD INPUT AREA			44200982		44200986		44200988		44213200	44201298	44213204	44200050
STA	LENGTH OF PATCH		Class B, Type II, 11 INCH		Class B, Type III, 11 INCH		Class B, Type IV, 11 INCH		SAW CUTS (3W+?L) (ft)	DOWEL BARS (each)	TIE BARS 3/4" (each)	WELDED WIRE REINF. (yd ²)
	LT LANE (ft)	RT LANE (ft)	LT LANE (yd ²)	RT LANE (yd ²)	LT LANE (yd ²)	RT LANE (yd ²)	LT LANE (yd ²)	RT LANE (yd ²)				
588+79	6	6	8.7	8.7	-	-	-	-	108	44	-	-
589+43	6	6	8.7	8.7	-	-	-	-	108	44	-	-
589+64	8		11.6	-	-	-	-	-	63	22	-	-
589+66		6	-	8.7	-	-	-	-	57	22	-	-
590+16	6	6	8.7	8.7	-	-	-	-	108	44	-	-
591+15	6	6	8.7	8.7	-	-	-	-	108	44	-	-
591+56	6		8.7	-	-	-	-	-	57	22	-	-
593+04	20	20	-	-	-	-	28.9	28.9	178	44	9	57.8
594+07		20	-	-	-	-	-	28.9	99	22	9	28.9
595+15	6	6	8.7	8.7	-	-	-	-	108	44	-	-
595+95	20	20	-	-	-	-	28.9	28.9	178	44	9	57.8
596+55	40		-	-	-	-	57.8	-	159	22	19	57.8
596+99	10		14.4	-	-	-	-	-	69	22	-	-
567+60	6		8.7	-	-	-	-	-	57	22	-	-
597+65		12	-	-	-	17.3	-	-	75	22	-	17.3
597+88		6	-	8.7	-	-	-	-	57	22	-	-
598+49	6	6	8.7	8.7	-	-	-	-	108	44	-	-
598+79	6	6	8.7	8.7	-	-	-	-	108	44	-	-
599+15	12	30	-	-	17.3	-	-	43.3	192	44	14	60.7
599+70	6	6	8.7	8.7	-	-	-	-	108	44	-	-
600+00	8	6	11.6	8.7	-	-	-	-	114	44	-	-
600+45		20	-	-	-	-	-	28.9	99	22	9	28.9
600+82	15		-	-	21.7	-	-	-	84	22	-	21.7
601+44	15		-	-	21.7	-	-	-	84	22	-	21.7
601+53		15	-	-	-	21.7	-	-	84	22	-	21.7
602+52	10		14.4	-	-	-	-	-	69	22	-	-
603+02	15		-	-	21.7	-	-	-	84	22	-	21.7
603+56	15		-	-	21.7	-	-	-	84	22	-	21.7
604+04	6		8.7	-	-	-	-	-	57	22	-	-
604+87		8	-	11.6	-	-	-	-	63	22	-	-
606+67		6	-	8.7	-	-	-	-	57	22	-	-
607+05	10	8	14.4	11.6	-	-	-	-	124	44	-	-
607+73	8		11.6	-	-	-	-	-	63	22	-	-
608+46	6	6	8.7	8.7	-	-	-	-	108	44	-	-
608+90		8	-	11.6	-	-	-	-	63	22	-	-
609+68	8	8	11.6	11.6	-	-	-	-	118	44	-	-
610+10	6	6	8.7	8.7	-	-	-	-	108	44	-	-
611+74		8	-	11.6	-	-	-	-	63	22	-	-
612+07	12		-	-	17.3	-	-	-	75	22	-	17.3
612+75	6	8	8.7	11.6	-	-	-	-	114	44	-	-
613+20		12	-	-	-	17.3	-	-	75	22	-	17.3
614+09	15	15	-	-	21.7	21.7	-	-	153	44	-	43.3
614+79	8	8	11.6	11.6	-	-	-	-	118	44	-	-
615+55	12		-	-	17.3	-	-	-	75	22	-	17.3
616+68		15	-	-	-	21.7	-	-	84	22	-	21.7
617+09	8		11.6	-	-	-	-	-	63	22	-	-
618+32		12	-	-	-	17.3	-	-	75	22	-	17.3
619+04		8	-	11.6	-	-	-	-	63	22	-	-
620+32		12	-	-	-	17.3	-	-	75	22	-	17.3
620+52		15	-	-	-	21.7	-	-	84	22	-	21.7
620+88	6		8.7	-	-	-	-	-	57	22	-	-
620+93		8	-	11.6	-	-	-	-	63	22	-	-
621+35		6	-	8.7	-	-	-	-	57	22	-	-
622+04		6	-	8.7	-	-	-	-	57	22	-	-

USER NAME = Brad.Cushman	DESIGNED - _____	REVISED - _____
DRAWN - _____	REVISIONS - _____	
PLOT SCALE = 100.0000 ' / in.	CHECKED - _____	REVISED - _____
PLOT DATE = Oct-24-2023 01:42:22 PM	DATE - _____	REVISED - _____

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

PATCHING SCHEDULE

SCALE: _____ SHEET ____ OF ____ SHEETS STA. _____ TO STA. _____

F.A.P. RTE. 642	SECTION 108 RS-3	COUNTY CARROLL	TOTAL SHEETS 75	SHEET NO. 17
CONTRACT NO. 64918				
ILLINOIS FED. AID PROJECT				

FIELD INPUT AREA			44200982		44200986		44200988		44213200	44201298	44213204	44200050
STA	LENGTH OF PATCH		Class B, Type II, 11 INCH		Class B, Type III, 11 INCH		Class B, Type IV, 11 INCH		SAW CUTS (3W+?L) (ft)	DOWEL BARS (each)	TIE BARS 3/4" (each)	WELDED WIRE REINF. (yd ²)
	LT LANE (ft)	RT LANE (ft)	LT LANE (yd ²)	RT LANE (yd ²)	LT LANE (yd ²)	RT LANE (yd ²)	LT LANE (yd ²)	RT LANE (yd ²)				
622+55	6	6	8.7	8.7	-	-	-	-	108	44	-	-
622+97	6		8.7	-	-	-	-	-	57	22	-	-
623+80	8		11.6	-	-	-	-	-	63	22	-	-
624+98	6	6	8.7	8.7	-	-	-	-	108	44	-	-
625+30		6	-	8.7	-	-	-	-	57	22	-	-
625+50	8		11.6	-	-	-	-	-	63	22	-	-
626+54		8	-	11.6	-	-	-	-	63	22	-	-
627+88	8		11.6	-	-	-	-	-	63	22	-	-
628+52	6	6	8.7	8.7	-	-	-	-	108	44	-	-
628+96		6	-	8.7	-	-	-	-	57	22	-	-
629+91	12		-	-	17.3	-	-	-	75	22	-	17.3
629+98		6	-	8.7	-	-	-	-	57	22	-	-
631+35	15		-	-	21.7	-	-	-	84	22	-	21.7
631+82	6	6	8.7	8.7	-	-	-	-	108	44	-	-
632+89	15		-	-	21.7	-	-	-	84	22	-	21.7
633+59		6	-	8.7	-	-	-	-	57	22	-	-
633+72	6		8.7	-	-	-	-	-	57	22	-	-
633+77		6	-	8.7	-	-	-	-	57	22	-	-
634+60	110	110	-	-	-	-	158.9	158.9	628	44	54	317.8
Total			329.3	332.2	221.0	156.0	274.4	317.8	6873	2134	123	969.2
			662		377		592		6873	2134	123	969

MODEL: Default
 FILE: \\saw.bentley.com\PI\DOT\Documents\DOT_Offices\Burlington\Program_Development\Sturles & Plans\Drawings\CADD\CAD\Drawings\17-64918-18-18-500.dwg

USER NAME = Brad.Cushman	DESIGNED - _____	REVISED - _____
	DRAWN - _____	REVISED - _____
PLOT SCALE = 100.0000' / in.	CHECKED - _____	REVISED - _____
PLOT DATE = Oct-24-2023 01:42:56 PM	DATE - _____	REVISED - _____

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

PATCHING SCHEDULE

SCALE: _____ SHEET ____ OF ____ SHEETS STA. _____ TO STA. _____

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
642	108 RS-3	CARROLL	75	18
CONTRACT NO. 64918				
ILLINOIS FED. AID PROJECT				