CODE NO.	ITEM	UNIT	TOTAL QUANTITY	6-00582-0000 80% FED 20% STATE ROADWAY 0005 RURAL	6-00582-0100 80% FED 20% STATE BRIDGE 0047 085-0004
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1050	1050	
40600990	TEMPORARY RAMP	SQ YD	306	306	
40602965	HOT-MIX ASPHALT BINDER COURSE, IL-9.5FG, N50	TON	5319	5319	
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	3429	3429	
40604050	HOT-MIX ASPHALT SURFACE COURSE, IL-9.5, MIX "C", N50	TON	8669	8669	
40800029	BITUMINOUS MATERIALS (TACK COAT)	POUND	473	473	
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	221	221	
~~42001300~~	~~PROTECTIVE COAT~~	~~SQ YD~~	~~312.3~~		~~312.3~~
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	96318	96318	
44000160	HOT-MIX ASPHALT SURFACE REMOVAL, 2 3/4"	SQ YD	7129	7129	
44000300	CURB REMOVAL	FOOT	622	622	
44000400	GUTTER REMOVAL	FOOT	21326	21326	
44004250	PAVED SHOULDER REMOVAL	SQ YD	425	425	
44200144	PAVEMENT PATCHING, TYPE II, 12 INCH	SQ YD	86	86	
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	1174	1174	

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	6-00582-0000 80% FED 20% STATE ROADWAY 0005 RURAL	6-00582-0100 80% FED 20% STATE BRIDGE 0047 085-0004
48203023	HOT-MIX ASPHALT SHOULDERS, 6 1/2"	SQ YD	1735	1735	
48203100	HOT-MIX ASPHALT SHOULDERS	TON	407	407	
50104400	CONCRETE HEADWALL REMOVAL	EACH	6	6	
50105220	PIPE CULVERT REMOVAL	FOOT	440	440	
50300260	BRIDGE DECK GROOVING	SQ YD	289		289
50300300	PROTECTIVE COAT	SQ YD	312.3		312.3
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	2490		2490
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	213	213	
52000110	PREFORMED JOINT STRIP SEAL	FOOT	45		45
54001001	BOX CULVERT END SECTIONS, CULVERT NO. 1	EACH	2	2	
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	5		5
54001002	BOX CULVERT END SECTIONS, CULVERT NO. 2	EACH	2	2	
52100520	ANCHOR BOLTS, 1"	EACH	30		30
54002020	EXPANSION BOLTS 3/4 INCH	EACH	16	16	
542A0217	PIPE CULVERTS, CLASS A, TYPE 1 12"	FOOT	85	85	
542A0223	PIPE CULVERTS, CLASS A, TYPE 1 18"	FOOT	171	171	
542A0229	PIPE CULVERTS, CLASS A, TYPE 1 24"	FOOT	98	98	
542A0241	PIPE CULVERTS, CLASS A, TYPE 1 36"	FOOT	118	118	

1 REVISED 10-30-2023

REV. - MS

MODEL: Default
FILE NAME: pw:\\ildot-pw.bentley.com:PWIDOT\Documents\IDOT Offices\District 6\Projects\D672F14\CADData\CADsheets\D672F14-sht-SOQ.dgn

USER NAME = andrew.cisler	DESIGNED -	REVISED -	
	DRAWN -	REVISED -	
PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED -	
PLOT DATE = 8/25/2023	DATE -	REVISED -	

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: | SHEET 2 OF 5 SHEETS | STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
612	101RS-9,BDR1,BP; 102RS-5	SCHUYLER	225	4

CONTRACT NO. 72F14

ILLINOIS | FED. AID PROJECT