

## SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				ROADWAY	SAFETY
				0004 URBAN	0021 URBAN
				URBAN 80% FED 20% STATE	
* 78009024	MODIFIED URETHANE PAVEMENT MARKING - LINE 24"	FOOT	192	192	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	109	109	
* 78200020	CURB REFLECTORS	EACH	165	165	
* 80400100	ELECTRICAL SERVICE INSTALLATION	EACH	1	1	
* 81028320	UNDERGROUND CONDUIT, PVC, 1" DIA.	FOOT	38	38	
* 81028330	UNDERGROUND CONDUIT, PVC, 1 1/4" DIA.	FOOT	22	22	
* 81028340	UNDERGROUND CONDUIT, PVC, 1 1/2" DIA.	FOOT	313	313	
* 81028350	UNDERGROUND CONDUIT, PVC, 2" DIA.	FOOT	334	334	
* 81028360	UNDERGROUND CONDUIT, PVC, 2 1/2" DIA.	FOOT	76	76	
* 81028370	UNDERGROUND CONDUIT, PVC, 3" DIA.	FOOT	95	95	
* 81400700	HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	9	9	
* 81400720	DOUBLE HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	1	1	
* 85704804	FULL-ACTUATED CONTROLLER, STANDARD SEQUENCE IV, 8 PHASES, IN TYPE IV CABINET	EACH	1	1	
* 87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	949.5	949.5	
* 87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	975.5	975.5	



\* SPECIALTY ITEM

△ REVISED 11-7-2023

MODEL: Default  
 FILE NAME: X:\Projects\Current\192-2330 IDOT Dist. 8 W/O I.L. 3 20th St. Intersection Improvements\Drawings\87643-ah-500.dgn

**HURST-ROSCHÉ, INC.**  
 HILLSBORO, ILLINOIS 62049  
 PHONE (217) 532-3959  
 HR # 192-2330  
 www.hurst-rosche.com

USER NAME = mamidon	DESIGNED - SMS	REVISED -
PLOT SCALE = 10.0000' / in.	DRAWN - BP	REVISED -
PLOT DATE = 12/9/2022	CHECKED - JJC	REVISED -
	DATE - 12/09/2022	REVISED -

**STATE OF ILLINOIS**  
**DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES**  
**IL RTE 3 GRANITE CITY**

SCALE: NONE    SHEET 5 OF 8 SHEETS    STA.    TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2	103R-1	MADISON	84	7
			CONTRACT NO. 76N43	
ILLINOIS FED. AID PROJECT				